

**FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL HARDWARE****NUMBER:03-1-0145 -X****SUBSYSTEM NAME:** MAIN PROPULSION**REVISION:** 3 07/25/00**PART DATA**

	<b>PART NAME</b>	<b>PART NUMBER</b>
	<b>VENDOR NAME</b>	<b>VENDOR NUMBER</b>
LRU	:HIGH PRESSURE GHE FILTER WINTEC	ME286-0056-0001 24228-626

**EXTENDED DESCRIPTION OF PART UNDER ANALYSIS:**

FILTER (FL5), HIGH PRESSURE HELIUM, PNEUMATIC HELIUM SUPPLY SYSTEM (0.375 INCH DIA).

**REFERENCE DESIGNATORS:** FL5**QUANTITY OF LIKE ITEMS:** 1**FUNCTION:**

THE FILTER TRAPS CONTAMINATION THAT MAY BE PRESENT IN HELIUM FROM THE GROUND SUPPORT EQUIPMENT SUPPLY AND/OR THE PNEUMATIC HELIUM TANK PRIOR TO FLOW THROUGH THE ISOLATION SOLENOID VALVES (LV7,8) AND INTO THE PNEUMATIC SUPPLY DISTRIBUTION SYSTEM.

**FAILURE MODES EFFECTS ANALYSIS FMEA -- CIL FAILURE MODE**

**NUMBER: 03-1-0145-02**

**REVISION#: 2 07/25/00**

**SUBSYSTEM NAME: MAIN PROPULSION**

**LRU: GHE FILTER**

**ITEM NAME: MPS PNEU GHE SUPPLY FILTER (FL5)**

**CRITICALITY OF THIS**

**FAILURE MODE: 1/1**

---

**FAILURE MODE:**

RUPTURE/LEAKAGE

**MISSION PHASE:**

PL PRE-LAUNCH  
LO LIFT-OFF  
DO DE-ORBIT

**VEHICLE/PAYLOAD/KIT EFFECTIVITY:**

102 COLUMBIA  
103 DISCOVERY  
104 ATLANTIS  
105 ENDEAVOUR

**CAUSE:**

MATERIAL DEFECT, FATIGUE, INTERFACE SEAL DAMAGE.

**CRITICALITY 1/1 DURING INTACT ABORT ONLY? NO**

---

**REDUNDANCY SCREEN**

A) N/A  
B) N/A  
C) N/A

**PASS/FAIL RATIONALE:**

A)

B)

C)

---

**- FAILURE EFFECTS -**

---

**(A) SUBSYSTEM:**

DURING ASCENT, THE PNEUMATIC HELIUM SUPPLY WILL BE LOST. ESCAPING HELIUM MAY OVERPRESSURIZE THE AFT COMPARTMENT.

WHEN THE CROSSOVER VALVE (LV10) OPENS AT MECO, THE PNEUMATIC HELIUM DISTRIBUTION SYSTEM WILL BE FED FROM THE LEFT ENGINE HELIUM SUPPLY. WHEN THE

**FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL FAILURE MODE  
NUMBER: 03-1-0145-02**

ENGINE 1 AND 3 INTERCONNECT "OUT" VALVES OPEN AT MECO PLUS 20 SECONDS, THE ENGINE 1 AND 3 HELIUM SUPPLIES WILL LEAK THROUGH THE FAILED LINE.

STORED HELIUM PRESSURE IN THE ACCUMULATOR LEG AND SUPPLEMENTAL HELIUM FROM LV10 SHOULD BE ADEQUATE TO OPERATE THE LO2 PREVALVES AT MECO. LOSS OF HELIUM MAY PREVENT OPERATION OF VALVES FOR MPS DUMP.

PURGE OF AFT COMPARTMENT AND LH2/LO2 SYSTEMS WOULD DEPEND SOLELY ON THE LEFT ENGINE HELIUM SYSTEM RESIDUALS, RESULTING IN INADEQUATE ABORT PURGE, INCOMPLETE PROPELLANT DUMP, AND INGESTION OF CONTAMINATION.

DURING ENTRY, VENT DOORS ARE CLOSED TO PREVENT INGESTION OF RCS AND APU GASES. RUPTURE DURING THE TIME PERIOD THAT THE VENT DOORS ARE CLOSED MAY RESULT IN OVERPRESSURIZATION OF AFT COMPARTMENT. VENT DOORS ARE OPENED WHEN VEHICLE VELOCITY DROPS BELOW 2400 FT/SEC.

PRIOR TO LIFTOFF, EXCESSIVE HELIUM LEAKAGE MAY BE DETECTABLE USING HAZARDOUS GAS DETECTION SYSTEM (HGDS).

**(B) INTERFACING SUBSYSTEM(S):**

SAME AS A.

**(C) MISSION:**

ON GROUND, POSSIBLE LAUNCH SCRUB DUE TO LCC VIOLATION.

**(D) CREW, VEHICLE, AND ELEMENT(S):**

POSSIBLE LOSS OF CREW/VEHICLE.

**(E) FUNCTIONAL CRITICALITY EFFECTS:**

NONE.

---

**-DISPOSITION RATIONALE-**

---

**(A) DESIGN:**

THE FILTER IS A 25 MICRON ABSOLUTE "OFF-THE-SHELF" ITEM. ITS ELEMENT IS OF ALL STAINLESS STEEL WELDED CONSTRUCTION. IT CONSISTS OF A PLEATED TWILLED DOUBLE DUTCH WIRE ELEMENT, A SUPPORT TUBE, AN END CAP, A FITTING AND TWO TEFLON O-RINGS.

THE MATERIALS USED IN THE DESIGN AND FABRICATION OF THE HELIUM FILTER ASSEMBLY ARE THE HEAD (304L), SUMP AND TWO TUBES (21-6-9 CRES). THERE HAS BEEN NO FAILURE HISTORY FOR THE MATERIALS USED IN ENVIRONMENTS SIMILAR TO THE REQUIREMENTS OUTLINED IN ME286-0056.

**FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL FAILURE MODE  
NUMBER: 03-1-0145-02**

THE FILTER HAS TWO POTENTIAL LEAK PATHS: THE TUBE/HEAD INTERFACE AND THE SUMP/HEAD INTERFACE. THE TUBES ARE THREADED INTO THE HEAD AND TORQUED TO 25 FT-LBS BEFORE BEING TIG WELDED TO THE HEAD. THE SUMP/HEAD INTERFACE IS DOUBLE SEALED. ITS PRIMARY SEAL IS A LEAD- COATED, A286 CRES K-SEAL. THE SECONDARY SEAL IS A TEFLON O-RING.

THE FILTER ASSEMBLY IS PROOF PRESSURE TESTED AT TWO TIMES ITS OPERATING PRESSURE DURING ATP AND CERTIFICATION TESTING. IT WAS BURST PRESSURE TESTED AT FOUR TIMES ITS OPERATING PRESSURE DURING CERTIFICATION TESTING.

**(B) TEST:**

ATP

EXAMINATION OF PRODUCT

BUBBLE POINT TEST (GREATER THAN 8.28 INCHES WATER)

PROOF PRESSURE TEST (9000 PSIG)

LEAKAGE (0 TO 4500 PSIG)

CLEANLINESS (100A)

CERTIFICATION

RANDOM VIBRATION (DRY AND UNPRESSURIZED)

14 MINUTES IN X AND Y AXIS, 20 TO 2000 HZ, 22.3 GRMS

34 MINUTES IN X AND Y AXIS, 20 TO 2000 HZ, 20.2 GRMS

TRANSIENT VIBRATION (DRY AND UNPRESSURIZED)

IN X AND Y AXIS, 5 TO 35 HZ +/- 0.25 G PEAK

FLOW CAPACITY (464 SCFM (0.08 LBS/SEC) GHE AT 970 PSIG, +70 DEG F)

CLEAN FLOW (20 PSID MAX)

2 GRAMS OF AC COARSE DUST (20 PSID MAX)

ELEMENT BUBBLE POINT TEST (GREATER THAN 8.28 INCH WATER)

PROOF PRESSURE TEST (9000 PSIG)

EXTERNAL LEAKAGE (4500 PSIG)

AMBIENT (+70 DEG F)

LOW TEMP (-160 TO -200 DEG F)

HIGH TEMP (+160 DEG F)

LEAKAGE/THERMAL (970 PSIG)

+100 TO +350 TO +150 DEG F (1X10<sup>-4</sup> SCC/SEC MAX LEAK RATE DURING CYCLE) LEAKAGE

CHECKED CONTINUOUSLY

ELEMENT PRESSURE

**FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL FAILURE MODE  
NUMBER: 03-1-0145-02**

PLUG FILTER ELEMENT WITH A SLURRY OF AC COARSE DUST  
PRESSURIZED TO 1125 PSID  
CLEAN ELEMENT  
ELEMENT BUBBLE POINT TEST

LIFE AND ENVIRONMENT REQUIREMENTS DEMONSTRATED BY ANALYSIS

BURST PRESSURE TEST (18,200 PSIG)

GROUND TURNAROUND TEST  
ANY TURNAROUND CHECKOUT IS ACCOMPLISHED IN ACCORDANCE WITH OMRSD.

**(C) INSPECTION:**

RECEIVING INSPECTION  
INSPECTION OF ALL CRITICAL DIMENSIONS. INCOMING MATERIALS ARE VERIFIED BY  
INSPECTION FOR MATERIAL AND PROCESS CERTIFICATION.

CONTAMINATION CONTROL  
FILTERS ARE MAINTAINED TO CLEANLINESS LEVEL 100A. AFTER BUBBLE POINT TEST AND  
PRIOR TO PACKAGING, FILTERS ARE DRIED IN VACUUM OVEN.

ASSEMBLY/INSTALLATION  
SURFACE FINISHES ARE VERIFIED ON FILTER COMPONENTS SUCH AS END CAP, FITTING,  
SUMP, AND TUBE. INSPECTION VERIFIES TORQUE APPLICATION TO SUMP IS IN  
ACCORDANCE WITH REQUIREMENT. LUBRICATION OF SUMP THREADS AND IDENTIFICATION  
MARKINGS ARE VERIFIED BY INSPECTION.

CRITICAL PROCESSES  
PART PASSIVATION IS VERIFIED ON FILTER COMPONENTS SUCH AS TUBE, SUMP, END CAP  
AND FITTING BY INSPECTION. TIG WELDS OF END CAP TO THE ELEMENT ASSEMBLY ARE  
VERIFIED BY INSPECTION. FILTER MARKING PROCESS BY CHEM-ETCH IS VERIFIED BY  
INSPECTION.

NONDESTRUCTIVE EVALUATION  
HELIUM LEAK DETECTION IS CONDUCTED TO DETECT ANY POSSIBLE LEAKAGE IN THE  
ASSEMBLY.

TESTING  
ATP IS VERIFIED BY INSPECTION.

HANDLING/PACKAGING  
EACH FILTER OR FILTER ELEMENT END ITEM AND ITS SUPPORTING DOCUMENTATION ARE  
VISUALLY CHECKED PRIOR TO SHIPMENT. FILTERS ARE FIRST PRE-PACKAGED TO ASSURE  
MAINTENANCE OF CLEANLINESS LEVEL. PACKAGING MATERIALS AND METHODS ARE  
UTILIZED IN ACCORDANCE WITH REQUIREMENTS.

**(D) FAILURE HISTORY:**

SEVERAL CASES OF EXTERNAL LEAKAGE WERE NOTED DURING CHECKOUT AT THE  
VENDOR (CAR'S A5560 AND A5561). A TEFLON COATED SEAL LEAKED DUE TO BODY

**FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL FAILURE MODE  
NUMBER: 03-1-0145-02**

INTERFERENCE DURING ASSEMBLY. THE TEFLON COATED SEAL WAS REPLACED WITH A GOLD PLATED, HARRISON K-SEAL.

DURING PROOF PRESSURE TESTING OF THE HELIUM PANEL AT DOWNEY, THE REQUIRED PRESSURE OF 4400 PSIG COULD NOT BE OBTAINED DUE TO EXTERNAL LEAKAGE OF THE FILTER (REFERENCE CAR AB8915). FAILURE ANALYSIS SHOWED THAT THE TEFLON "O" RING SEAL IN THE HEAD ASSEMBLY WAS SHEARED OFF. THE "O" RING GROOVE WAS 0.052 INCH UNDERSIZE ON THE DIAMETER CAUSING THE "O" RING TO PROTRUDE OUT OF THE GROOVE 0.026 INCH. WHEN THE SUMP WAS INSERTED INTO THE HEAD ASSEMBLY AND TIGHTENED, THE "O" RING WAS SHEARED. THE HEAD ASSEMBLY IS MACHINED BY AN OUTSIDE VENDOR. CORRECTIVE ACTION WAS TO INSTITUTE 100% DIMENSIONAL INSPECTION DURING RECEIVING.

CURRENT DATA ON TEST FAILURE, FLIGHT FAILURE, UNEXPLAINED ANOMALIES, AND OTHER FAILURES EXPERIENCED DURING GROUND PROCESSING ACTIVITY CAN BE FOUND IN THE PRACA DATABASE.

**(E) OPERATIONAL USE:**

PNEUMATIC TANK, REGULATOR, AND ACCUMULATOR PRESSURE ARE ON S/M ALERT FDA SYSTEM AND THE BFS SYSTEM SUMMARY DISPLAY. THIS ALLOWS THE FLIGHT CREW TO RESPOND TO A PNEUMATIC HELIUM SYSTEM LEAK INDEPENDENT OF GROUND CONTROL.

---

**- APPROVALS -**

---

S&R ENGINEERING	: W.P. MUSTY	:/S/ W. P. MUSTY
S&R ENGINEERING ITM	: P. A. STENGER-NGUYEN	:/S/ P. A. STENGER-NGUYEN
DESIGN ENGINEERING	: CHARLES EBERHART	:/S/ CHARLES EBERHART
MPS SUBSYSTEM MGR.	: TIM REITH	:/S/ TIM REITH
MOD	: JEFF MUSLER	:/S/ JEFF MUSLER
USA SAM	: MIKE SNYDER	:/S/ MIKE SNYDER
USA ORBITER ELEMENT	: SUZANNE LITTLE	:/S/ SUZANNE LITTLE
NASA SR&QA	: BILL PRINCE	:/S/ BILL PRINCE