

FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL HARDWARE**NUMBER: 03-1-0726 -X****SUBSYSTEM NAME:** MAIN PROPULSION**REVISION:** 1 02/20/01

PART DATA

	PART NAME	PART NUMBER
	VENDOR NAME	VENDOR NUMBER
LRU	: TRANSDUCER, LO2 TEMPERATURE RDF	ME449-0013-0020 21034

EXTENDED DESCRIPTION OF PART UNDER ANALYSIS:

TRANSDUCER, LO2 ENGINE INLET TEMPERATURE.

REFERENCE DESIGNATORS: V41T1131C
V41T1231C
V41T1331C

QUANTITY OF LIKE ITEMS: 3
ONE PER ENGINE

FUNCTION:

MEASURES TEMPERATURE OF THE LO2 AT EACH OF THE SSME INLET FEEDLINES. THE DATA IS USED FOR MONITORING OF PROPER LO2 THERMAL CONDITIONING PRIOR TO SSME START AND POST FLIGHT DATA ANALYSIS.

FAILURE MODES EFFECTS ANALYSIS FMEA -- CIL FAILURE MODE

NUMBER: 03-1-0726-02

REVISION#: 1 10/30/01

SUBSYSTEM NAME: MAIN PROPULSION

LRU: LO2 SSME INLET TEMPERATURE TRANSDUCER

CRITICALITY OF THIS

ITEM NAME: LO2 SSME INLET TEMPERATURE TRANSDUCER

FAILURE MODE: 1/1

FAILURE MODE:

RUPTURE/LEAKAGE

MISSION PHASE:

PL PRE-LAUNCH

LO LIFT-OFF

VEHICLE/PAYLOAD/KIT EFFECTIVITY:

102 COLUMBIA

103 DISCOVERY

104 ATLANTIS

105 ENDEAVOUR

CAUSE:

FATIGUE, MATERIAL DEFECTS

CRITICALITY 1/1 DURING INTACT ABORT ONLY? NO

REDUNDANCY SCREEN

A) N/A

B) N/A

C) N/A

PASS/FAIL RATIONALE:

A)

B)

C)

- FAILURE EFFECTS -

(A) SUBSYSTEM:

LO2 LEAKAGE INTO THE AFT COMPARTMENT. GN2 PURGE OF THE AFT COMPARTMENT MAY LOWER THE GO2 CONCENTRATION. POSSIBLE OVERPRESSURIZATION OF THE AFT COMPARTMENT. POSSIBLE LOSS OF ADJACENT CRITICAL FUNCTIONS DUE TO CRYO EXPOSURE. LEAKAGE DETECTABLE ON GROUND USING HAZARDOUS GAS DETECTION SYSTEM (HGDS).

**FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL FAILURE MODE
NUMBER: 03-1-0726-02**

ALSO RESULTS IN POSSIBLE LOSS OF HELIUM SUPPLY DURING MANIFOLD REPRESSURIZATION CAUSING LOSS OF AFT COMPARTMENT PURGE.

(B) INTERFACING SUBSYSTEM(S):
SAME AS A.

(C) MISSION:
ON GROUND, VIOLATION OF HGDS LCC WILL RESULT IN LAUNCH SCRUB.

(D) CREW, VEHICLE, AND ELEMENT(S):
POSSIBLE LOSS OF CREW/VEHICLE.

(E) FUNCTIONAL CRITICALITY EFFECTS:
NONE

-DISPOSITION RATIONALE-

(A) DESIGN:
THE TRANSDUCER IS HERMETICALLY SEALED AND IS DESIGNED AND CONSTRUCTED TO WITHSTAND THE STATIC AND DYNAMIC LOADS IMPOSED BY OPERATIONAL SERVICE AND ALL OTHER HANDLING ASPECTS. THE PROBE IS CYLINDRICAL CONSISTING OF A ONE PIECE HEX NUT AND THREADED SECTION WHICH IS TUNGSTEN-INERT GAS (TIG) WELDED TO AN EXTENDED MANDREL. THE PROBE FROM THE SEALING SURFACE TO THE TIP IS 4.0 INCHES IN LENGTH. THE SENSING WIRE AND MANDREL IS CONTAINED WITHIN AN OUTER STAINLESS STEEL SHEATH THAT IS TIG WELDED TO THE THREADED PART AND ALSO AT THE TIP OF THE MANDREL. THE STRUCTURE IS ALL STAINLESS STEEL. THE PROBE IS DESIGNED AND CONSTRUCTED TO WITHSTAND 3,000 PSIA WITHOUT ANY STRUCTURAL FAILURE.

(B) TEST:
ATP

EXAMINATION OF PRODUCT

LEAKAGE TEST

LEAK TESTING PRECLUDES LEAKAGE GREATER THAN 1×10^{-6} SCC/SEC.

INSULATION RESISTANCE TEST

USING 100 VOLTS DC AND AN ELECTRIFICATION TIME OF 2 MINUTES BEFORE MEASUREMENT THE RESISTANCE SHALL BE LESS THAN 50 MEGOHMS WHEN MEASURED BETWEEN INSULATED TERMINALS AND BETWEEN THE TERMINAL AND THE CASE.

**FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL FAILURE MODE
NUMBER: 03-1-0726-02**

CALIBRATION

CALIBRATED AT 5 POINTS (-450, -410, -320, +32, AND +212 DEG F)

CERTIFICATION

CALIBRATION

CALIBRATED AT 5 POINTS (-450, -410, -320, +32, AND +212 DEG F)

THERMAL SHOCK

10 CYCLES FROM +75 TO -320 DEG F

RANDOM VIBRATION AND LOW TEMPERATURE TEST:

13.3 HOURS OF RANDOM VIBRATION AT -320 DEG F IN EACH OF THE 2 AXES.

BURST PRESSURE TESTING

NO LEAKAGE SHALL OCCUR WHEN SUBJECTED TO 3000 PSI.

OMRSD

ANY TURNAROUND CHECKOUT IS ACCOMPLISHED IN ACCORDANCE WITH OMRSD.

(C) INSPECTION:

RECEIVING INSPECTION

RECEIVING INSPECTION PERFORMS VISUAL AND DIMENSIONAL EXAMINATION OF ALL INCOMING PARTS. CERTIFICATION RECORDS/TEST REPORTS ARE MAINTAINED CERTIFYING MATERIALS AND PHYSICAL PROPERTIES.

CONTAMINATION CONTROL

CLEANLINESS LEVEL 400A IS MAINTAINED AND VERIFIED IN ACCORDANCE WITH APPLICABLE REQUIREMENT.

ASSEMBLY/INSTALLATION

MANDATORY INSPECTION POINTS ARE INCLUDED IN MANUFACTURING PROCESS. TOOL CALIBRATION IS VERIFIED TO THE REQUIREMENT. PARTS ARE INSPECTED VISUALLY, DIMENSIONALLY, AND INCREMENTALLY IN ACCORDANCE WITH SPECIFICATION.

CRITICAL PROCESSES

DRY FILM LUBRICANT APPLIED TO THREADS IS VERIFIED PER DRAWING SPECIFICATION. TIG WELDING IS VERIFIED BY INSPECTION AND LEAK CHECK.

NONDESTRUCTIVE EVALUATION

HELIUM LEAK TEST IS VERIFIED BY INSPECTION. RADIOGRAPHIC INSPECTION IS CONDUCTED TO VERIFY THE EXISTENCE OF STRAIN RELIEF ON THE WINDING ELEMENT AND TO DETECT METALLIC CONTAMINATION IN THE HOUSING WHERE THE CONNECTOR IS WELDED.

TESTING

ATP AND PROOF PRESSURE TESTS ARE OBSERVED AND VERIFIED BY INSPECTION.

HANDLING/PACKAGING

**FAILURE MODES EFFECTS ANALYSIS (FMEA) -- CIL FAILURE MODE
NUMBER: 03-1-0726-02**

PACKAGING AND PROTECTION ARE VERIFIED BY INSPECTION TO APPLICABLE REQUIREMENTS. SPECIAL HANDLING PER DOCUMENTED INSTRUCTIONS IS VERIFIED TO PRECLUDE DAMAGE, SHOCK, AND CONTAMINATION DURING COMPONENT HANDLING/TRANSPORTING/ PACKAGING BETWEEN WORK STATIONS.

(D) FAILURE HISTORY:

CURRENT DATA ON TEST FAILURE, FLIGHT FAILURE, UNEXPLAINED ANOMALIES, AND OTHER FAILURES EXPERIENCED DURING GROUND PROCESSING ACTIVITY CAN BE FOUND IN THE PRACA DATABASE.

(E) OPERATIONAL USE:

FLIGHT: NO CREW ACTION CAN BE TAKEN.

GROUND: GROUND OPERATIONS SAFING PROCEDURES CONTAIN SAFING SEQUENCE OF EVENTS FOR MAJOR LEAKS IN THE OXYGEN SYSTEM.

- APPROVALS -

S&R ENGINEERING	: L. DANG	:/S/ L. DANG
S&R ENGINEERING ITM	: P. A. STENGER-NGUYEN	:/S/ P. A. STENGER-NGUYEN
DESIGN ENGINEERING	: HERB WOLFSON	:/S/ HERB WOLFSON
MPS SUBSYSTEM MGR.	: TIM REITH	:/S/ TIM REITH
INSTRUMENTATION	: BILL MCKEE	:/S/ BILL MCKEE
MOD	: JEFF MUSLER	:/S/ JEFF MUSLER
USA SAM	: MIKE SNYDER	:/S/ MIKE SNYDER
USA ORBITER ELEMENT	: SUZANNE LITTLE	:/S/ SUZANNE LITTLE
NASA SR&QA	: ERICH BASS	:/S/ ERICH BASS