

SAA09FY12-005  
REV. B

MAR 11 1994  
B/L: 389.00  
SYS: 250-TON  
BRIDGE  
CRANE, VAB

Critical Item: Potentiometer, Bridge (2 Total, 1/Crane)  
Find Number: RPOT  
Criticality Category: 2

SAA No: 09FY12-005

System/Area: 250-Ton Bridge Crane  
(#1 & #2)/VAB

NASA  
Part No: NA

PMN/  
Name: K60-0533, K60-0534/  
250-Ton Bridge Crane  
(#1 & #2)/VAB

Mfg/  
Part No: Ohmite/  
RHS750

Drawing/  
Sheet No: 69-K-L-11388/  
24

Function: Reference potentiometer connected to the master control switch (joystick), 3MC, to regulate the input excitation voltage to the generator field DC input controller, 3FC, and the resulting output to the generator field winding for bridge speed control during operations.

Critical Failure Mode/Failure Mode No: Fails Open/09FY12-005.096

Failure Cause: Corrosion, fatigue.

Failure Effect: If the failure occurs on the resistive element, it would result in a loss of the parallel resistance branch will create a larger input into the DC generator field controller which will cause an increasing speed of the DC motors controlling the bridge. The worst case scenario would be moving a critical load (SRB segment, Orbiter, or ET) in the slow coarse speed mode (maximum coarse speed is 75 ft/min), the failure occurring, causing a sudden increase to full coarse speed and the effect being the critical load striking a VAB wall or work platform resulting in possible damage to a vehicle system. Time to effect: seconds.

#### ACCEPTANCE RATIONALE

Design:

Rated Power  
25 watts

Actual Power  
.18 watts

Rated Voltage  
300 volts

Actual Voltage  
12 volts

Rated Current  
.176 amps

Actual Current  
.015 amps

Attachment  
S050234CK  
Sheet 116 of 147

MAR 11 1994

- **Material:**
  - **Body:** Ceramic
  - **Windings:** High grade resistance alloy
  - **Coating:** Vitreous enamel
  - **Contact Arm:** Metal graphite composition
  - **Terminals:** Solder coated
- **Resistance tolerance:** =/- 10 %

**Test:**

- OMRSD file VI requires verification of proper performance of the bridge operational test annually.
- OMI Q3008, Operating Instructions, requires all crane systems to be operated briefly in all speeds to verify satisfactory operation before lifting operations.

**Inspection:**

- This item is not readily accessible for inspection. OMI Q6003, Maintenance Instructions, instructs that inspections shall not entail any disassembly of equipment.

**Failure History:**

- The PRACA database was researched and no failure data was found on this component in the critical failure mode.
- The GIDEP failure data interchange system was researched and no failure data was found on this component in the critical failure mode.

**Operational Use:**

- **Correcting Action:**
  - 1) The failure can be recognized via the ammeter (increase in current) and the Selsyn (positions change) that is in view of both operators.
  - 2) When the failure indication is noticed, the operator can stop all crane operations by pressing the E-Stop button or returning the Master Control Switch to neutral.
  - 3) When the failure occurs in the fine speed mode of operation, the motor generator set will be shut down by an overvoltage protection relay when the voltage in the DC motor loop reaches 115% of the full fine voltage output.
  - 4) Operators are trained and certified to operate these cranes and know and understand what to do if a failure indication is present.
  - 5) During all critical lifts, there is at least one remote Emergency Stop (E-Stop) operator observing the load lift and can stop the crane if a failure indication is noticed.
  - 6) Operationally, the crane must be operated in the fine speed mode if a critical load is within 10 feet of any structure in the direction of travel.

MAR 11 1994

- Timeframe:
  - Estimated operator reaction time is 3 to 10 seconds.