

CIL
CRITICAL ITEMS LIST
FILE: CILS/1

NAME P/N QTY	CNT	FAILURE MODE & CAUSES	FAILURE EFFECT	RATIONALE FOR ACCEPTANCE
VOLUME CONTROL E1H 540 SV767704-1 (1)	2/2	688707: ELECTRICAL SHORT IN LOWER VOLUME CONTROL. CAUSE: INTERNALLY GENERATED DEBRIS.	END ITEM: INCREASE IN VOLUME. RISKLOW OF INCREASE DEPENDENT ON LOCATION OF SHORT. GPE INTERFACE: LOSS OF USE OF BOTH OF THE REDUNDANT COMMUNICATION R.F. SETS. 254.7 AND 279.0 FREQUENCIES. MISSION: TERMINATE EVA. CREW/VEHICLE: NONE.	A. DESIGN - THE WIPER/RESISTIVE ELEMENT ASSEMBLIES ARE ENGAGED WITHIN AN ENVIRONMENTALLY SEALED HOUSING. THE SEALS AROUND THE CONCENTRIC SHIFTS ARE PROVIDED BY DUAL O-SEALS. THE SEAL AT THE BACK OF THE ITEM IS PROVIDED BY PUTTING AROUND THE SOLDER TERMINALS. THIS ARRANGEMENT PREVENTS CONTAMINATION FROM ENTERING THE CASING AND CAUSING EXCESSIVE WEAR OR CORROSION. THE EXTERNAL WIRES USED ARE #22 AWG PER M22759/10 (TEFLON). THE SOLDERING IS PER AM5500.4 (3A-1) AND THEN PUT IN TO PROVIDE STRAIN RELIEF. THE WIRE BUNDLE IS DESIGNED TO WITHSTAND A PULL FORCE OF 5 LBS. WITHOUT DEGRADATION. B. TEST - COMPONENT ACCEPTANCE TEST - VECTOR TESTS INCLUDE RESISTANCE, OPERATING TORQUE, FUNCTIONAL, DIELECTRIC WITHSTANDING, AND INSULATION RESISTANCE TESTS. IN-PROCESS TEST - ITEM OPERATION AND RESISTANCE IS VERIFIED DURING ELECTRICAL TESTS PERFORMED DURING DCN ASSEMBLY. PDA TEST - ITEM OPERATION IS VERIFIED DURING DCN PDA PER 359U-40-015. TESTS INCLUDE VIBRATION, THERMAL CYCLES TESTS FOLLOWED BY ELECTRICAL TESTING, AND OPERATION TORQUE. CERTIFICATION TEST - THE ITEM COMPLETED THE 25 YEAR STRUCTURAL VIBRATION AND SHOCK CERTIFICATION DURING 10/01 AND FOUR HOUR THERMAL VACUUM CERTIFICATION DURING 2/02, BOTH AS PART OF THE DCN. THE ITEM IS CYCLE CERTIFIED BY SIMILARITY TO THE DYNAMIC/IC POP WHICH WAS CERTIFIED DURING THE SKYLARK PROGRAM. THE DYNAMIC/IC PART COMPLETED 5,000 CYCLES WHICH IS 2.5 TIMES THE CERTIFICATION REQUIREMENT OF 1537 CYCLES FOR THIS ITEM. NO CLASS 2 ENGINEERING CHANGES HAVE BEEN INCORPORATED SINCE THIS CONFIGURATION WAS TESTED.

CIL
CRITICAL ITEMS LIST
FILE: CIL5/1

NAME P/N QTY	CRIT	FAILURE MODE & CAUSES	FAILURE EFFECT	RATIONALE FOR ACCEPTANCE
VOLUME CONTROL ITEM 340 SV267784-1 111	2/2	368TH071 ELECTRICAL SWITCH 14 LOWER VOLUME CONTROL.		<p>B. TEST (CONTINUED) - CHECKOUT TEST - VOLUME CONTROL OPERATION IS VERIFIED DURING PIA PER PEMU-R-001, PARA. 4.10, SEMI COMMUNICATION AND BICRO CHECK.</p> <p>C. INSPECTION - THE LEAD WIRES ARE INSPECTED DURING SOURCE INSPECTION OF THE PART, AND AGAIN DURING DCN ASSEMBLY FOR DAMAGE AND HEAR TO THE INSULATION. AN OPEN CIRCUIT IS ALSO PRECLUDED VIA INSPECTION OF SOLDERING AT THE SWITCH TERMINALS (PRIOR TO POTTING) PER WMS300.4 (SA-1). ALL SWITCH LEAD WIRES APRE PILL TESTED AFTER INSERTION INTO CONNECTORS DURING DCN ASSEMBLY TO INSURE PROPER LOCKING OF THE CRIMP CONTACTS.</p> <p>D. FAILURE HISTORY - NONE.</p> <p>E. GROUND TURNAROUND - VOLUME CONTROL OPERATION IS VERIFIED DURING GROUND SURROUND PER PEMU-R-001, SEMI COMMUNICATION AND BICRO CHECK.</p> <p>F. OPERATIONAL USE - CIRM RESPONSE - PREVA: TROUBLESHOOT PROBLEM, IF NO SUCCESS, CONSIDER THIRD EMO IF AVAILABLE. EMO GO FOR EVA IF VOLUME IS ACCEPTABLE TO EV CREWMEMBER. EVA: EMO GO FOR EVA IF VOLUME IS ACCEPTABLE TO EV CREWMEMBER, OTHERWISE TERMINATE EVA. POSTEVA: BOFF EMO NOMINALLY. SPECIAL TRAINING - NO TRAINING SPECIFICALLY COVERS THIS FAILURE MODE.</p> <p>OPERATIONAL CONSIDERATIONS - EVA CHECKLIST PROCEDURES VERIFY HARDWARE INTEGRITY AND SYSTEMS OPERATIONAL STATUS PRIOR TO EVA. FLIGHT RULES REQUIRE THAT EVA BE TERMINATED IF TWO-WAY COMMUNICATION BETWEEN EACH EV CREWMEMBER AND ORDITER, EITHER DIRECT OR THROUGH RELAY, IS UNAVAILABLE.</p>

0234-2
5