

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

```

*****
*
*           MPS LEAK AND FUNCTIONAL TEST (LPS)           *
*           (GH2 PRESSURIZATION SYSTEM)                   *
*
*****
* EFFECTIVITY                CATEGORY: F                 *
*                               NF-V                       *
* CENTER:      KSC                               *
*                               SYSTEM:  MPS/SSME          *
* SITE:  OPF BAY 1/2/3                               *
* VEHICLE:    ALL                                   *
* FLOW:  ALL                                         *
* DESIGN CENTER CONCURRENCE:  JSC                     *
*****

```

```

*****
* THIS DOCUMENT CONTAINS FUNCTIONAL *
* CRITICALITY 1 AND/OR IR RELATED *
* OPERATIONS.                       *
*****


```

**THIS DOCUMENT DOES NOT
CONTAIN HAZARDOUS OPERATIONS**

NASA

National Aeronautics and
Space Administration

Kennedy Space Center





DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

LOCKHEED SPACE OPERATIONS COMPANY

```

*****
*
*           MPS LEAK AND FUNCTIONAL TEST (LPS)           *
*           (GH2 PRESSURIZATION SYSTEM)                 *
*
*****
* EFFECTIVITY           CATEGORY: F                     *
*                               NF-V                     *
* CENTER:      KSC                                           *
*                               SYSTEM:  MPS/SSME          *
* SITE:  OPF BAY 1/2/3                                       *
* VEHICLE:    ALL                                           *
* FLOW:  ALL                                           *
* DESIGN CENTER CONCURRENCE:  JSC                         *
*****

```

PREPARED BY:

LSOC TEST DOCUMENTATION *3-9-92*

APPROVED BY:

CONTRACTOR

SPC SAFETY ENGINEERING

THIS PROCEDURE DOES NOT CONTAIN HAZARDOUS OPERATIONS

INSTRUCTION CHANGE REQUEST

INSTRUCTION CHANGE REQUEST FOR: () OMI () SW (2) ICR NUMBER 01/LSO-206 (3) SHEET 1 OF 1

(4) OMI/CAP NUMBER V1009.007 (5) REV/EFFECTIVITY BASIC (6) THIS ICR DOES () DOES NOT (X) INCREASE HAZARD LEVEL OF OMI.

(7) SYSTEM LAPS (8) DOCUMENTS AFFECTED? OMP : YES () NO () OMRSD: YES () NO ()

(9) OMI/CAP TITLE LAPS LEAK AND FUNCTIONAL TEST (LPS) (RHZ PRESS SYSTEM)

(10) PAGE	(11) STEP	(12) CHANGE	(13) REASON
		INCORPORATE THE FOLLOWING PERMANENT DEVIATIONS:	1) KSC
		00-01 THRU 00-08, 01-01 THRU 01-03,	2) PREVIOUS
		02-01, 03-01, 03-02, 05-01, 06-01,	DEVIATIONS
		08-01 THRU 08-03, 10-01 THRU 10-03,	3) NONE
		12-01, 13-01, APPA-01, APPB-01,	4) LAST RUN
		APPB-02, APPA-02	5) MANDATORY
			6) NONE
		INCORPORATE RCN 0V10544, DEV'S:	7) N/A
		00-06, 10-03 And RCN 0V10150m	8) USE:

APPENDIX Z AFFECTED? YES NO
Signature: [Signature] 12/20/91

(14) APPROVAL:

CONTRACTOR	DATE	GOVERNMENT	DATE	SAFETY	DATE
	12-6-91		12-20-91		2-13-92
	12-20-91				

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

REVISION RECORD PAGE

REV-CHANGE	DATE	REASON	PAGES AFFECTED	EFFECTIVITY
BASIC	: 10-05-91	: LS0420/00	: ALL	: ALL
A	: 02-25-92	: 01/LS0206	: ALL	: ALL
		: RCN		
		: OV10544		
		: OV10150M		

TABLE OF CONTENTS

PAGE

COVER PAGE
APPROVAL PAGE/CHANGE RECORD PAGE
TABLE OF CONTENTS
OBJECTIVE/DESCRIPTION 1
ILLUSTRATIONS 2
HAZARDOUS MANLOADING NA
BAR CHARTS NA

SECTION I - INFORMATION

1.1 REFERENCED INSTRUCTIONS..... 22
1.2 COMPUTER SYSTEMS..... 27
1.3 SPECIAL TOOLS, EQUIPMENT AND MATERIALS..... 28
1.4 SUPPORT TOOLS, EQUIPMENT AND MATERIALS..... 33
1.5 PERSONNEL REQUIREMENTS..... 34
1.6 SAFETY REQUIREMENTS..... 35
1.7 SPECIAL INSTRUCTIONS..... 36
1.8 OMRS REQUIREMENTS SATISFIED BY THIS TOP..... 48

SECTION II - PRE-OPERATION SETUP INSTRUCTIONS

01-000 PRE-OPERATION SETUPS - ORBITER..... 53
01-001 PRE-OPERATION SETUP 1 - QUALITY SUMMARY SHEET
(CMQC)..... 53
01-004 PRE-OPERATION SETUP 2 - PD16 GH2 SENSE LINE QD
INSTALLATION - OMT0, OQCV, NASA QC..... 55
01-009 PRE-OPERATION SETUP 3 - PD10 GH2 PREPRESS QD
INSTALLATION - OMT0, OQCV, NASA QC..... 57

SECTION III - OPERATION SUPPORT SETUP INSTRUCTIONS

02-000 OPERATION SUPPORT SETUPS - ORBITER..... 63
02-001 OPERATION SUPPORT SETUP 1 - TP10 HANDVALVE
INSTALLATION - OMT0, OQCV, NASA QC..... 63
02-012 OPERATION SUPPORT SETUP 2 - MPS 1-INCH QD LEAK
CHECK TOOL SETUP - OMT0, OQCV..... 69

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

SECTION IV - OPERATION INSTRUCTIONS

03-000	CALL TO STATION.....	71
04-000	GH2 FLOW CONTROL VALVE SIGNATURE TRACE.....	73
05-000	ORBITER GH2 MPS FLOW CONTROL VALVE AUTO CHECKOUT VERIFICATION.....	89
06-000	GH2 PRESSURIZATION SYSTEM DECAY CHECK - CMPS, RMPS, RTH2, OMT0 AND OQCV.....	93
07-000	CV24 REVERSE SEAT LEAK CHECKS.....	105
08-000	PD10 AND CV17 - VALIDATION AND INTERNAL LEAK CHECKS - CMPS, OMT0, OQCV, RTH2.....	111
09-000	GH2 PRESSURIZATION SYSTEM FLANGE LEAK CHECKS..	133
10-000	GH2 PRESSURIZATION SYSTEM LEAK CHECK - CMPS, OMT0, OQCV, AND RTH2.....	137
11-000	CV21, CV22, CV23 INTERNAL LEAK CHECK - CMPS, OMT2, OMT0, OQCV & RTH2.....	145
12-000	LV52 GH2 VENT SOL FLOW PATH VERIFICATION - CMPS, OMT0, RTH2, OQCV, AND NASA QC.....	167
13-000	GH2 PREPRESS SYSTEM PRESSURIZATION (OPF) (CONTINGENCY).....	171
14-000	GH2 PREPRESS SYSTEM VENTING THRU PD16 (OPF) (CONTINGENCY).....	177
15-000	GH2 PREPRESS SYSTEM VENTING THRU PD5/LV52 (OPF) (CONTINGENCY).....	179
16-000	TEST SUPORT TERMINATION.....	183

SECTION V - POST OPERATION INSTRUCTIONS

17-000	POST OPERATION INSTRUCTIONS - ORBITER.....	185
17-001	POST OPERATION INSTRUCTION 1 - MPS GH2 SYSTEM DATA REVIEW.....	185

APPENDICES

A	GH2 SYSTEM COMPONENTS - INTERNAL LK CKS.....	187
	DATA SHEET A-1 - MPS COMPONENT SEAT INTERNAL LEAK CHECKS.....	187
	DATA SHEET A-2 - CHECK VALVE REVERSE LEAKAGE (INTERVAL REQUIREMENTS).....	189
B	DATA SHEET B-1 - GH2 PRESSURIZATION SYSTEM (HIGH PRESSURE) JOINT LIST AND RESULTS.....	191
	DATA SHEET B-2 - GH2 2 IN. LINE GIMBAL JTS - MASS SPEC LEAK CHECK JOINT LIST AND RESULTS..	219
	DATA SHEET B-3 GH2 PRESSURIZATION SYSTEM BUBBLE SOAP LEAK CHECKS JOINT LIST AND RESULTS	223
	DATA SHEET B-4 - GH2 LEAK CHECKS AT ORB/ET DISCONNECT.....	229
C THRU Y	NA
Z	EMERGENCY INSTRUCTIONS	235
18-000	EMERGENCY SHUTDOWN.....	235
19-000	EMERGENCY GH2 PRESSURIZATION SYSTEM VENTING THRU S70-0695-8 PANEL.....	237

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OBJECTIVE

VERIFY MAIN PROPULSION SYSTEM (EXCLUDING SSME) OPERATIONAL
READINESS BY INTERNAL/EXTERNAL LEAK CHECKS, COMPONENT
FUNCTIONAL VERIFICATION AND ELECTRICAL CHECKS IN OPF

DESCRIPTION

1. VISUAL INSPECTION OF MPS.
2. TEST SET UPS.
 - A. PLACARD GSE (S3500, V3502).
 - B. VERIFY/ACTIVATE LPS.
 - C. GSE POWER UP (VAE24).
 - D. PRESSURIZE GSE.
3. GH2 PRESS SYSTEM
 - A. VALVE CYCLING (VAE43).
 - B. EXTERNAL LEAK CHECKS (VAE20) USES HELIUM SUPPLIED BY THE S70-0695-8 PNL.
 - C. FUNCTIONAL AND INTERNAL CHECK TESTS (VAE20) USES HELIUM SUPPLIED BY THE S70-0695-8 PNL.
4. GH2 REPRESS SYSTEM
 - A. EXTERNAL LEAK CHECKS (VAE20) USES HELIUM SUPPLIED BY THE S70-0695-8 PNL.
 - B. FUNCTIONAL AND INTERNAL CHECK TSETS (VAE20) USES HELIUM SUPPLIED BY THE S70-0695-8 PNL.
5. TEST SECURING
 - A. SECURE VEHICLE.
 - B. SECURE GSE (VAE24).




FIGURE 1 - PD5/LV52 INSTALLATION (REF V070-415142)
(FOR REFERENCE ONLY)

V1009.007 Fig 1A





FIGURE 2 - GH2 SYSTEM JOINTS AT LH2/GH2 ORB/ET DISCONNECT
(OV-105 HAS NO DELTA P)
(FOR REFERENCE ONLY)



V1009.007 Fig. 3A

FIGURE 3A - LH2 PNEUMATIC SUPPORT ASSEMBLY
 (FOR REFERENCE ONLY) (OV102,OV103,OV104)
 (REF DWGS V070-415519 AND MLO-720-4152-103)

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A




FIGURE 3B - LH2 PNEUMATIC SUPPORT ASSEMBLY (FOR REFERENCE ONLY)
(OV-105 ONLY) (REF DWGS MLO-720-4150-105)





FIGURE 4 - GH2 PRESSURIZATION SYSTEM BRAZE-LEAK TEST POINTS
(DWG V070-415402) (FOR REFERENCE ONLY)



V1009.007 Fig. 5

FIGURE 5 - GH2 PRESSURIZATION SYSTEM - BRAZE/TEST PORT LEAK TEST POINTS (DWG V070-415402) (FOR REFERENCE ONLY)




FIGURE 6 - GH2 PRESSURIZATION SYSTEM - ORB/SSME I/F LEAK TEST POINTS (DWG V070-415402) (FOR REFERENCE ONLY)




FIGURE 7 - GH2 SYSTEM AT ORB/SSME I/F TEST PORT DETAIL (FOR REFERENCE ONLY)




FIGURE 8 - (0-2) I/F PANEL FOR BAY-1 (MPS DEDICATED TEST FLEXHOSES/QD'S)
(FOR REFERENCE ONLY)




FIGURE 9 - (0-2) I/F PANEL FOR BAY-2 (MPS DEDICATED TEST FLEXHOSES/QD'S)
(FOR REFERENCE ONLY)




FIGURE 10 - (0-2) I/F PANEL FOR BAY-3 (MPS DEDICATED TEST FLEXHOSES/QD'S)
(FOR REFERENCE ONLY)




FIGURE 11 - LH2 T-0 UMBILICAL PANEL - ORBITER LEFT SIDE
(FOR REFERENCE ONLY)




FIGURE 12 - LH2 ORB/ET UMBILICAL ORBITER HALF
(FOR REFERENCE ONLY)




FIGURE 13 - GH2 FCV LEAK TEST POINTS (TOP VIEW)
 (FOR REFERENCE ONLY)




FIGURE 14 - GH2 FCV LEAK TEST POINTS (SIDE VIEW)
(FOR REFERENCE ONLY)

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A





FIGURE 15 - GH2 FLOW CONTROL VALVE COMPONENT JOINTS
(FOR REFERENCE ONLY)



**FIGURE 16 - MPS 1-INCH QD LEAK CHECK TOOL
(FOR REFERENCE ONLY)**




FIGURE 17 - VIEW OF GIMBAL TYPE BELLOWS FOR GH2
PRESSURIZATION SYSTEM
(FOR REFERENCE ONLY)

V1009.007 Fig. 17





FIGURE 18 - GH2 DISCONNECT - JOINTS FPD5, F254, AND F255
(FOR REFERENCE ONLY)



V1009.007 Fig. 1

FIGURE 19 - VIEW OF GIMBAL-TYPE BELLOWS FOR LH2
PRESSURIZATION SYSTEM
(FOR REFERENCE ONLY)

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

SECTION I

1

INFORMATION

1.1 REFERENCED INSTRUCTIONS

1.1.1 DOCUMENTS

<u>NUMBER</u>	<u>REV</u>	<u>TITLE</u>
GP-1098	LI	KSC GROUND OPERATIONS SAFETY PLAN (KSC)
KHB 1710.2	LI	KSC SAFETY PRACTICES HANDBOOK (KSC)
KSC-C-123F	LI	SURFACE CLEANLINESS OF FLUID SYSTEMS, SPECIFICATION FOR CLEANLINESS LEVELS (KSC)
MA0101-301	LI	INSTALLATION OF THREADED FASTENERS (RI)
MA0102-306	LI	FABRICATED AND INSTALLED RIGID AND FLEXIBLE TUBE ASSEMBLIES (RI)
MA0110-311	LI	CONTAMINATION CONTROL DURING MANUFACTURING AND CHECKOUT OF THE ORBITER VEHICLE (RI)
MA0112-303	LI	APPLIED LUBRICANT FOR SPACE VEHICLES (RI)
MF0001-003	LI	PROOF PRESSURE AND LEAK DETECTION AEROSPACE PLUMBING SYSTEMS AND ASSEMBLIES (RI)
MF0004-028	LI	ORBITER TIME/CYCLE CHECKOUT REQUIREMENTS (RI)
80K51846	LI	METAL-REINFORCED FLEXHOSE ASSEMBLY REQUIREMENTS (LSOC)

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

MSFC-SPEC-384	LI	LEAK DETECTION COMPOUND OXYGEN SYSTEMS TYPE I (MSFC)
SE-S-0073	LI	SPACE SHUTTLE FLUID PROCUREMENT AND USE CONTROL (JSC)
S9904	LI	OPF EMERGENCY PROCEDURES DOCUMENT (LSOC)
SP-002(2)KV	LI	TOOL AND HARDWARE TETHERING REQUIREMENTS

1.1.2 DRAWINGS

NUMBER -----	REV ---	TITLE -----
GW70-005800-3	LI	MPS CAP AND PLUG SET (TEST)
GW70-005800-5	LI	MPS CAP AND PLUG SET (FERRY FLIGHT)
GW70-420958	LI	SET - QD FILTER ASSY (S70-0958)
VS70-415001	LI	MAIN PROPULSION SYSTEM - SCHEMATIC (OV-102)
VS70-415004	LI	MPS SCHEMATIC - DFI
V070-415001	LI	MPS INSTALLATION (OV-102)
V070-415003	LI	MPS INSTALLATION (OV-103)
V070-415402	LI	LH2 PRESS SYS INSTL (OV-102)
V070-415413	LI	LH2 PRESS SYS INSTL (OV-103 AND SUBS)
V070-415601	LI	SYSTEM INSTALLATION - PROPELLANT MANAGEMENT
V070-415940	LI	INST INSTL LH PRESS
79K06421	LI	MECH SCHEMATIC - 02 PNL
79K10547	LI	FLEXHOSE ASSY - PNEUMATIC SERVICE - OPF

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.1.3 SUPPORTING SUBTASKS

SUBTASK NUMBER	SUBTASK TITLE/ FUNCTION TO BE PERFORMED	CALLING SEQ-STEP
V1171VL1	MPS/SSME PRESSURIZATION OPERATIONS, OPF (LPS) GH2 PREPRESS VENTING AND SECURING THRU PD16 OPF PD5 GH2 2 IN. ORB ET DISC COVER PLATE INSTALLATION LH2 MANIFOLD VENTING THRU FILL DRAIN LINE OPF	04-001 06-004 06-008
V41-50008	PD5 GH2 2-IN. TEST PLATE, CLEANING/INSPECTION/INSTALLATION	06-024
V1171VL1	MPS/SSME PRESSURIZATION OPERATIONS, OPF (LPS) MPS GH2 PREPRESS SYSTEM SECURING OPF	06-028
V41-40016	PD5 2-IN. TEST PLATE, REMOVAL	06-029
V1171VL1	MPS/SSME PRESSURIZATION OPERATIONS, OPF (LPS) LH2 MANIFOLD VENTING THRU FILL DRAIN LINE OR THRU RTLS DUMP PORT OPF ORBITER MPS 750 PSI PNEUMATIC SYSTEM SECURING AND BLOWDOWN THROUGH BLOWDOWN HOSE LH2 MANIFOLD VENTING THRU FILL DRAIN LINE OPF MPS LH2, LH2 RECIRC, AND GH2 MANIF PRESSURIZATION TO 25 PSIG USING REPRESS REGS LH2 MANIFOLD VENTING THRU FILL DRAIN LINE OR THRU RTLS DUMP PORT OPF ORBITER MPS 750 PSI PNEUMATIC SYSTEM SECURING AND BLOWDOWN THROUGH BLOWDOWN HOSE MPS GH2 PREPRESS SYSTEM SECURING OPF	07-001 07-002 07-009 07-010 07-013 07-014 08-061 09-004
V41-40016	PD5 2-IN. TEST PLATE, REMOVAL	10-005
V41-50008	PD5 GH2 2-IN. TEST PLATE, CLEANING/INSPECTION/INSTALLATION	10-009
V1171VL1	MPS/SSME PRESSURIZATION OPERATIONS, OPF (LPS) MPS GH2 PREPRESS SYSTEM SECURING OPF	10-011 10-013

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

V41-40016	PD5 2-IN. TEST PLATE, REMOVAL	10-014]
		12-001]
V1171VL1	MPS/SSME PRESSURIZATION OPERATIONS, OPF (LPS)]]
	PD16 HARDWARE INSTALLATION OPF	14-002]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.1.4 SUPPORTING SOFTWARE

APP PGM -----	TITLE -----
VAE18	GHE SYS DISPLAY/CONTROL/EM
VAE20	LH2 SYS DISPLAY/CONTROL/EM
VAE24	PNEU CONSOLES POWER UP/POWER DOWN OPF
VAE43	LOX/LH2 PREPRESS FLOW CONTROL C/O
VDE01	MPS GHE SYS DISPLAY SKEL OPF
VDE20	LH2 SYS DISPLAY
VDE41	LH2 SYS SOLENOID C/O MENU

THE FOLLOWING PROGRAMS MAY BE REQUIRED FOR CONTINGENCY

PURPOSES

SAE12	MPS LH2 PROPELLANT MONITOR
SDE07	MPS LO2 ANALOG STATUS
SDE11	MPS LH2 SYSTEM VALVE STATUS
SDE12	MPS LH2 SYSTEM GRAPHIC DISPLAY
SDE13	MPS LH2 SYSTEM PRESS., TEMP VS TIME
SDE15	MPS LH2 SYSTEM ANALOG STATUS
VAE02	LH2 PNEU CONSOLE (OPF) EM VERIF

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.2 COMPUTER SYSTEMS

LPS
CCMS
CDS

1.2.1 SYSTEM CONFIGURATION:

GSE
6/18

VEHICLE LINKS AND FORMATS:

LDB
OI128
GPC128
FORMAT 129
FORMAT 42,44
PASS: MC7,MC9
BFS: N/A

CONSOLES REQUIRED:

C4

HIMS ACTIVE:

8096

1.2.2 DATA REQUIREMENTS (REAL TIME)

RPS

1.2.3 DATA REQUIREMENTS (POST TEST)

NONE REQUIRED

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.3 SPECIAL TOOLS, EQUIPMENT AND MATERIALS

1.3.1 MATERIALS

ISSUE/ RETURN -----	PART NO. -----	NOMENCLATURE -----	AVAIL -----	MAX KIT ---	QTY ---	FUNCTION -----
___/___	NA	SOAP SOLUTION (UI=BOTTLE)	_____	1	1	TBD-00
___/___	NA	TEFLON TAPE (UI=ROLL)	_____	1	1	SOSU-02
___/___	MS20955N32	SAFETY WIRE (UI=ROLL)	_____	1	1	TBD-00
___/___	MB0140-010	TYPE II LUBE (UI=EACH)	_____	1	1	OSSU-1
			_____		1	TBD-00
___/___	L070-000080- 122	FLEXHOSE 9 FT (UI=EACH)	_____	1	1	TBD-00
___/___	L070-000080- 168	FLEXHOSE 50 FT (UI=EACH)	_____	1	1	TBD-00

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.3.2 EQUIPMENT

ISSUE/ RETURN -----	PART NO. -----	NOMENCLATURE -----	AVAIL -----	MAX KIT ---	QTY ---	FUNCTION -----
___/___	L070-000070-009	BACK-TO-BACK 1/4 IN. OD (UI=EACH)	_____	1	1	OI-11
___/___	L070-000070-016	BACK-TO-BACK 1/4 IN. OD (UI=EACH)	_____	1	1	OSSU-1
___/___	ME286-0068-0008-0001 AND -0015 EQUIV SUBS	1/4 IN. MINIFILTER (UI=EACH)	_____	7	3	OSSU-1 TBD-00
___/___	C-MS28778-4	O-RING (UI=EACH)	_____	2	2	OSSU-1
___/___	SSKG250-4T	HAND VALVE (UI=EACH)	_____	1	1	OSSU-1
___/___	C-KC118C6	ELBOW 90 (UI=EACH)	_____	1	1	OSSU-2
___/___	74332026-503	DUST CAP P/O A70-0640-3 (UI=EACH)	_____	1	1	OSSU-2
___/___	C-KC133C6-4	REDUCER ADAPTER (UI=EACH)	_____	1	1	OSSU-1
___/___	C-KC112C4	ADAPTER (UI=EACH)	_____	1	1	OSSU-1
___/___	C-KC103-4	NOSE SEAL (UI=EACH)	_____	2	2	OSSU-1
___/___	C-KC150C4	CAP (UI=EACH)	_____	1	1	OSSU-1
___/___	C-KC125C6-4	REDUCER (UI=EACH)	_____	1	1	OI-11
___/___	C-KC103-6	NOSE SEAL (UI=EACH)	_____	1	1	OSSU-1
___/___	C-KC131C4	ELBOW (UI=EACH)	_____	1	1	OI-11

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

___/___	C70-0903	FLOWMETER (UI=EACH)	___	1	1	OI-ALL
___/___	C70-0796	ET/SRB ELECT INTERFACE UNIT (UI=EACH)	___	1	1	TBD-00
			___		1	TBD-00
___/___	E70-0036	CRYOGENIC SENSOR SIMULATOR (UI=EACH)	___	1	1	TBD-00
			___		1	TBD-00
___/___	HP428B	AMMETER (CLAMP-ON) (UI=EACH)	___	1	1	OI-04
___/___	NA	*TEKTRONIX 2200 OSCILLOSCOPE (UI=EACH)	___	1	1	OI-04
___/___	NA	*TEKTRONIX HC100 PLOTTER (UI=EACH)	___	1	1	OI-04

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.3.3 TOOLS

<u>ISSUE/ RETURN</u>	<u>PART NO.</u>	<u>NOMENCLATURE</u>	<u>AVAIL</u>	<u>MAX KIT</u>	<u>QTY</u>	<u>FUNCTION</u>
___/___	NA	TORQUE WRENCH 0-200 IN. LBS (UI=EACH)	_____	1	1	POSU-ALL
			_____		1	OSSU-ALL
			_____		1	OI-ALL
			_____		1	POI-ALL
___/___	NA	TORQUE WRENCH 0-600 IN. LBS (UI=EACH)	_____	1	1	POSU-ALL
___/___	NA	TORQUE WRENCH 0-1200 IN. LBS (UI=EACH)	_____	1	1	POSU-ALL
			_____		1	OSSU-ALL
			_____		1	OI-ALL
			_____		1	POI-ALL
___/___	NA	TORQUE WRENCH 0-50 IN. LBS (UI=EACH)	_____	1	1	POSU-ALL
			_____		1	OSSU-ALL
			_____		1	OI-ALL
			_____		1	POI-ALL
___/___	NA	TORQUE WRENCH 0-100 IN. LBS (UI=EACH)	_____	1	1	OI-ALL

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.3.4 FLIGHT EQUIPMENT

ISSUE/ RETURN	PART NO.	NOMENCLATURE	AVAIL	MAX KIT	QTY	FUNCTION
___/___	MD273-0044-2004	PLUG (UI=EACH)	_____	10	10	OSSU-01
			_____		10	OI-09
			_____		10	OI-13
			_____		10	OI-28
			_____		10	OI-29
___/___	ME261-0033-0104	SEAL (UI=EACH)	_____	4	4	OI-10
			_____		4	OI-09
			_____		4	OI-16
___/___	ME261-0033-0202	SEAL (UI=EACH)	_____	25	25	OI-18
			_____		25	OI-21
___/___	ME261-0033-0204	SEAL (UI=EACH)	_____	9	9	OI-07
			_____		9	OI-13
			_____		9	OI-28
			_____		9	OI-29
			_____		9	OI-32
___/___	MD273-0032- 2004	PLUG (UI=EACH)	_____	1	1	OI-16
			_____		1	POI-02
___/___	MD273-0032- 2002	PLUG (UI=EACH)	_____	1	1	OI-18

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.4 SUPPORT TOOLS, EQUIPMENT AND MATERIALS

1.4.2 COMMUNICATIONS (PER KICS)

1. VOICE RECORDING - CONTINUOUS WITH TIMING

OIS CHANNELS 132, 168, 111, 117, 232
RADIO NET 105/205 (BACKUP)

2. PAGING AND AREA WARNING: OPF

1.4.8 SERVICES

SERVICE/SPECIAL REQUIREMENTS	LOCATION	PURPOSE
-----	-----	-----
FACILITY PNEUMATICS		
6000 PSI GHE		
3000 PSIG GHE		
3000 PSI GN2		
50 PSI AIR PURGE		

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.5 PERSONNEL REQUIREMENTS

FOLLOWING CRITICAL SKILLS ARE REQUIRED FOR PERFORMANCE
OF INDICATED PORTIONS OF THIS OMI.

CONTROL NO. -----	TITLE -----	SEQUENCE -----	
028	ELECTRICAL CONNECTOR MATE/DEMATE	04,05]
085	MASS SPEC LEAK DETECTOR (LEYBOLD)	10]
086	MASS SPEC PROBE OPERATOR - ORB (LEYBOLD & CEC)	10]
242	TORQUE AND SAFETY WIRING	01,02,06 07,08,09 11]
403	FLIGHT ELECTRICAL TESTING (INSPECTORS & TECHNICIANS)	04]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.6 SAFETY REQUIREMENTS

1.6.1 HAZARDS

NONE

1.6.2 REQUIREMENTS

1. ALL TOOLS AND EQUIPMENT TO BE USED WITHIN 5 FEET OF THE ORBITER SHALL BE TETHERED.
2. OTHER SAFETY REQUIREMENTS PERTINENT TO THIS OMI ARE CONTAINED IN THE APPROPRIATE SEQUENCES/STEPS.

1.7 SPECIAL INSTRUCTIONS

1. EXTERNAL LEAK CHECKS USING SOAP SOLUTION - TYPE 1 JOINTS

NOTE

ALL THREADED, BRAZED, WELDED,
AND COMPONENT JOINTS BETWEEN
THE SSME ISO CHECK VALVES AND
FLOW CONTROL VALVE INLETS MUST
BE MASS SPEC LEAK CHECKED.

- A. JOINTS WHICH CAN BE INSPECTED AROUND 360 DEG OF THE CIRCUMFERENCE WILL BE REFERRED TO AS "TYPE 1". OPTICAL AIDS FOR FULL INSPECTION OF JOINT (BORESCOPE, MIRROR, ETC.) ARE ACCEPTABLE.
 - B. JOINTS WHICH CANNOT BE INSPECTED FOR BUBBLE FORMATION AROUND 360 DEG OF THE CIRCUMFERENCE (DUE TO POSITION OR FOAM), ARE CONSIDERED "TYPE 2" AND REQUIRE MASS SPEC LEAK CHECK.
 - C. UNLESS OTHERWISE SPECIFIED, ALL EXTERNAL LEAK CHECKS WILL BE PERFORMED USING LEAK DETECTION COMPOUND PER MSFC-SPEC-384, TYPE I. AFTER LIQUID OR FOAM IS APPLIED TO THE COMPONENT, NO VISIBLE BUBBLE FORMATION FOR 1 MINUTE WILL BE CONSIDERED NO LEAKAGE. A 360 DEGREE INSPECTION OF THE JOINT WILL BE MADE. A MIRROR WILL BE USED ON JOINTS WHERE 360 DEGREE INSPECTION IS NOT POSSIBLE WITH EYE ALONE. FOLLOWING THE LEAK CHECK, ALL AFFECTED FITTINGS, COMPONENTS, TUBING AND SURROUNDING AREAS WILL HAVE LEAK CHECK SOLUTION REMOVED USING DISTILLED DEIONIZED WATER, AND CLEAN LOW-LINT CLOTH PRIOR TO REDUCING PRESS. DO NOT APPLY LEAK CHECK SOLUTION TO FLEXLINES OR BELLOW. EXTREME CARE SHOULD BE USED TO KEEP LEAK CHECK SOLUTION FROM CONTACTING ELECTRICAL COMPONENTS.
- 2. PRESSURE MUST BE VENTED BEFORE FITTINGS ARE LOOSENED OR REPAIRS ATTEMPTED.
 - 3. ALL IDENTIFIED LEAKS MUST BE DOCUMENTED FOR DISPOSITION BY ENGINEERING.
 - 4. THROUGHOUT THIS OMI, THE SYMBOL BD INDICATES INFORMATION TO BE GATHERED AS ENGINEERING BASELINE DATA ONLY.
 - 5. THROUGHOUT THIS OMI, REFERENCE IS MADE TO SOLENOID VALVES, PNEUMATIC VALVES AND RELIEF VALVES. REF DES NUMBERS; LVXX, PVXX, AND RVXX ARE ALL PREFIXED WITH 50V41.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

6. OPERATION OF THE C70-0903 ATMOSPHERIC FLOWMETER UNIT.

NOTE

PYROMETER IS NOT TO BE
USED UNLESS OTHERWISE
SPECIFIED.

SETUP

VERIFY CALIBRATED AND HAS VALID CALIBRATION STICKERS AND
VALID CALIB CURVES.

LEVEL UNIT BY ADJUSTING LEVELING LEGS UNTIL LEVELING BUBBLE,
AT TOP OF UNIT, IS CENTERED.

CONNECT SENSE LINE TO APPROPRIATE FLOWMETER INLET PORT.

TEST

VERIFY SYSTEM TO BE LEAK CHECKED IS PRESSURIZED.

SELECT APPROPRIATE PLUG ADAPTER TO FIT OUTLET TO BE TESTED.

ATTACH PLUG TO SENSE LINE.

CONNECT SENSE LINE INTO TEST ARTICLE OUTLET.

PERFORM "PINCH TEST" OF SENSE LINE AND VERIFY
GOOD SEAL BY FLOWMETER BALL MOVEMENT.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

NOTE

DO NOT HANDLE SENSE LINE
WHILE TAKING MEASUREMENTS.

ALLOW FLOWMETER TO STABILIZE
BEFORE RECORDING DATA.
USE FLOWMETER THAT WILL
READ IN THE UPPER 2/3 OF
THE SCALE WHERE POSSIBLE.

WHEN FLANGE, SHAFT SEAL OR
INTERNAL LEAKAGE IS MEASURED
AND IS AS MUCH AS ONE-HALF
THE MAX ALLOWABLE LEAKAGE
AT A PRESSURE IN THE RANGE
SPECIFIED FOR THAT JOINT,
THEN MEASUREMENTS MUST BE
MADE AT OR NEAR THE MINIMUM
AND MAXIMUM PRESSURE LIMITS
TO DETERMINE THE PRESSURE
VERSUS LEAKAGE CHARACTERISTICS
FOR THAT CONDITION.

IF UNABLE TO READ FLOWMETER DUE TO SMALL LEAKAGE RATE,
REMOVE SENSE LINE FROM NUMBERED METER PORT AND INSERT
INTO NEXT MOST SENSITIVE PORT. CONTINUE UNTIL ACCEPTABLE
MEASUREMENT IS OBTAINED.

RECORD READINGS ON DATA SHEET AND CALCULATE LEAK RATE
FROM TUBE CALIBRATION CURVE GRAPH OR DATA TABLES.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

7. MASS SPECTROMETER LEAK CHECKS

THIS LEAKAGE DETECTION METHOD MUST BE USED FOR FLEXLINES AND BELLOWS, AND MAY BE USED FOR WELDS, BRAZED JOINTS, THREADED CONNECTIONS, OR BOLTED JOINTS AS SPECIFIED IN INDIVIDUAL WORK UNIT CODES.

THE MASS SPECTROMETER LEAK CHECK METHOD SHALL BE EITHER PROBE TECHNIQUE (METHOD A) OR THE ENCLOSURE TECHNIQUE (METHOD B) AS DEFINED IN MF0001-003 OR AS SPECIFIED IN THIS DOCUMENT.

UNLESS OTHERWISE SPECIFIED IN INDIVIDUAL REQUIREMENTS, THE MAXIMUM ALLOWABLE LEAKAGE FOR WELDS, BRAZED JOINTS, FLEXLINES, BELLOWS, CRYOGENIC AND PNEUMATIC THREADED JOINTS, AND GH2 LOW PRESSURE JOINTS, SHALL BE 1×10^{-6} SCCS INDICATED FOR METHOD A OR B. GH2 HIGH PRESSURE SHALL BE 1×10^{-7} AS INDICATED PER MF0001-003 METHOD A OR B. BASELINE DATA BUBBLE SOAPS AND MASS SPEC'S MAY BE PERFORMED BY MPS ENGINEER AT ANY TIME AS REQUIRED. BASELINE DATA TO BE RECORDED BY THE ENGINEER.

8. LEAK CHECK METHODS FOR NEW AND REPAIRED JOINTS.

NEW AND REPAIRED GH2 CONNECTIONS AND COMPONENT JOINTS SHALL BE LEAK CHECKED PER MATRIX EXCEPT FOR LISTED JOINTS.

	TYPE I -----	TYPE II -----	INST. & TEST PORTS -----
GH2 LOW	SOAP SOLUTION INCLUDING A CHECK OF ADJACENT THREADED FITTINGS	MASS SPEC PER MF0001-003 WITH MAX ALLOWABLE INDICATED LEAKAGE 1 X 10 ⁻⁶	SOAP SOLUTION
GH2 HIGH	MASS SPEC PER MF0001-003 WITH MAX ALLOWABLE INDICATED LEAKAGE 1 X 10 ⁻⁷	MASS SPEC PER MF0001-003 WITH MAX ALLOWABLE INDICATED LEAKAGE 1 X 10 ⁻⁷	MASS SPEC PER MF0001-003 WITH MAX ALLOWABLE INDICATED LEAKAGE 1 X 10 ⁻⁷

GH2 LOW PRESSURE: FCV BODY TO ORB/ET I/F AND T=0 DISCONNECT.
GH2 HIGH PRESSURE: SSME I/F TO FCV INLET.

NEW AND REPAIRED GH2 COMPONENT FLANGED CONNECTIONS NOT EQUIPPED WITH LEAK DETECTION PORTS SHALL BE LEAK CHECKED USING MASS SPEC. (PER MF0001-003 METHOD A OR B). ALLOWABLE LEAKAGE IS 1 X 10⁻⁶ SCCS, INDICATED, UNLESS OTHERWISE SPECIFIED BY INDIVIDUAL REQUIREMENT.

NEW AND REPAIRED COMPONENT AND LINE FLANGES EQUIPPED WITH LEAK DETECTION PORTS BEFORE REASSEMBLY SHALL BE INSPECTED TO VERIFY THAT LEAK DETECTION PORT IS CLEAR AND FREE OF DEBRIS. DURING LEAK TEST TEMPORARILY APPLY SEALANT TAPE AROUND THE FLANGE CIRCUMFERENCE TO DIRECT LEAKAGE OUT TO THE LEAK DETECTION PORT.

9. OPERATION OF LEYBOLD ULTRA TEST IV MASS SPECTROMETER:

WHEN LEYBOLD ULTRA TEST IV MASS SPECTROMETER IS BEING USED, ALTERNATE METHOD B IS NOT ALLOWED, METHOD A (PROBE TECHNIQUE), METHOD B (VENTED ENCLOSURE TECHNIQUE), OR METHOD D (ACCUMULATED LEAKAGE TECHNIQUE) ARE ALLOWED AND SHALL BE PERFORMED IN ACCORDANCE WITH MF0001-003. RESPONSE TIME SHALL BE LESS THAN 20 SEC.

PERMEABILITY RATIO SHALL BE LESS THAN 600

MAXIMUM BACKGROUND SHALL BE LESS THAN 0.8 X ALLOWABLE MAXIMUM LEAK RATE OF THE JOINT.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

10. MPS WILL BE RESPONSIBLE FOR PERFORMING AN INFORMAL OIR.

11. LUBRICATION

NOTE

PREVIOUSLY LUBRICATED MALE
DYNATUBE FITTINGS SHALL NOT BE
RELUBRICATED (MA0112-303,3.4.6)

LUBRICATE ALL NON-DRY LUBED MALE THREADED JOINTS AND
O-RINGS WITH MB0140-010 TYPE II APPROVED LUBRICANTS,
(EXAMPLE: BRAYCOTE 3L-38RP GREASE).

A. O-RINGS

1. TO ASSIST IN THE INSTALLATION OF A DRY O-RING,
APPLY LUBRICANT OVER THE SURFACE OF THE O-RING
USING GLOVE COVERED FINGERTIPS. WIPE LUBRICANT
OFF GLOVED FINGERS WITH A CLEAN LOW-LINT WIPE
THEN REMOVE EXCESS LUBRICANT FROM O-RING WITH
FINGERTIPS. WORK WITH O-RING IN THIS MANNER
UNTIL NO VISUAL ACCUMULATION OF LUBRICANT IS
OBSERVABLE ON GLOVED FINGERTIPS BY FURTHER WIPING.
2. TO HOLD A STATIC O-RING IN ITS GROOVE WHEN
INSTALLING A MATING PART, APPLY LUBRICANT IN
THE GROOVE NOT TO EXCEED 10 PERCENT OF THE
TOTAL GROOVE VOLUME.

CAUTION

DO NOT APPLY LUBE TO MD273-0032
OR -0044 PLUGS. DRY LUBE IS
ALREADY APPLIED.

B. THREADED PARTS

1. APPLY LUBRICANT IN A STREAK ACROSS ALL MALE
THREADS, WITH A STREAK WIDTH NOT TO EXCEED
0.12 IN. THE LUBRICANT SHOULD BE APPLIED AT
AT ONE POINT WITH THE LUBRICANT FLUSH WITH
THE CREST OF THE THREADS.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

CAUTION

EXERCISE CARE NOT TO GET
LUBRICANT ON FLARED SEALING
SURFACES OR ON THE ENDS OF
FITTINGS WHERE IT COULD GET
INTO A SYSTEM.

2. APPLY A THIN LAYER OF THREAD LUBRICANT TO THRUST SURFACE OF A TUBING SLEEVE TO PREVENT GALLING WHEN TORQUING.

12. SAFETY WIRE ALL PLUGS, TRANSDUCERS, ETC PER MA0102-306 USING SAFETY WIRE AS SPECIFIED IN BODY OF OMI.

13. CLEANLINESS LEVEL OF MPS SUBSYSTEMS ARE

GHE AND GO2 SUBSYSTEM	LEVEL 100A
LO2 SUBSYSTEM	LEVEL 800A
LH2 AND GH2 SUBSYSTEM	LEVEL 400

PERSONNEL INSTALLING TEST EQUIPMENT SHALL VERIFY THAT ALL EQUIPMENT IS CLEANED TO THE PROPER LEVEL PRIOR TO INSTALLATION

TEST EQUIPMENT MAY BE TRANSFERRED FROM ONE SUBSYSTEM TO ANOTHER SUBSYSTEM ONLY IF THE SECOND SYSTEM HAS THE SAME OR LOWER CLEANLINESS LEVEL REQUIREMENT.

ALL FLUID TEST EQUIPMENT THAT INTERFACES ORBITER FLUID SYSTEMS TO BE CLEANED TO KSC-C-123F LEVEL 100A.

14. MATERIAL USAGE PERMIT (MUP)

MUP 87-009 - ALLOWS MPS TO USE ACLAR DURING PROCESSING. CLEANLINESS CLASS 100A REQUIRED.

15. LEAK CHECK OF FOAMED JOINTS (BRAZED OR THREADED)

BRAZED, WELDED, THREADED OR FLANGED JOINTS WITHOUT TEST PORTS COVERED WITH FOAM INSULATION DO NOT REQUIRE CHECKS EXCEPT WHEN INVALIDATED.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

16. TORQUE CHECK OF LEAKING DYNATUBE JOINT

- A. VERIFY PRESSURE IS AT ZERO IN LINE.
- B. DETERMINE HOW LOOSE FITTING IS. ATTEMPT TO TIGHTEN IT BY HAND AND COUNT NUMBER OF TURNS UNTIL FINGER TIGHT.
- C. USING DIAL INDICATOR TORQUE WRENCH, APPLY TIGHTENING TORQUE (CW) TO FITTING AND RECORD TORQUE REQUIRED TO CAUSE FIRST MOVEMENT UP TO MAXIMUM ALLOWED TORQUE.
- D. IF FITTING IS FOUND TO BE AT MAXIMUM TORQUE VALUE AND NO (CW) MOVEMENT OCCURED, DISASSEMBLE FITTING AND INSPECT MATING SURFACES FOR MISALIGNMENT, SCRATCHES, OR LACK OF LUBRICANT ON MALE THREADS.

17. MPS CAP/PLUG SET REMOVAL PROCEDURE

- A. WHEN CAP/PLUG HAS BEEN REMOVED FROM THE VEHICLE RINSE OFF CAP/PLUG SEALING SURFACE WITH FREON-TF. WIPE WITH LINT FREE CLOTHS. OBTAIN TIR LOG NO. TO DOCUMENT REMOVAL.
- B. INSPECT GSE SEALING SURFACE FOR DAMAGE: DINGS, SCRATCHES, GOUGES ETC. RECORD RESULTS.
- C. BAG PLATE BY COVERING SEALING SURFACE WITH ACLAR 22A PER MK0116-0011, APPLY INTEGRITY SEALS. COVER SEALING SURFACE WITH LIBERAL AMOUNT OF PLASTIC WRAP FOR PROTECTION.
- D. BAG AND IDENTIFY ALL ATTACHMENT HARDWARE AND INSPECTION STAMP.
- E. I.D. CAP/PLUG WITH P/N, AND INSPECTION STAMP.
- F. ON PARTS TAG PLACE LEVEL OF CLEANLINESS MAINTAINED BASED ON SYSTEM WHICH CAP/PLUG WAS REMOVED PER 1.7.13 AND MA0110-311.
- G. ATTACH HARDWARE BAG TO CAP/PLUG BAG USING TAPE AND RETURN ITEMS TO RESPECTIVE CAP/PLUG SET:

MPS TEST A70-0640-3-11
MPS TEST A70-0640-3-14
FERRY FLIGHT A70-0640-5-21

CAUTION

DO NOT SPRAY FREON INTO
DISCONNECT BEING CLEANED.

18. MPS VEHICLE DISCONNECT CLEANING PROCEDURE AND TEST EQUIPMENT INSTALLATION.
 - A. VISUALLY INSPECT DISCONNECT WITH WHITE LIGHT FOR DAMAGE TO SEALING SURFACE. RECORD RESULTS. INITIATE PR IF DAMAGE IS NOTED TO SEALING SURFACE, IF DAMAGE (SMALL SCRATCHES, NICKS, ETC.) ARE NOTED ON NON-SEALING SURFACE CONTACT MPS ENGR FOR FURTHER INFORMATION.
 - B. VISUALLY INSPECT MPS 1 IN. QD'S (PD8-10,14) AND VERIFY MS16625-4250 SNAP RING IS FULLY SEATED IN GROOVE AND NO DISTORTION OR DISLOCATION IS EVIDENT.
 - C. VISUALLY INSPECT VENT HOLES IN QD'S (PD9,10,14) FOR OBSTRUCTIONS OR CONTAMINATION.
 - D. IF PARTICULATE/CONTAMINATION IS NOTED, REMOVE BY WIPING AREA WITH FREON-TF MOISTENED LINT FREE CLOTH. (REPEAT THIS AND FREON WIPE UNTIL VISUALLY CLEAN.
 - E. IF A CAP/PLUG IS TO BE INSTALLED IT MUST CONFORM TO CLEAN LEVELS CALLED OUT IN 1.7.13.
 - F. ON PARTS TAG, PLACE LEVEL OF CLEANLINESS MAINTAINED, BASED ON SYSTEM WHICH CAP/PLUG WAS REMOVED PER CLEANLINESS SPECIAL INSTRUCTION AND MA0110-311.
 - G. IF NO CAP/PLUG IS TO BE INSTALLED, COVER DISCONNECT WITH ACLAR 22A CLEAN LEVEL 100A. APPLY INTEGRITY SEALS.
19. WHEN AN MPS SUBSYSTEM IS OPENED OR WHEN INTERFACING HARDWARE IS ATTACHED. THE INTERFACE AND/OR THE INTERIOR SURFACES OF THE MPS THAT CAN BE SEEN SHALL BE INSPECTED FOR CLEANLINESS. INSPECTED SURFACES SHALL BE VISIBLY CLEAN (WITH THE UNAIDED EYE) PER MA0110-311.

REF OMRS V41GEN.041 MPS CLEANLINESS INSPECTION

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

20. V1171VL1 - MPS/SSME PRESSURIZATION OPERATIONS (LPS)

THIS OMI ALLOWS MPS ENGR TO USE SPECIFIC TASKS REQUIRED FOR TESTING IN CASES WHERE VEHICLE IS OUT OF NORMAL CONFIGURATION OR TO PERFORM SPECIAL TEST REQUIREMENTS. V1171VL1 MAY BE USED AT ANY TIME DURING STS FLOW TO SUPPORT ENGR AND TASK BEING PERFORMED. THIS OMI MAY ALSO BE CALLED OUT BY OTHER WADS, (OMI'S, TPS'S, PR'S, ETC.)

21. CDS DATA RETRIEVAL

- A. CDS ENABLE KEY - PRESS
- B. TYPE IN "TXK-"
- C. SIGN ON KEY - PRESS
- D. PAGE CLEAR BREAK KEY - PRESS
- E. TYPE "XX_TCID", FD (UP TO 6 FD'S); START TIME (GMT), STOP TIME (GMT), DATE
- F. (XX=LC, LIST CHANGE; P, PLOT; L, LIST)
- G. CDS XMIT KEY - PRESS AT END OF EACH LINE

22. EFFECTIVITY CODES

EFFECTIVITY CODES DEFINE FLIGHTS AND ORBITERS FOR WHICH EACH OMRSD REQUIREMENT APPLIES. THIS PROCEDURE CONTAINS NOTES WITH A BRIEF DESCRIPTION OF REQUIREMENT, OMRSD NUMBER, EFFECTIVITY OF THE REQUIREMENT AND A NOT PERFORMED STATEMENT IF APPLICABLE. THE SYSTEM ENGINEER WILL DETERMINE FROM THE EFFECTIVITY CODES IF STEPS FOLLOWING THE NOTE ARE REQUIRED. THE NOT PERFORMED STATEMENT APPLIES TO ALL STEPS BETWEEN NOTE AND COMPLETION STATEMENT WHICH CONTAINS DESCRIPTION OF THE REQUIREMENT COMPLETED. EFFECTIVE FLIGHTS AND ORBITERS ARE DETERMINED FROM THE CODES AS FOLLOWS.

VXX ORBITER EFFECTIVITY

VA ALL ORBITERS
V02 OV-102
V03 OV-103
V04 OV-104
V05 OV-105

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

CODE -----	FLIGHTS -----
VXXF;C	CONTINGENCY
VXXF1-90	ALL
VXXF1;C	1 AND CONTINGENCY
VXXF1,15F;C	1 AND INTERVALS OF EVERY 5 THEREAFTER AND CONTINGENCY
VXXF1,2,5;C	1, 2, 5 AND CONTINGENCY
VXXF1-90;Z	ALL, SATISFIED BY JSC REVIEW OF FLT DATA
VXXF1-4,15F;C	1 THRU 4 AND INTERVALS OF EVERY 5 THEREAFTER AND CONTINGENCY
VXXF5I10F;C	FLIGHT 5 AND INTERVALS OF EVERY 10 AND CONTINGENCY

23. THE ORDER OF PERFORMANCE OF SEQUENCES/STEPS (HAZARDOUS OR NON-HAZARDOUS) WITHIN THIS OMI IS GOVERNED IN ACCORDANCE WITH SPI-519.

24. THROUGHOUT THIS OMI THE BELOW LISTED GSE PANELS WILL BE LOCATED AS FOLLOWS:

OPF BAYS 1&2:

OPF BAY 3:

]]

S70-0695-2 PNL PLATFORM 12W
S70-0695-8 PNL PLATFORM 12E

S70-0695-2 PNL PLATFORM 12E
S70-0695-8 PNL PLATFORM 12W

25. ONCE A GSE HAND REG IS SET PER THIS OMI OR SUPPORTING SUBTASK WAD, THE REG MAY BE ADJUSTED (CW) OR (CCW) TO INCREASE OR DECREASE GSE SUPPLY PRESSURE TO MAINTAIN INITIALLY SET VALUE.

ADDITIONALLY, FOR SELF VENTING TYPE HAND REGS, THE BLEEDER VALVE ADJUSTMENT SCREW MAY BE ADJUSTED TO PROPERLY ALLOW HAND REG TO VENT AS DESIGNED. STANDARD PRACTICE IS AS FOLLOWS:

WHILE INCREASING THE REG UP TO SET PRESSURE, TURN THE BLEEDER VALVE ADJUSTMENT SCREW COUNTERCLOCKWISE TO REDUCE/STOP VENTING. WHEN DESIRED PRESSURE IS OBTAINED, TURN ADJUSTMENT SCREW COUNTERCLOCKWISE UNTIL VENTING STOPS, PLUS ONE QUARTER TURN.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

26. THIS OMI COMPLIES WITH THE FOLLOWING MPS V41 GEN REQUIREMENTS:

V41GEN.041	MPS CLEANLINESS INSPECTION
V41GEN.130	MAX SOAP W/PERSONNEL PRESENT (GH2 PRESS)
V41GEN.160	ORBITER EXTERNAL LEAK CHECK CRITERIA
V41GEN.170	SOAP SOLUTION LEAK CHECKS
V41GEN.180	FOAM INSULATED JOINT LEAK CHECKS
V41GEN.190	MASS SPECTROMETER LEAK CHECKS
V41GEN.200	FLANGED JOINTS/SHAFT SEAL/INTERNAL LK CK
V41GEN.210	LEAK CK METHODS - NEW/REPAIRED JOINTS

27. MPS WILL BE RESPONSIBLE FOR PERFORMING AN INFORMAL OIR.

MINIMUM ATTENDEES ARE LSOC/NASA SYSTEM ENGINEERING AND PP&C.

28. THIS BOOK IS NON-HAZARDOUS AND MAY BE RUN ROR.

DATE: 02-25-92

1.8 OMRS REQUIREMENTS SATISFIED BY THIS TOP

VEHICLE/ELEMENT NO. ORB_____/FLT____ ET____ SRB____ LH____ RH____

GROUND HARDWARE PMN/SN _____ COMPONENT/SEGMENT _____/FLT____

SITE _____ TCN _____ DATE _____

TOP WAS RUN AS A STANDALONE YES _____ NO _____
 TOP WAS RUN AS A SUBTASK TO TOP _____.

OMRS NO./CIL NO	NOMENCLATURE/ EFFECTIVITY	SEQ-STEP (CAP)	QC/ENG VERIF
-----	-----	-----	-----

V41AD0.010 (1R)	L01 LV53/LV56 ULL PRESS CNTL W/CK OUT CMDS V03F1-12 V04F1-8	05-015]
	L02 V02F11-90 V03F13-90 V04F9-90 V05F1-90]
V41AD0.020 (1R)	L01 LV54/LV57 ULL PRESS CNTL W/CK OUT CMDS V03F1-12 V04F1-8	05-015]
	L02 V02F11-90 V03F13-90 V04F9-90 V05F1-90]
V41AD0.030 (1R)	L01 LV55/LV58 ULL PRESS CNTL W/CK OUT CMDS V03F1-12 V04F1-8	05-015]
	L02 V02F11-90 V03F13-90 V04F9-90 V05F1-90]
V41AD0.100-A	E1 GH2 FCV CURRENT SIG (LV56) L02 V02FB16I5FR12;C V03FB18I5FR14;C V04FB13I5FR9;C V05F1-2I5F;C	04-021]
V41AD0.100-B	E2 GH2 FCV CURRENT SIG (LV57) L02 V02FB16I5FR12;C V03FB18I5FR14;C V04FB13I5FR9;C V05F1-2I5F;C	04-031]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.8 OMRS REQUIREMENTS SATISFIED BY THIS TOP

VEHICLE/ELEMENT NO. ORB_____/FLT____ ET____ SRB____ LH____ RH____

GROUND HARDWARE PMN/SN _____ COMPONENT/SEGMENT _____/FLT____

SITE _____ TCN _____ DATE _____

TOP WAS RUN AS A STANDALONE YES _____ NO _____

TOP WAS RUN AS A SUBTASK TO TOP _____.

OMRS NO./CIL NO	NOMENCLATURE/ EFFECTIVITY	SEQ-STEP (CAP)	QC/ENG VERIF
-----	-----	-----	-----
V41AD0.100-C	E3 GH2 FCV CURRENT SIG (LV58)	04-041	_____]
L02	V02FB16I5FR12;C]]
	V03FB18I5FR14;C]]
	V04FB13I5FR9;C]]
	V05F1-2I5F;C]]
V41AY0.040-A	GH2 PRESS SYSTEM JOINT LK CKS	10-016	_____]
(1)	L01 V03F7I5FE14]]
	V04F3I5FE10]]
	L02 V02F8I5FR12]]
	V03F7I5FR15]]
	V04F3I5FR11]]
	V05F2I5F]]
V41AY0.040-B	GH2 PRESS SYS ORB/ORB FLANGE LK CKS	09-003	_____]
(1)	L01 V03F7I5FE14]]
	V04F3I5FE10]]
	L02 V02F8I5FR12]]
	V03F7I5FR15]]
	V04F3I5FR11]]
	V05F2I5F]]
V41AY0.045	GH2 PRESS SYS INVALIDATED JNT LEAK CK	08-060	_____]
	VAF;C]]
V41AY0.046	GH2 FCV WELD LK TEST	10-002	_____]
	V02F12-90	(EFFECTI)]]
	V03F15-90]]
	V04F11-90]]
	V05F2-90]]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.8 OMRS REQUIREMENTS SATISFIED BY THIS TOP

VEHICLE/ELEMENT NO. ORB_____/FLT____ ET____ SRB____ LH____ RH____

GROUND HARDWARE PMN/SN _____ COMPONENT/SEGMENT _____/FLT_____

SITE _____ TCN _____ DATE _____

TOP WAS RUN AS A STANDALONE YES _____ NO _____

TOP WAS RUN AS A SUBTASK TO TOP _____.

OMRS NO./CIL NO	NOMENCLATURE/ EFFECTIVITY	SEQ-STEP (CAP)	QC/ENG VERIF
-----	-----	-----	-----
V41AY0.200 (1)	GH2 PRESS SYSTEM DECAY CHECK	06-019	_____]
	L01 V02F1-11]]
	V03F1-13]]
	V04F1-8]]
	L02 V02FR12;C]]
	V03FR14;C]]
	V04FR9;C]]
	V05F;C]]
V41AY0.380	LH2 REPRESS SYS INVALIDATED JT LK CK VAF;C	07-012	_____]
V41BA0.052 (1R)	CV24 GH2 REPRESS CK VLV REV LK CK	07-007	_____]
	V02F1-90;C]]
	V03F1-90;C]]
	V04F1-90;C]]
	V05F2-90;C]]
V41BA0.080-B (1R)	CV17 LH2 TK PREPRESS CK VLV LK CK	08-019	_____]
	L02 V02FOMDP;C]]
	V03FOMDP;C]]
	V04FOMDP;C]]
	V05F5,OMDP;C]]
V41BA0.100-A (1R)	CV21 E-1 GH2 ISO CK VLV LK CK	11-021	_____]
	L01 V02F8I5FE11;C]]
	V03F7I5FE13;C	11-022	_____]
	V04F3I5FE8;C]]
	L02 V02FR12;C]]
	V03FR14;C]]
	V04FR9;C]]
	V05F2;C]]

DATE: 02-25-92

1.8 OMRS REQUIREMENTS SATISFIED BY THIS TOP

VEHICLE/ELEMENT NO. ORB_____/FLT____ ET____ SRB____ LH____ RH____
 GROUND HARDWARE PMN/SN _____ COMPONENT/SEGMENT _____/FLT____
 SITE _____ TCN _____ DATE _____

TOP WAS RUN AS A STANDALONE YES _____ NO _____
 TOP WAS RUN AS A SUBTASK TO TOP _____.

OMRS NO./CIL NO	NOMENCLATURE/ EFFECTIVITY	SEQ-STEP (CAP)	QC/ENG VERIF
-----	-----	-----	-----
V41BA0.100-B (1R)	CV22 E-2 GH2 ISO CK VLV LK CK	11-034	_____]
L01	V02F8I5FE11;C		_____]
	V03F7I5FE13;C	11-035	_____]
	V04F3I5FE8;C		_____]
L02	V02FR12;C		_____]
	V03FR14;C		_____]
	V04FR9;C		_____]
	V05F2;C		_____]
V41BA0.100-C (1R)	CV23 E-3 GH2 ISO CK VLV LK CK	11-048	_____]
L01	V02F8I5FE11;C		_____]
	V03F7I5FE13;C	11-049	_____]
	V04F3I5FE8;C		_____]
L02	V02FR12;C		_____]
	V03FR14;C		_____]
	V04FR9;C		_____]
	V05F2;C		_____]
V41BB0.020 (1)	PD5/LV52 GH2 PRESS DISC LEAK CHECK	06-026	_____]
	V02F8;C		_____]
	V03F7;C		_____]
	V04F3;C		_____]
	V05F;C		_____]
V41BB0.050 (1R)	PD10 LH2 PREPRESS DISC REV LK CK	08-041	_____]
L02	V02FB16I5FR12;C		_____]
	V03FB18I5FR14;C		_____]
	V04FB13I5FR9;C		_____]
	V05F5I5F;C		_____]
V41BB0.051	CV17/PD10 REV LK VALID	08-007	_____]
	V02F12-90		_____]
	V03F14-90		_____]
	V04F9-90		_____]
	V05F2-90		_____]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

1.8 OMRS REQUIREMENTS SATISFIED BY THIS TOP

VEHICLE/ELEMENT NO. ORB_____/FLT____ ET____ SRB____ LH____ RH____

GROUND HARDWARE PMN/SN _____ COMPONENT/SEGMENT _____/FLT____

SITE _____ TCN _____ DATE _____

TOP WAS RUN AS A STANDALONE YES _____ NO _____

TOP WAS RUN AS A SUBTASK TO TOP _____.

OMRS NO./CIL NO	NOMENCLATURE/ EFFECTIVITY	SEQ-STEP (CAP)	QC/ENG VERIF
-----	-----	-----	-----

V41BZ0.220	LV52 LH2 PRESS LINE VENT VLV FLOW PATH	12-011]
	V02F8;C]
	V03F7;C]
	V04F3;C]
	V05F;C]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

SECTION II

PRE-OPERATION SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
01-000			PRE-OPERATION SETUPS - ORBITER	
01-001			PRE-OPERATION SETUP 1 - QUALITY SUMMARY SHEET (CMQC)	
01-002	CMQC		VERIFY REQUIRED PRE-OPERATION SETUPS COMPLETE FOR CALL TO STATIONS.]]

NOTE

COMPLETION OF THE NEXT TWO PRE-OPERATION SETUPS IS NOT A CONSTRAINT TO CALL TO STATION.

- 2 PD16 GH2 SENSE LINE QD INSTALLATION
NOT PERFORMED _____]
- 3 PD10 GH2 PREPRESS QD INSTALLATION
NOT PERFORMED _____]

01-003 ORBITER PRE-OPERATION SETUP 1 - QUALITY SUMMARY SHEET COMPLETE. REQUIRED PRE-OPERATIONS FOR CALL TO STATIONS COMPLETE.

QV: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

PRE-OPERATION SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

PRE-OPERATION SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
01-004			PRE-OPERATION SETUP 2 - PD16 GH2 SENSE LINE QD INSTALLATION - OMT0, OQCV, NASA QC	

NOTE

DO NOT PERFORM THIS
PRE-OPERATION SETUP IF
FLEXHOSE/QD ASSY IS ALREADY
INSTALLED AT ORBITER QD
50V41PD16.

PRE-OPERATION SETUP 2 NOT PERFORMED

NOTE

COMPLETION OF THIS
PRE-OPERATION SETUP IS NOT A
CONSTRAINT TO CALL TO STATION.

COMPLETION VERIFICATION WILL
BE PERFORMED PRIOR TO THE
OPERATION BEING SUPPORTED.

01-005 VERIFY GW70-420958-002 GRND HALF COUPLING
IS CONNECTED TO 79K10547-HE16 FLEXHOSE.
VERIFY 79K10547-HE16 FLEXHOSE IS CONNECTED
TO (0-2) INTERFACE PANEL PORT A131506
(SEE FIGURES 8-10).

T: _____

01-006 S70-0695-8 PNL

A83066 SOV - CLOSE (CW)
A83070 - OPEN (CCW)
A83065 GAGE SOV - OPEN (CCW)
A83145 - OPEN (CCW)

VERIFY GAGE A83143 READS 0 PSIG.

A83070 - CLOSE (CW)

T: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

PRE-OPERATION SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

50V41PD16 IS LOCATED IN AFT FUSELAGE (LEFT HAND SIDE) JUST DOWNSTREAM OF GH2 FLOW CNTL VALVES.

01-007

1. REMOVE GRND PLUG (CCW) FROM GW70-420958-002 COUPLING. MAINTAIN SYSTEM CLEANLINESS (REF MA011-311).
2. REMOVE CAP (CCW) FROM 50V41PD16 TEST POINT COUPLING.
3. GW70-420958-002 QD FILTER ASSY

OK TO INSTALL QWN: _____

CONNECT GW70-420958-002 QD/FILTER ASSY TO 50V41PD16 INSIDE THE AFT FUSELAGE. INSERT GROUND HALF COUPLING AND TURN (CW). TORQUE TO 15-20 IN. LBS. SECURE WITH FLEXHOSE RESTRAINTS. (REF 80K51846)

Z _____ DUE DATE _____

VERIFY CSR-242 TQV: _____
SS3

4. CONNECT AIRBORNE CAP AND GND PLUG TOGETHER.
5. SUPPORT HE16 FLEXHOSE TO AVOID CREATING TORQUE ON THE GSE/VEHICLE DISCONNECT. USE TIE WRAPS.

TQW: _____

01-008

ORBITER PRE-OPERATION SETUP 2 - PD16 GH2 SENSE LINE QD INSTALLATION COMPLETE.

QV: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

PRE-OPERATION SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
01-009			PRE-OPERATION SETUP 3 - PD10 GH2 PREPRESS QD INSTALLATION - OMT0, OQCV, NASA QC	

NOTE

DO NOT PERFORM THIS
PRE-OPERATION SETUP IF
FLEXHOSE/QD ASSEMBLY IS
ALREADY INSTALLED AT
ORBITER QD 50V41PD10.

PRE-OPERATION SETUP 3 NOT PERFORMED

NOTE

OPERATIONS INVOLVING CRIT 1
AND/OR IR ITEMS ARE CONTAINED
IN THE FOLLOWING SEQUENCE/
STEPS.

COMPLETION OF THIS
PRE-OPERATION SETUP IS NOT A
CONSTRAINT TO CALL TO STATION.

COMPLETION VERIFICATION WILL
BE PERFORMED PRIOR TO THE
OPERATION BEING SUPPORTED.

FERRY FLIGHT CAPS ARE REMOVED
POST FERRY FLIGHT PER JOB
CARD V41-20005 IN SUPPORT OF
V5003.

01-010

IF NOT INSTALLED, INSTALL PD16 PER
PRE-OPERATION SETUP 2.

TQV: _____

NOT PERFORMED _____

PD10 - VEHICLE DISCONNECT INSPECTION

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

PRE-OPERATION SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
01-011			IF INSTALLED REMOVE ACLAR/TAPE FROM DISCONNECT 50V41PD10.	TQV: _____
			NOT PERFORMED	_____
01-012			CLEAN AND INSPECT VEHICLE DISCONNECT (REF 1.7.18 SPECIAL INSTRUCTIONS). RESULTS _____	TQW: _____
01-013			S70-0695-8 PANEL A83066 SOV - CLOSE (CW) A83070 - OPEN (CCW) A83065 GAGE SOV - OPEN (CCW) A83145 - OPEN (CCW) UNTIL AUDIBLE VENTING CEASES, THEN CLOSE (CW). VERIFY GAGE A83143 READS 0 PSIG. A83070 - CLOSE (CW)	T: _____
01-014			IF TWISTED, LOOSEN 79K10547-HE10 FLEXHOSE FROM INLET OF G070-005820 QD. USE BACKUP WRENCH. MAINTAIN SYSTEM CLEANLINESS.	TQW: _____
			NOT PERFORMED	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

PRE-OPERATION SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

CAUTION

FLT HALF QD IS FLOATING.
FLT HALF QD MUST BE CENTERED
PRIOR TO ATTEMPTING MATE
WITH GSE.

PD10 IS KEYED WITH TWO
SLOTS AT 90 DEGREE
INTERVALS. ORIENT FLT HALF
TO GND HALF PRIOR TO
INSTALLATION.

THE FOLLOWING STEPS MUST
BE WORKED IN ORDER TO
PREVENT INADVERTANT
CONNECTION OF WRONG GROUND
HALF TO ORBITER DISCONNECTS
AS PD10 AND PD14 ARE
PHYSICALLY IDENTICAL AND
COULD BE SWITCHED.

01-015

VERIFY 79K10547-HE10 FLEXHOSE IS CONNECTED
TO (0-2) A105347 I/F PNL PORT (SEE
FIGURES 8 THRU 10).

TQV: _____]

01-016

TRACE FLEXHOSE TO END AND VERIFY
G070-005820-005 GH2 PREPRESS GND QD IS
CONNECTED TO 79K10547-HE10 FLEXHOSE.

TQV: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

PRE-OPERATION SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

WARNING

PERSONNEL INVOLVED IN CLEANING OPERATIONS MUST WEAR RUBBER GLOVES AND IF WORKING ABOVE EYE LEVEL, GOGGLES.

01-017

G070-005820-005 QD

PRIOR TO INSTALLING G070-005820-005 QD, REMOVE ACLAR/TAPE FROM FORWARD END OF G070-005820-005. INSPECT TEFLON NOSE SEAL AND MATING SURFACE, RINSE OFF WITH FREON AND REMOVE ANY RESIDUE WITH LINT FREE CLOTH. VERIFY TWO LOCKING PINS ARE DISENGAGED AND RETENTION FINGERS ARE EXPOSED ON G070-005820-005 QD.

TQW: _____

01-018

LOCATE PD10 ON LH2 T-0 (SEE FIGURE 11).

T: _____

01-019

G070-005820-005 QD

OK TO INSTALL QWN: _____

1. ALIGN AND ENGAGE G070-005820-005 QD TO 50V41PD10 DISCONNECT PUSHING G070-005820-005 IN LINE TO ENGAGE COLLET.
2. MOVE LOCKING PINS TO THE LOCKED POSITION AND VERIFY QD IS FULLY ENGAGED. TURN LOCKING PINS (CW) SNUG.
3. SUPPORT G070-005820-005 QD ASSY IN HORIZONTAL POSITION, USING TIE WRAPS ATTACHED TO CARRIER FRAME.

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

PRE-OPERATION SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
01-020			TORQUE 79K10547-HE10 FLEXHOSE TO INLET OF QD 270-345 IN. LBS. Z _____ DUE DATE _____ VERIFY CSR-242	TQV: _____ TQW: _____
01-021			ORBITER PRE-OPERATION SETUP 3 - PD10 GH2 PREPRESS QD INSTALLATION COMPLETE.	QV: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

PRE-OPERATION SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

SECTION III

OPERATION SUPPORT SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
02-000			OPERATION SUPPORT SETUPS - ORBITER	
02-001			OPERATION SUPPORT SETUP 1 - TP10 HANDVALVE INSTALLATION - OMT0, OQCV, NASA QC	

NOTE

IF REQD BY EFFECTIVITY (1-5
FLIGHTS), PERFORM NEXT STEP
TO INSTALL HANDVALVE AT TP10.

THIS OPERATION SUPPORT SETUP
INSTALLS A HANDVALVE AT GH2
PRESSURIZATION SYSTEM TEST
PORT 50V41TP10 TO SUPPORT
50V41PD10 LH2 PREPRESS QD
REVERSE LEAK CHECK.

OPERATION SUPPORT SETUP 1 NOT PERFORMED

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION SUPPORT SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
02-002			MPS ENG OK TO PROCEED _____	

NOTE

THE FOLLOWING HARDWARE IS
REQD FOR THIS OPERATION
SUPPORT SETUP (CLEAN LVL 100A):

QTY	PART NO.	NOMENCLATURE
1	SSKG250-4T	1/4" HANDVALVE - (ROBBINS OR DRAGON) (1000 PSI MIN)
1	L070-000070-016	1/4 " 90 DEG BACK-TO-BACK
1	C-KC150C4	CAP
1	C-KC133C6-4	REDUCER-ADAPTER
1	C-KC112C4	ADAPTER
1	C-KC103-6	SEAL
2	C-KC103-4	SEAL
2	MS28778-4	O-RING
1	ME286-0068-0008	MINIFILTER (-0001 AND -0015 ARE EQUIV SUBS)

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION SUPPORT SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

TP10 HANDVALVE BUILD-UP

02-003

OMTO

1. INSTALL KC112C4 ADAPTER IN OUTLET PORT OF ROBBINS TYPE (1/4 IN.) HANDVALVE. USE MS28778-4 O-RING.

TORQUE TO 55-80 IN. LBS.

Z _____ DUE DATE _____

2. INSTALL KC133C6-4 REDUCER ADAPTER IN INLET PORT OF (1000 PSI MIN. OPER. PRESS) ROBBINS TYPE 1/4 IN. HANDVALVE USING MS28778-4 O-RING. TORQUE FITTING TO 55-80 IN. LBS.

Z _____ DUE DATE _____

VERIFY CSR-242

TQV: _____
SSI-2

3. BAG HANDVALVE ASSY TO MAINTAIN CLEAN.

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION SUPPORT SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

TP10 PLUG REMOVAL

NOTE

PERFORM THE FOLLOWING TWO STEPS
IF TEST PORT PLUG IS INSTALLED.

02-004	OMTO		VERIFY WITH CMPS THAT THE GH2 PRESSURIZATION SYSTEM IS AT AMBIENT PRESSURE FOR TP10 PLUG REMOVAL.	
--------	------	--	---	--

MPS ENGR CONTACTED _____

TIME/DATE _____/_____

T: _____

NOT PERFORMED _____

NOTE

A ME261-0033-0104 GOLD OR
ME261-0033-0204 LEAD K-SEAL
MAY BE INSTALLED/REMOVED AT
TP10. (SEE FIG 4)

02-005	OMTO		<ol style="list-style-type: none"> 1. SLOWLY LOOSEN BLEEDER PLUG IN TP10 APPROX 2-4 TURNS TO ALLOW LINE TO VENT TO AMBIENT. 2. REMOVE PLUG AT 50V41TP10. DOUBLE BAG AND SEAL PLUG. RETAIN K-SEAL CLEAN FOR INSTALLATION IN NEXT STEP. 3. ATTACH PLUG TO LINE NEXT TO TP10. 	
--------	------	--	---	--

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION SUPPORT SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

02-006

ME286-0068-0008 FILTER

OK TO INSTALL QW: _____

1. INSPECT ME286-0068-0008 MINIFILTER TO VERIFY THAT FILTER SCREEN IS INSTALLED.
2. LUBE MINIFILTER (REF. SPECIAL INSTRUCTIONS 1.7).

INSTALL ME286-0068-0008 MINIFILTER INTO TP10 WITH ME261-0033-0104 OR -0204 SEAL (PREVIOUSLY REMOVED FROM TP10). TORQUE TO 170-200 IN. LBS.

FILTER S/N _____

Z _____ DUE DATE _____

VERIFY CSR-242 TQV: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION SUPPORT SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

HANDVALVE INSTALLATION AT TP10

NOTE

ORIENT HANDVALVE/BACK-TO-BACK
SO THAT A FLEXHOSE/FILTER ASSY.
MAY BE INSTALLED WITHOUT
INTERFERENCE FROM SURROUNDING
STRUCTURE/TUBING.

02-007	OMTO		INSTALL A L070-000070-016 1/4 IN. 90 DEG BACK-TO-BACK ONTO THE KC112C4 ADAPTER AT THE HANDVALVE USING A KC103-4 SEAL. TORQUE TO 135-185 IN. LBS USING A BACKUP WRENCH.	
--------	------	--	--	--

Z_____ DUE DATE_____

VERIFY CSR-242 TQV:_____

TQW:_____

02-008	OMTO		INSTALL L070-000070-016 1/4 IN. BACK-TO-BACK (HAND VALVE ASSY) ONTO MINIFILTER AT TP10 USING A KC103-4 SEAL. TORQUE FITTING TO 135-185 IN. LBS.	
--------	------	--	--	--

Z_____ DUE DATE_____

VERIFY CSR-242 TQV:_____

TQW:_____

02-009	OMTO		INSTALL KC150C6 CAP TO OPEN PORT ON TP10 HANDVALVE WRENCH TIGHT.	
--------	------	--	---	--

T:_____

02-010	OMTO		TP10 HANDVALVE - CLOSE (CW)	
--------	------	--	-----------------------------	--

T:_____

02-011			ORBITER OPERATION SUPPORT SETUP 1 - TP10 HANDVALVE INSTALLATION COMPLETE.	
--------	--	--	--	--

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION SUPPORT SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
02-012			OPERATION SUPPORT SETUP 2 - MPS 1-INCH QD LEAK CHECK TOOL SETUP - OMTD, OQCV	

NOTE

DO NOT PERFORM THIS OPERATION SUPPORT SETUP IF LEAK CHECK TOOL ALREADY CONFIGURED OR IS NOT REQUIRED THIS FLOW.

PD10 LEAK CHECK TOOL IS ONLY REQUIRED TO SUPPORT PD10 CHECKOUT DURING OMDP FLOW OR FOR LRU RETEST. CONTACT MPS ENGR.

OPERATION SUPPORT SETUP 2 NOT PERFORMED

MPS ENGR CONTACTED:

NOTE

THE FOLLOWING HARDWARE IS REQUIRED FOR THIS OPERATION SUPPORT SETUP.

1	KC118C6	90 DEG ELBOW
1	74332026-503	DUST CAP
A/R		TEFLON TAPE

02-013 OMTD OBTAIN FOLLOWING PART FROM MERL

1	KC118C6	90 DEG ELBOW
1	NA	TEFLON TAPE

T: _____

02-014 OMTD OBTAIN ONE 74332026-503 DUST CAP FROM A70-0640-3 MPS CAP AND PLUG SET.

T: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION SUPPORT SETUP INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
02-015	OMTO		REMOVE P7-249(L)-3 RELIEF PLUG AND 3-906 O-RING (CCW), FROM 74332026-503 DUST CAP. BAG AND RETAIN PLUG FOR FUTURE INSTALLATION (SEE FIGURE 16).	

TQV: _____

NOTE

THE FOLLOWING STEP ALLOWS RE-POSITIONING OF INTERNAL SPRING TO PREVENT INTERFERENCE WITH KC118 ELBOW DURING CAP INSTALLATION.

02-016	OMTO		IF GAP ON INTERNAL SPRING IS NOT POSITIONED DIRECTLY OVER RELIEF PLUG, RE-POSITION SPRING USING SNAP-RING OR NEEDLE NOSE PLIERS.	
--------	------	--	--	--

TQW: _____

NOT PERFORMED

02-017	OMTO		INSTALL A KC118C6, 90 DEG ELBOW, USING TEFLON TAPE ON THREADS, INTO 74332026-503 DUST CAP RELIEF PORT, WRENCH TIGHT. ORIENT ELBOW SO FLOWMETER CAN BE CONNECTED DURING LEAK CHECKS. (SEE FIG 16)	
--------	------	--	--	--

TQW: _____

02-018	OMTO		TEMPORARILY ID THIS DUST CAP AS "MPS 1-IN. QD LEAK CHECK TOOL".	
--------	------	--	---	--

TQW: _____

02-019	OMTO		NOTIFY MPS ENGINEERING THAT OPERATION SUPPORT SETUP 2 - MPS 1-INCH QD LEAK CHECK TOOL SETUP IS COMPLETE.	
--------	------	--	--	--

MPS ENGR CONTACTED: _____

DATE/TIME: _____/_____

T: _____

02-020			ORBITER OPERATION SUPPORT SETUP 2 - MPS 1-INCH QD LEAK CHECK TOOL SETUP COMPLETE.	
--------	--	--	---	--

QV: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

SECTION IV

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
03-000			CALL TO STATION	
03-001	OTC NTD 232 STM 111	NTD STM GYCC	START VOICE RECORDING FOR V1009.007 AS SCHEDULED.	
03-002	OTC 132		ANNOTATE VOICE TAPE DOCUMENT NO. _____ TITLE _____ DATE _____ TIME _____ GMT VEHICLE _____ LOCATION _____	
03-003	OTC	CMQC	REPORT CONSTRAINTS STATUS.	QV: _____
03-004	OTC	CMQC	VERIFY PRE-OPERATION SETUPS REQUIRED FOR CALL TO STATION ARE RECORDED AS COMPLETE IN QUALITY SUMMARY SHEET.]]] QV: _____
03-005	NTD PA	ALL	PERSONNEL PARTICIPATING IN V1009.007 GO TO COMMAND CHANNEL 168 AND STAND BY FOR STATUS CHECKS OF TEST READINESS.	
03-006	OTC		REPORT TEST READINESS STATUS. CMPS _____ MAIN PROPULSION SYS ENG (LSOC) OMTO _____ MECHANICAL TECH ORBITER (OPF)	
03-007	OTC	ALL	VERIFY YOUR COPY OF V1009.007 IS REV LEVEL ____.	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
03-008	NTD 232	LPS	VERIFY LPS READY TO SUPPORT V1009.007. RECORD TCID NO. _____. RECORD SYSTEM OPERATIONS SOFTWARE NO. _____.	
03-009	NTD	OTC	PROCEED WITH V1009.007 AND REPORT WHEN MILESTONES COMPLETE.	
03-010	NTD *SCC	*SCC *OSE	VERIFY READINESS TO SUPPORT V1009.007 REV ____.	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
04-000			GH2 FLOW CONTROL VALVE SIGNATURE TRACE	

NOTE

THE FOLLOWING STEPS WILL PERFORM ELECTRICAL (CURRENT) SIGNATURE TRACES OF THE GH2 FLOW CONTROL VALVES.

THE STEPS IN THIS SEQUENCE MAY BE WORKED OUT OF ORDER AT THE DIRECTION OF MPS ENGINEERING.

THE FOLLOWING EQUIPMENT WILL BE SUPPLIED BY MPS ENGINEERING.

- 1 TEKTRONIX 2220 OSCILLOSCOPE
- 1 TEKTRONIX HC100 PLOTTER

EFFECTIVITY: REF SECTION 1.8

04-001 CMPS IF THE GH2 SYSTEM IS NOT AT AMBIENT PRESSURE, PERFORM "GH2 PREPRESS VENTING AND SECURING THRU PD16 (OPF)" PER OMI V1171VL1, OR THIS OMI.
RT OMI LOG NO. _____

NOT PERFORMED

04-002 CMPS CRT (VAE20)
RECORD GH2 SYSTEM PRESSURE:
GH2 SYS PRESSURE _____ PSIA BD

04-003 OQCV THE FOLLOWING CRITICAL SKILL IS REQUIRED FOR PERFORMANCE OF THIS SEQUENCE.

VERIFY CSR-403 TQV: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
04-004	OETO		VERIFY THE FOLLOWING EQUIPMENT IS ON HAND: 1 HP428B AMPMETER (CLAMP-ON) Z _____ DUE DATE _____	

T: _____

NOTE

IF GH2 FLOW CONTROL VALVE
ELECTRICAL CONNECTORS ARE
MATED DO NOT PERFORM NEXT
THREE STEPS.

04-005	CMPS		CONSOLE KYBD SAE12 PERF PGM KEY - PRESS	
--------	------	--	---	--

NOT PERFORMED _____

NOTE

FOLLOWING STEP PROVIDES
ELECTRICAL CONNECTOR SAFING
FOR ELECTRICAL CONNECTOR
MATING.

04-006	CMPS		CRT (SAE12) VERIFY ET OI POWER IS OFF	
--------	------	--	--	--

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
04-007	OETO		IF NOT MATED, MATE THE FOLLOWING CONNECTORS:	
			OK TO MATE	QW: _____
			1. 50V77W90P787 TO 50V41LV56J1	
			SCAN LOG NO. _____	
			NOT PERFORMED	_____
				SS1
			2. 50V77W91P788 TO 50V41LV57J1	
			SCAN LOG NO. _____	
			NOT PERFORMED	_____
				SS2
			3. 50V77W31P789 TO 50V41LV58J1	
			SCAN LOG NO. _____	
			NOT PERFORMED	_____
				SS3
			VERIFY CSR-028	TQV: _____
				TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
04-008	CMPS	OETO	SET UP TEK 2220 OSCILLOSCOPE AS FOLLOWS:	
			1. AUTO SW - IN	
			2. DISPLAY SW - OUT	
			3. SAVE REF SW - OUT	
			4. PRETRIG SW - IN	
			5. POSTTRIG SW - IN	
			6. SAVE SW - OUT	
			7. STORE SW - IN	
			8. INTENSITY - SET ON MEDIUM	
			9. CH1 VERTICAL MODE SW - CH1	
			10. X-Y SW - OUT	
			11. BW LIMIT SW - OUT	
			12. ADD-ALT-CHOP SW - ALT	
			13. VOLTS/DIV - 1X.1	
			14. AC-GND-DC - DC	
			15. SEC/DIV - 10 MS	
			16. <-POSITION-> - MIDDLE	
			17. STORE ONLY SW - OUT	
			18. TRIGGER VAR HOLD OFF - MIDDLE	
			19. TRIGGER ROLL/SGL SWP SW - OUT	
			20. TRIGGER ROLL/P-P AUTO SW - OUT	
			21. TRIGGER SCAN/NORM SW - OUT	
			22. TRIGGER SLOPE IN/OUT - OUT	
			23. TRIGGER LEVEL - TURN SLIGHTLY RIGHT OF CENTER	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
04-008 CON'T			24. TRIGGER INT SW - CH1 25. TRIGGER SOURCE SW - INT 26. TRIGGER EXT COUPLING - DC	T: _____
04-009	RMPS	OETO	IF NOT MATED, MATE HP428B OUTPUT TO OSCILLOSCOPE PROVIDED BY MPS ENGINEERING.	TV: _____
			NOT PERFORMED	_____
04-010		OETO	MATE HP1B INTERFACE CABLE FROM TEK 2220 OSCILLOSCOPE TO HC100 PLOTTER.	TQV: _____
04-011	CMPS		IF NOT ACTIVE: CONSOLE KYBD (C4) VAE43 PERF PGM KEY - PRESS GO TO PG B	_____
			NOT PERFORMED	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.

ENGINE 1 GH2 FLOW CONTROL VALVE SIGNATURE TRACES				

NOTE

NOTED REQUIREMENT IS SATISFIED
BY COMPLETION OF TWO OF THE
NEXT NINE STEPS.

OMRS V41AD0.100-A

04-012 RMPS OETO LOCATE GH2 FLOW CONTROL VALVE LV56 AND
INSTALL HP428B CLAMP-ON AMPMETER AROUND
EITHER SOLENOID WIRE. IF CURRENT POLARITY
IS REVERSED DURING VALVE CYCLE AS INDICATED
BY NEGATIVE DEFLECTION OF NEEDLE ON HP428B,
TURN CLAMP 180 DEG ON WIRE.

TQW: _____

CAUTION

NO MORE THAN ONE GH2 FLOW
CONTROL VALVE CAN BE ENERGIZED
AT ANY ONE TIME. TOTAL
ENERGIZED TIME CAN NOT EXCEED
20 MINUTES IN A THREE HOUR
PERIOD.

NOTE

FLOW CONTROL VALVE IS TO
REMAIN ENERGIZED WHILE
OBTAINING ENERGIZED VALVE
TRACE.

PGM VAE43 HAS BUILT-IN
HARDWARE PROTECTION TO
PRECLUDE CUMMULATIVE POWER
ON TIME EXCEEDING 20
MINUTES.

REF OMRS V41GEN.060

04-013 CMPS CURSOR CNTL (VAE43)
E-1 GH2 FCV (LV56) - ENERGIZE

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
04-014	RMPS	OQCV	ONCE AN ACCEPTABLE SIGNATURE TRACE IS OBTAINED, TAKE A PLOT OF THE TRACE WITH PLOTTER PROVIDED. RECORD REQUIRED DATA ON PLOT PER MPS ENGR DIRECTION. OMRS V41AD0.100-A	TQWN: _____
NOTE				
IN NEXT STEP, CYCLING STORE SWITCH RESETS OSCILLOSCOPE.				
04-015	RMPS	OETO	POSITION OSCILLOSCOPE SWITCH: SLOPE SW - IN STORE SW - OUT STORE SW - IN	TQW: _____
04-016	CMPS		CURSOR CNTL (VAE43) E-1 GH2 FCV (LV56) - DE-ENERGIZED	
04-017	RMPS	OQCV	ONCE AN ACCEPTABLE SIGNATURE TRACE IS OBTAINED, TAKE A PLOT OF THE TRACE WITH PLOTTER PROVIDED. RECORD REQUIRED DATA ON PLOT PER MPS ENGR DIRECTION. OMRS V41AD0.100-A	TQWN: _____
04-018	RMPS	OETO	POSITION OSCILLOSCOPE SWITCH: SLOPE SW - OUT STORE SW - OUT STORE SW - IN	TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

PREVIOUS SIX STEPS WILL BE REPEATED FOUR TIMES TO ENSURE ACCEPTABLE TRACES ARE OBTAINED.

04-019 OQCV FOLLOWING MATRIX WILL BE FILLED OUT FOR RUNS 2 THROUGH 5 OF THE PREVIOUS SIX STEPS.

	RUN 2	RUN 3	RUN 4	RUN 5
CMPS	_____	_____	_____	_____
TQWN:	_____	_____	_____	_____
TQW:	_____	_____	_____	_____
CMPS	_____	_____	_____	_____
TQWN:	_____	_____	_____	_____
TQW:	_____	_____	_____	_____

04-020 OETO REMOVE CLAMP-ON AMPMETER FROM SOLENOID WIRE ON LV56.

T: _____

04-021 COMPLETION OF TWO OF THE PREVIOUS NINE STEPS SATISFIES NOTED OMRS REQUIREMENT.

OMRSD V41AD0.100-A

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

ENGINE 2 GH2 FLOW CONTROL VALVE SIGNATURE TRACES

NOTE

NOTED REQUIREMENT IS SATISFIED BY COMPLETION OF TWO OF THE NEXT NINE STEPS.

OMRS V41AD0.100-B

04-022	RMPS OETO		LOCATE GH2 FLOW CONTROL VALVE LV57 AND INSTALL HP428B CLAMP-ON AMPMETER AROUND EITHER SOLENOID WIRE. IF CURRENT POLARITY IS REVERSED DURING VALVE CYCLE AS INDICATED BY NEGATIVE DEFLECTION OF NEEDLE ON HP428B TURN CLAMP 180 DEG ON WIRE.	
--------	-----------	--	---	--

TQW: _____

CAUTION

NO MORE THAN ONE GH2 FLOW CONTROL VALVE CAN BE ENERGIZED AT ANY ONE TIME. TOTAL ENERGIZED TIME CAN NOT EXCEED 20 MINUTES IN A THREE HOUR PERIOD.

NOTE

FLOW CONTROL VALVE IS TO REMAIN ENERGIZED WHILE OBTAINING ENERGIZED VALVE TRACE.

PGM VAE43 HAS BUILT-IN HARDWARE PROTECTION TO PRECLUDE CUMMULATIVE POWER ON TIME EXCEEDING 20 MINUTES.

REF OMRS V41GEN.060

04-023	CMPS		CURSOR CNTL (VAE43)	
			E-2 GH2 FCV (LV57) - ENERGIZE	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
04-024	RMPS	OQCV	ONCE AN ACCEPTABLE SIGNATURE TRACE IS OBTAINED, TAKE A PLOT OF THE TRACE WITH PLOTTER PROVIDED. RECORD REQUIRED DATA ON PLOT PER MPS ENGR DIRECTION. OMRS V41AD0.100-B	TQWN: _____
04-025	RMPS	OETO	POSITION OSCILLOSCOPE SWITCH: SLOPE SW - IN STORE SW - OUT STORE SW - IN	TQW: _____
04-026		CMPS	CURSOR CNTL (VAE43) E-2 GH2 FCV (LV57) - DE-ENERGIZED	
04-027	RMPS	OQCV	ONCE AN ACCEPTABLE SIGNATURE TRACE IS OBTAINED, TAKE A PLOT OF THE TRACE WITH PLOTTER PROVIDED. RECORD REQUIRED DATA ON PLOT PER MPS ENGR DIRECTION. OMRS V41AD0.100-B	TQWN: _____
04-028	RMPS	OETO	POSITION OSCILLOSCOPE SWITCH: SLOPE SW - OUT STORE SW - OUT STORE SW - IN	TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

PREVIOUS SIX STEPS WILL BE REPEATED FOUR TIMES TO ENSURE ACCEPTABLE TRACES ARE OBTAINED.

04-029 OQCV FOLLOWING MATRIX WILL BE FILLED OUT FOR RUNS 2 THROUGH 5 OF THE PREVIOUS SIX STEPS.

	RUN 2	RUN 3	RUN 4	RUN 5
CMPS	_____	_____	_____	_____
TQWN:	_____	_____	_____	_____
TQW:	_____	_____	_____	_____
CMPS	_____	_____	_____	_____
TQWN:	_____	_____	_____	_____
TQW:	_____	_____	_____	_____

04-030 OETO REMOVE CLAMP-ON AMPMETER FROM SOLENOID WIRE ON LV57.

T: _____

04-031 COMPLETION OF TWO OF THE PREVIOUS NINE STEPS SATISFIES NOTED OMRS REQUIREMENT.

OMRSD V41AD0.100-B

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.

ENGINE 3 GH2 FLOW CONTROL VALVE SIGNATURE TRACES				

NOTE

NOTED REQUIREMENT IS SATISFIED BY COMPLETION OF TWO OF THE NEXT NINE STEPS.

OMRS V41AD0.100-C

04-032 RMPS OETO LOCATE GH2 FLOW CONTROL VALVE LV58 AND INSTALL HP428B CLAMP-ON AMPMETER AROUND EITHER SOLENOID WIRE. IF CURRENT POLARITY IS REVERSED DURING VALVE CYCLE AS INDICATED BY NEGATIVE DEFLECTION OF NEEDLE ON HP428B, TURN CLAMP 180 DEG ON WIRE.

TQW: _____

CAUTION

NO MORE THAN ONE GH2 FLOW CONTROL VALVE CAN BE ENERGIZED AT ANY ONE TIME. TOTAL ENERGIZED TIME CAN NOT EXCEED 20 MINUTES IN A THREE HOUR PERIOD.

NOTE

FLOW CONTROL VALVE IS TO REMAIN ENERGIZED WHILE OBTAINING ENERGIZED VALVE TRACE.

PGM VAE43 HAS BUILT-IN HARDWARE PROTECTION TO PRECLUDE CUMMULATIVE POWER ON TIME EXCEEDING 20 MINUTES.

REF OMRS V41GEN.060

04-033 CMPS CURSOR CNTL (VAE43)
E-3 GH2 FCV (LV58) - ENERGIZE

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
04-034	RMPS	OQCV	ONCE AN ACCEPTABLE SIGNATURE TRACE IS OBTAINED, TAKE A PLOT OF THE TRACE WITH PLOTTER PROVIDED. RECORD REQUIRED DATA ON PLOT PER MPS ENGR DIRECTION. OMRS V41AD0.100-C	TQWN: _____
04-035	RMPS	OETO	POSITION OSCILLOSCOPE SWITCH: SLOPE SW - IN STORE SW - OUT STORE SW - IN	TQW: _____
04-036		CMPS	CURSOR CNTL (VAE43) E-3 GH2 FCV (LV58) - DE-ENERGIZED	
04-037	RMPS	OQCV	ONCE AN ACCEPTABLE SIGNATURE TRACE IS OBTAINED, TAKE A PLOT OF THE TRACE WITH PLOTTER PROVIDED. RECORD REQUIRED DATA ON PLOT PER MPS ENGR DIRECTION. OMRS V41AD0.100-C	TQWN: _____
04-038	RMPS	OETO	POSITION OSCILLOSCOPE SWITCH: SLOPE SW - OUT STORE SW - OUT STORE SW - IN	TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

PREVIOUS SIX STEPS WILL BE REPEATED FOUR TIMES TO ENSURE ACCEPTABLE TRACES ARE OBTAINED.

04-039 OQCV FOLLOWING MATRIX WILL BE FILLED OUT FOR RUNS 2 THROUGH 5 OF THE PREVIOUS SIX STEPS.

	RUN 2	RUN 3	RUN 4	RUN 5
CMPS	_____	_____	_____	_____
TQWN:	_____	_____	_____	_____
TQW:	_____	_____	_____	_____
CMPS	_____	_____	_____	_____
TQWN:	_____	_____	_____	_____
TQW:	_____	_____	_____	_____

04-040 OETO REMOVE CLAMP-ON AMPMETER FROM SOLENOID WIRE ON LV58.

T: _____

04-041 COMPLETION OF TWO OF THE PREVIOUS NINE STEPS SATISFIES NOTED OMRS REQUIREMENT.

OMRSD V41AD0.100-C

04-042 OETO RETURN HP428B CLAMP-ON AMPMETER TO STOCK.

T: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

ENGINEERING DATA REVIEW/ACCEPTANCE

NOTE

ASSESSMENT OF CURRENT TRACES
FOR EACH VALVE WILL BE
PERFORMED BY RI-DOWNEY AND
JSC SSM/EP2.

04-043	QOCV		ROUTE ALL SIGNATURE TRACES TO MPS ENGINEERING FOR FORWARDING TO ROCKWELL/DOWNEY MPS DESIGN AND NASA JSC-SSM FOR DATA ASSESSMENT.	
--------	------	--	--	--

QV: _____

04-044			RECORD ENGINEERING ACCEPTABILITY OF GH2 FLOW CONTROL VALVE SIGNATURE TRACES.	
--------	--	--	--	--

RESULTS: _____
(ACCEPTABLE/UNACCEPTABLE)

LSOC-MPS ENGINEER _____

RI-LSS ENGINEER _____

04-045			GH2 FLOW CONTROL VALVE SIGNATURE TRACES COMPLETE.	
--------	--	--	---	--

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
05-000			ORBITER GH2 MPS FLOW CONTROL VALVE AUTO CHECKOUT VERIFICATION	

EFFECTIVITY: (REF SECTION 1.8)

NOTE

FLOW CONTROL VALVE SOLENOIDS WILL BE ENERGIZED. THIS SEQUENCE USES PGM VAE43 WHICH COMPLIES WITH FCV CONSTRAINTS PER OMRS V41GEN.060.

OPERATIONS INVOLVING CRIT 1 AND/OR 1R ITEMS ARE CONTAINED IN THE FOLLOWING SEQUENCE/STEPS.

PERFORM NEXT STEP IF PGM VAE43 IS NOT ACTIVE.

COMPLETION OF THIS SEQUENCE SATISFIES NOTED REQUIREMENTS.

OMRS V41AD0.010]
OMRS V41AD0.020]
OMRS V41AD0.030]

05-001	CMPS	CONSOLE KYBD (C4) VAE43 PERF PGM KEY - PRESS SELECT APPLICATIONS PAGE-B
--------	------	--

NOT PERFORMED

05-002	CMPS	CONSOLE KYBD (C4) IF NOT ACTIVE SAE12 PERF PGM KEY - PRESS
--------	------	--

NOT PERFORMED

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

PERFORM NEXT TWO STEPS
IF C70-0796 OR E70-0036 ET
SIMULATORS ARE MATED TO
VEHICLE.

NEXT STEP PROVIDES ELECTRICAL
CONNECTOR SAFING FOR CONNECTOR
DEMATE. SCAN LOG NUMBERS ARE
NOT REQUIRED FOR GSE ELECTRICAL
CONNECTOR DEMATE.

05-003	CMPS		CRT (SAE12) VERIFY ET OI POWER IS DOWN	NOT PERFORMED
--------	------	--	--	---------------

05-004	CMPS	OETO	DEMATE 50V77W12P523 AND 50V77W12P533 CONNECTORS FROM C70-0796/E70-0036 ET SIMULATOR. VERIFY CSR-028	TQV: _____ TQV: _____ NOT PERFORMED
			ET OI PWR - ON	_____

05-005	CMPS		PFPK (SAE12) - PRESS TURN ON ET PWR - PRESS VERIFY ET OI PWR ON	
--------	------	--	---	--

05-006	CMPS	OTC OTC *ACM	IF AFT FUSELAGE IS OCCUPIED, NOTIFY PERSONNEL THAT MPS SOLENOIDS WILL BE CYCLED INTERMITTENTLY FOR APPROXIMATELY 10 MINUTES AND MECHANICAL NOISES WILL OCCUR. NOT PERFORMED	_____
--------	------	-----------------	---	-------

05-007	CMPS	OTC	CDR SUPPORT FOR MPS FLOW CONTROL VALVE CHECKOUT IS REQUIRED ON CHANNEL 168. CHECKOUT WILL LAST FOR APPROX. 10 MINUTES.	_____
--------	------	-----	--	-------

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

THE FOLLOWING STEP PERFORMS
ORBITER MPS FLOW CONTROL VALVE
VERIFICATION USING CHECKOUT
COMMANDS.

CDR SUPPORT IS REQUIRED FOR
NEXT STEP. DO NOT PROCEED
UNTIL CDR REPORTS ON STATION.

05-008	CMPS		CURSOR CNTL (VAE43) CURSOR TO "AUTO CHECKOUT (ELECTRONIC BOX)" XMIT CURSOR KEY - PRESS	
--------	------	--	--	--

NOTE

PERFORM/NOT PERFORM NEXT
TWO STEPS AS REQUIRED TO
SUPPORT FURTHER CHECKOUT
(SIGNAL COND - ON) OR
SECURING (SIGNAL COND - OFF).

05-009	CMPS		CURSOR CNTL (VAE43) TERMINATE (SIGNAL COND ON)	
--------	------	--	---	--

NOT PERFORMED _____

05-010	CMPS		CURSOR CNTL (VAE43) TERMINATE (SIGNAL COND OFF)	
--------	------	--	--	--

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
			ET OI PWR - OFF	
05-011	CMPS		IF ET OI PWR IS ON AND OI NOW REQUIRED OFF: PFPK (SAE12) - PRESS TURN OFF ET PWR - PRESS	NOT PERFORMED
			NOTE	
			NEXT STEP PROVIDES ELECTRICAL CONNECTOR SAFING IF THE C70-0796 OR E70-0036 ET SIMULATORS MUST BE MATED TO THE ORBITER. SCAN LOG NUMBERS ARE NOT REQUIRED FOR GSE ELECTRICAL CONNECTOR MATE.	
05-012	CMPS		CRT (SAE12) VERIFY ET OI POWER IS DOWN	NOT PERFORMED
05-013	CMPS	OETO	IF DEMATED PER THIS SEQUENCE AND REQUIRED FOR FURTHER TESTING, MATE 50V77W12P523 AND 50V77W12P533 CONNECTORS TO C70-0796 OR E70-0036 ET SIMULATOR.	VERIFY CSR-028 TQV:____ TQW:____ NOT PERFORMED
05-014	CMPS		ORBITER MPS FLOW CONTROL VALVE AUTO CHECKOUT VERIFICATION COMPLETE.	
05-015			COMPLETION OF THIS SEQUENCE SATISFIES NOTED OMRS REQUIREMENTS. OMRSD V41AD0.010-1R OMRSD V41AD0.020-1R OMRSD V41AD0.030-1R	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
06-000			GH2 PRESSURIZATION SYSTEM DECAY CHECK - CMPS, RMPS, RTH2, OMT0 AND OQCV	

NOTE

THIS SEQUENCE SATISFIES
 OMRS V41AY0.200 IFC AND/
 OR V41BB0.020, THEY ARE
 CONTINGENCY OMRS. DO
 NOT PERFORM THIS SEQUENCE
 IF NO LEAKAGE/LRU REPLACEMENT
 IS PERFORMED.

]]]

ENTIRE SEQUENCE NOT PERFORMED

STEPS AND SUBSTEPS WITHIN
 THIS SEQUENCE MAY BE WORKED
 OUT OF NUMERICAL ORDER AS
 DETERMINED BY MPS ENGINEERING.

OPERATIONS INVOLVING CRIT 1
 AND/OR 1R ITEMS ARE CONTAINED
 IN THE FOLLOWING SEQUENCE/STEPS.

06-001 VERIFY ALL GH2 SYSTEM LEAK AND FUNCTIONAL
 CHECKS WHICH CAN EFFECT DECAY TEST ARE COMPLETE.

MPS ENGR _____ DATE _____

NOTE

THE FOLLOWING EIGHT STEPS
 ESTABLISH SYSTEM CONFIGURATION
 FOR DECAY CHECK.

06-002 CMPS RMPS VERIFY PD10 GH2 PREPRESS QD INSTALLED AT LH2
 T-0 (SEG FIG 11).

06-003 CMPS *PAD VERIFY LEFT HAND ET DOOR IS OPEN AND WILL
 REMAIN OPEN FOR THIS TEST.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
06-004	OMTO		IF REQUESTED BY MPS ENGR, AND GH2 TEST PLATE IS NOT INSTALLED, PERFORM "PD5 GH2 2 IN. ORB/ET DISC COVER PLATE INSTALLATION" PER OMI V1171VL1. RT OMI LOG NO: _____	NOT PERFORMED _____
06-005	OMTO		IF TEST PLATE IS INSTALLED AT MPS ORB/ET QD PD5, AND TEST PORT IS CAPPED, VERIFY POPPET ACUATOR BOLT IS FULLY RETRACTED (CCW) THEN REMOVE CAP ASSY. BAG AND SEAL CAP. LEAVE PORT OPEN TO VENT (PD5 SEAT LEAKAGE). TQV: _____	NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

PD16 - CONFIGURE

NOTE

THE PD16 GROUND HALF COUPLING
MAY BE DEMATED FROM THE FLIGHT
HALF WITH PRESSURE IN THE
GH2 SYSTEM.

06-006	CMPS	OMTO	IF GSE FLEXHOSE/QD INSTALLED, REMOVE GW70-420958-002 GROUND HALF COUPLING FROM 50V41PD16 DISCONNECT BY TURNING (CCW) MAINTAIN CLEANLINESS. INSTALL GRND PLUG INTO GW70-420958-002 (CW) SNUG. DO NOT INSTALL FLIGHT CAP. LOOSELY BAG AND SEAL FLIGHT HALF QD.	
--------	------	------	--	--

TQW: _____

NOT PERFORMED _____

06-007	CMPS	OMTO	IF INSTALLED, REMOVE FLIGHT CAP FROM 50V41PD16 BY TURNING (CCW). MAINTAIN CLEANLINESS. LOOSELY BAG AND SEAL.	
--------	------	------	--	--

TQW: _____

NOT PERFORMED _____

06-008	CMPS		IF LH2 MANIFOLD IS NOT AT AMBIENT PRESSURE, PERFORM "LH2 MANIFOLD VENTING THRU FILL/ DRAIN LINE (OPF)" PER OMI V1171VL1.	
--------	------	--	--	--

RT OMI LOG NO. _____

NOT PERFORMED _____

06-009	CMPS	RSME	VERIFY SSME HOT GAS SYSTEMS ARE VENTED ON ALL THREE ENGINES AND WILL REMAIN VENTED UNTIL COMPLETION OF GH2 DECAY TEST.	
--------	------	------	--	--

SSME ENGR _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.

GH2 SYSTEM PRESSURIZATION				

06-010		CMPS	IF NOT ACTIVE, PERFORM GH2 PREPRESS SYSTEM PRESSURIZATION (OPF)" PER OMI V1171VL1, OR THIS OMI. PRESSURIZE SYSTEM TO 400 +/- 25 PSIG. RT OMI LOG NO. _____	
				NOT PERFORMED _____
06-011		CMPS	CRT (VAE20) VERIFY ORBITER PRESSURE READS 400 +/- 25 PSIG. VERIFY NO INCREASE IN LH2 MANIFOLD PRESSURE. RECORD LH2 PRESS _____ PSIA BD RECORD GMT _____	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

IF TEST PLATE IS INSTALLED,
PERFORM NEXT STEP TO MONITOR
PD5 SEAT LEAKAGE FOR ENGINEERING
BASELINE DATA (BD). NEXT STEP
MAY BE PERFORMED IN PARALLEL
WITH DECAY TEST. ENTER "N/A"
FOR DATA NOT REQUIRED.

NEXT STEP MAY BE PERFORMED
AT MPS ENGINEERING DISCRETION.

PD5 - 400 PSI SEAT LEAK TEST (BD)

06-012 CMPS OMT0 CONNECT C70-0903 FLOWMETER TO TEST PLATE
TEST PORT AT PD5. REPORT READING AT INTERVALS
PER CMPS.

Gh2 PRESS V41P1490A1 (CRT-PSIA)	TUBE NO./SCALE	LEAK RATE (SCIMS GHE) BD	TUBE Z NO. / DUE DATE
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

TQW: _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
06-013		CMPS	CRT (VAE20)	
			VERIFY GH2 PRESSURIZATION SYSTEM HAS STABILIZED AT 400 +/- 25 PSI FOR 10 MINUTES MINIMUM	

NOTE

THE GH2 DECAY TEST STARTS
WHEN A83143 GAGE INDICATES
ZERO PSIG.

06-014	CMPS	RTH2	S70-0695-8 PNL	
			A83115 REG - FULL DECREASE (CCW)	
			A83070 VENT VALVE - OPEN (CCW)	
			VERIFY PRESSURE BETWEEN T-0 UMBILICAL AND PANEL VENTS TO 0 PSIG ON GAGE A83143.	
			RECORD GMT _____	

TQW: _____

06-015	CMPS		CURSOR CNTL (VAE20)	
			VERIFY ORBITER GH2 SYSTEM PRESSURE INDICATES 400 +/- 25 PSIG.	
			A83134 LH2 PREPRESS SOV - CLOSE	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

INITIAL VALUES

06-016	CMPS		MONITOR LH2 MANIFOLD AND GH2 DISC PRESSURES AND RECORD RESULTS BELOW.	
--------	------	--	---	--

DECAY TEST START _____ GMT

- GH2 DISC PRESS
V41P1490A1 _____ PSIA BD
- LH2 MANIFOLD PRESS
V41P1433C1 _____ PSIA BD

NOTE

MONITOR GH2 SYSTEM DECAY FOR FIRST 100 PSI OF DECAY OR 20 MINUTES, WHICHEVER COMES FIRST. DECAY MAY BE MONITORED FOR MORE THAN 20 MINUTES AT MPS ENGINEERING DISCRETION.

FINAL VALUES

06-017	CMPS		PERFORM CDS DATA RETRIEVAL ON V41P1490A1 AND RECORD ACTUAL GH2 SYSTEM DECAY RATE.	
--------	------	--	---	--

DECAY TEST FINISH _____ GMT

- GH2 DISC PRESS
V41P1490A1 _____ PSIA BD
- LH2 MANIFOLD PRESS
V41P1433C1 _____ PSIA BD
- CALCULATE GH2 DISC PRESSURE DECAY RATE (ACTUAL)

ACTUAL DECAY RATE = _____ PSI/MINUTE

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

MAX ALLOWABLE DECAY CALCULATION

06-018

MAXIMUM ALLOWABLE DECAY IS EQUAL TO
0.031 X (15+C+D) WHERE:

NOTE

CV21, 22, 23 NET LEAKAGE TO
SSME'S DURING DECAY CHECK
ARE TO BE RECORDED AS FOLLOWS:

IF EITHER FWD OR AFT PORTION
OF CHECK VALVE LEAKED 0 SCIM
THE NET LEAKAGE EQUALS 0 SCIM.

IF THE FWD AND AFT CHECK VLV
LEAKAGES ARE BOTH GREATER THAN
0 SCIM, THE NET LEAKAGE
RECORDED MUST BE THE LOWER OF
TWO LEAK RATES.

PD5/LV52 LEAKAGE WILL BE TAKEN
FROM HISTORICAL DATA IF REAL
TIME LEAK CHECK WAS NOT
PERFORMED THIS FLOW.

C = SUM OF LAST RECORDED READINGS FROM
CV21, CV22, CV23 REVERSE LEAK CHECKS
(NET LEAKAGE TO SSME'S)

D = PD5/LV52 - 400 PSIG AVERAGE LEAK RATE

CV21 _____ SCIM

CV22 _____ SCIM

CV23 _____ SCIM

C = _____ SCIM

D = _____ SCIM

CALCULATE/RECORD MAXIMUM ALLOWABLE GH2

DECAY RATE _____ PSI/MINUTE

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
06-019	CMPS		RECORD AND VERIFY ACTUAL DECAY IS LESS THAN OR EQUAL TO MAX ALLOWABLE DECAY RATE. ACTUAL GH2 SYSTEM DECAY _____ PSI/MIN ALLOWABLE GH2 SYS DECAY _____ PSI/MIN OMRSD V41AY0.200-1 PD16 RECONFIGURE -----	

NOTE

PD16 GRND HALF COUPLING
IS DESIGNED TO BE MATED
WITH SYSTEM PRESSURIZED.

06-020	OMTO		REMOVE PLUG (CCW) FROM GW70-420958-002 GND HALF COUPLING. MAINTAIN SYSTEM CLEANLINESS (REF MA0110-311).	TQW: _____
06-021	OMTO		REMOVE BAG/TAPE FROM FLT HALF 50V41PD16.	TQW: _____
06-022	OMTO		GW70-420958-002 QD/FILTER ASSY OK TO INSTALL	QW: _____

1. PRIOR TO INSTALLING, VISUALLY INSPECT GROUND HALF AND FLIGHT HALF FOR DAMAGE OR CONTAMINATION. NO ANOMALIES ALLOWED. VERIFY NO PARTICULATES USING WHITELIGHT INSPECTION.
2. CONNECT QD/FILTER ASSY TO PD16 INSIDE AFT FUSELAGE. INSTALL GROUND HALF TURNING (CW). TORQUE TO 15-20 IN. LBS.

Z _____ DUE DATE _____

VERIFY CSR-242 TQV: _____

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
06-023		OMTO	CONNECT FLIGHT HALF DUST CAP AND GND PLUG TOGETHER FINGER TIGHT.	

T: _____

PD5 - 100 PSI GH2 PRESSURIZATION

 DISCONNECT AND LV52 SEAT LEAK TEST

NOTE

PD5 - 100 PSI GH2
 PRESSURIZATION DISCONNECT
 AND LV52 SEAT LEAK TEST (NEXT
 FOUR STEPS) PERFORMED ONLY
 IF REQUIRED. CONTINGENCY
 REQUIREMENT TO BE PERFORMED
 AFTER LRU REPLACEMENT OR IF
 LEAKAGE IS SUSPECTED (REF
 OMRS V41BB0.020).

ENTIRE SEQUENCE NOT PERFORMED _____

EFFECTIVITY: (REF SECTION 1.8)

06-024	CMPS	OMTO	IF NOT INSTALLED, INSTALL G070-005861 TEST PLATE ONTO PD5 DISCONNECT PER: JC V41-50008 - TEST PLATE, PD5 GH2 2 IN. CLEANING/INSPECTION/INSTALLATION	
--------	------	------	---	--

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

PERFORM NEXT STEP ONLY IF
PRESSURE HAS NOT YET DECAYED
TO 100 +/- 20 PSIG AND PD16
GROUND HALF QD IS INSTALLED.
IF PD5/LV52 LEAKAGE OF 100
SCIM IS EXCEEDED, PERFORM
V41BC0.090 TO ISOLATE LV52
INTERNAL LEAKAGE FROM PD5.

06-025 CMPS RTH2 S70-0695-8 PNL

A83070 VLV - OPEN (CCW)
A83145 VLV - OPEN (CCW)

WHEN ORB GH2 PRESS LINE INDICATES 100 +/- 20 PSIG:

A83145 VLV - CLOSE (CW)
A83070 VLV - CLOSE (CW)

TQW: _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.										
06-026	CMPS	OMTO	<p>USING C70-0903 ATMOSPHERIC FLOWMETER, MEASURE COMBINED LEAKAGE AT 2 IN. DISC 50V41PD5 TEST PLATE TEST PORT (100 SCIM MAX).</p> <table border="1"> <thead> <tr> <th>GH2 PRESS (CRT-PSIA)</th> <th>TUBE NO./SCALE</th> <th>LEAK RATE (SCIMS GHE) 100 MAX</th> <th>TUBE Z NO. /</th> <th>DUE DATE</th> </tr> </thead> <tbody> <tr> <td>_____</td> <td>____/____</td> <td>_____</td> <td>_____</td> <td>_____</td> </tr> </tbody> </table>	GH2 PRESS (CRT-PSIA)	TUBE NO./SCALE	LEAK RATE (SCIMS GHE) 100 MAX	TUBE Z NO. /	DUE DATE	_____	____/____	_____	_____	_____	
GH2 PRESS (CRT-PSIA)	TUBE NO./SCALE	LEAK RATE (SCIMS GHE) 100 MAX	TUBE Z NO. /	DUE DATE										
_____	____/____	_____	_____	_____										

OMRSD V41BB0.020-1

TQW: _____]

NOT PERFORMED _____

06-027 CMPS PD5-100 PSI GH2 PRESSURIZATION DISCONNECT AND LV52 SEAT LEAK TEST COMPLETE.

NOT PERFORMED _____

06-028 CMPS IF NO LONGER REQUIRED, PERFORM "MPS GH2 PREPRESS SYSTEM SECURING (OPF)", PER OMI V1171VL1, OR THIS OMI.

RT OMI LOG NO. _____

NOT PERFORMED _____

NOTE

PERFORM NEXT STEP ONLY IF ALL TESTING WITH TEST PLATE IS COMPLETE.

06-029 CMPS OMTO IF THE PD5 TEST PLATE IS INSTALLED, REMOVE GH2 2 IN. TEST PLATE PER:

JC V41-40016 - PLATE, PD5 2 IN. GH2 PREPRESS, REMOVAL

NOT PERFORMED _____

06-030 CMPS OTC GH2 PRESSURIZATION SYSTEM DECAY CHECK COMPLETE.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
07-000			CV24 REVERSE SEAT LEAK CHECKS	

EFFECTIVITY: (V41BA0.052 REF SECTION 1.8)

NOTE

STEPS AND SUBSTEPS WITHIN THIS SEQUENCE MAY BE WORKED OUT OF NUMERICAL ORDER AS DETERMINED BY MPS ENGINEERING.

OPERATIONS INVOLVING CRIT 1 AND/OR 1R ITEMS ARE CONTAINED IN THE FOLLOWING SEQUENCE/STEPS.

HARDWARE REQUIRED

PART NO.	NOMENCLATURE	QUANTITY
MD273-0044-2004	PLUG	1
ME261-0033-0204	K-SEAL	1
C70-0903	FLOWMETER	1

07-001 CMPS IF LH2 MANIFOLD IS NOT AT, OR NEAR AMBIENT PRESSURE, PERFORM "LH2 MANIFOLD VENTING THRU FILL/DRAIN LINE OR THRU RTLS DUMP PORT (OPF)" PER OMI V1171VL1.

RT OMI LOG NO. _____

NOT PERFORMED _____

07-002 CMPS IF ACTIVE AND NOT REQUIRED FOR FURTHER TESTING, PERFORM "ORBITER MPS 750 PSI PNEUMATIC SYSTEM SECURING AND BLOWDOWN THROUGH BLOWDOWN HOSE (OPF)" PER OMI V1171VL1.

RT OMI LOG NO. _____

NOT PERFORMED _____

07-003 CMPS VERIFY LH2 REPRESS SOLENOID VALVES LV42, LV43 ARE CLOSED (DEENERGIZED) AND WILL REMAIN CLOSED FOR THE DURATION OF CV24 LEAK CHECK.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.

TP36 PLUG REMOVAL				

07-004 CMPS OMT0 USING A LINT-FREE CLOTH DAMPENED WITH FREON, WIPE EXTERIOR OF THE PLUG IN TP36 (LOCATED BETWEEN CV24 AND CV13).

TQW: _____

CAUTION

DURING PERFORMANCE OF NEXT STEP A SMALL AMOUNT OF HELIUM MAY VENT. IF VENTING CONTINUES FOR LONGER THAN 30 SECONDS NOTIFY CMPS.

NOTE

THE FOLLOWING STEP IS REQUIRED TO SUPPORT CV24 LEAK CHECKS.

07-005 CMPS OMT0 REMOVE LOCKWIRE AND PLUG FROM TP36. IF PLUG WAS MD273-0032-2004, DISCARD PLUG AND OBTAIN MD273-0044-2004. IF PLUG WAS MD273-0044-2004, RETAIN AND MAINTAIN PLUG CLEAN AND DISCARD SEAL.

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

WARNING

MONITOR TP36 FOR AUDIBLE FLOW.
IF AUDIBLE, OMT0 MUST NOTIFY
CMPS IMMEDIATELY TO VENT GH2
PRESS SYSTEM PER APPENDIX Z -
EMERGENCY GH2 PRESSURIZATION
SYS VENTING THRU S70-0695-8 PNL.

CV24 REVERSE LEAK CHECK

07-006	CMPS		IF NOT ACTIVE, PERFORM GH2 PREPRESS SYSTEM PRESSURIZATION (OPF)" PER OMI V1171VL1 OR THIS OMI. PRESSURIZE SYSTEM TO 400 +/- 25 PSIG.	
--------	------	--	--	--

RT OMI LOG NO. _____

NOT PERFORMED _____

07-007	CMPS OMT0		LEAK CHECK USING C70-0903 FLOWMETER (REF 1.7 SPECIAL INSTRUCTIONS) AT 50V41TP36. RECORD DATA IN APPENDIX A, DATA SHEET A-1 FOR 50V41CV24 (15 SCIM MAX).	
--------	-----------	--	--	--

OMRSD V41BA0.052-1R

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.

TP36 RECONFIGURE/LEAK CHECK -----				
07-008	CMPS	OMT0	PLUG AND SEAL	
			OK TO INSTALL	QW: _____
			INSTALL MD273-0044-2004 PLUG AND NEW ME261-0033-0204 K-SEAL IN TP36. TORQUE TO 170-200 IN. LBS.	
			Z _____ DUE DATE _____	
			INSTALL SAFETY WIRE MS20995N32.	
			VERIFY CSR-242	TQV: _____
				TQW: _____
			NOT PERFORMED	_____
07-009	CMPS		IF LH2 MANIFOLD IS NOT AT AMBIENT PRESSURE PERFORM "LH2 MANIFOLD VENTING THRU FILL/ DRAIN LINE (OPF)" PER OMI V1171VL1.	
			RT OMI LOG NO. _____	
			NOT PERFORMED	_____
07-010	CMPS		PRESSURIZE LH2 MANIFOLD TO 20-30 PSIG BY PERFORMING "MPS LH2, LH2 RECIRC, AND GH2 MANIF PRESSURIZATION TO 25 PSIG USING REPRESS REGS (OPF)" PER OMI V1171VL1.	
			RT OMI LOG NO. _____	
07-011	CMPS		CRT (VAE20)	
			VERIFY LH2 PRESSURIZATION SYSTEM IS PRESSURIZED TO 20-30 PSIG.	
			RECORD LH2 PRESS _____ PSIA	BD
			CONVERT TO _____ PSIG	BD

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

WARNING

ALL PERSONNEL PERFORMING
BUBBLE SOAP LEAK CHECKS
MUST WEAR FACESHIELDS.

07-012	CMPS	OMTO	PERFORM BUBBLE SOAP LEAK CHECKS OF THE JOINT LISTED BELOW. NO BUBBLE FORMATION IN ONE MINUTE ALLOWED.	
--------	------	------	---	--

TP36 BUBBLE SOAP RESULTS: _____

OMRSD V41AY0.380

TQW: _____

07-013	CMPS		IF LH2 MANIFOLD IS NOT AT, OR NEAR AMBIENT PRESSURE, PERFORM "LH2 MANIFOLD VENTING THRU FILL/DRAIN LINE OR THRU RTLS DUMP PORT (OPF)" PER OMI V1171VL1.	
--------	------	--	--	--

RT OMI LOG NO. _____

NOT PERFORMED _____

07-014	CMPS		IF ACTIVE AND NOT REQUIRED FOR FURTHER TESTING, PERFORM "ORBITER MPS 750 PSI PNEUMATIC SYSTEM SECURING AND BLOWDOWN THROUGH BLOWDOWN HOSE (OPF)" PER OMI V1171VL1.	
--------	------	--	---	--

RT OMI LOG NO. _____

NOT PERFORMED _____

07-015	CMPS		CV24 LEAK TEST COMPLETE.	
--------	------	--	--------------------------	--

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
08-000			PD10 AND CV17 - VALIDATION AND INTERNAL LEAK CHECKS - CMPS, OMT0, OQCV, RTH2	

NOTE

STEPS AND SUBSTEPS WITHIN THIS SEQUENCE MAY BE WORKED OUT OF NUMERICAL ORDER AS DETERMINED BY MPS ENGINEERING.

OPERATIONS INVOLVING CRIT 1 AND/OR 1R ITEMS ARE CONTAINED IN THE FOLLOWING SEQUENCE/STEPS.

THE FOLLOWING OMRS' ARE SATISFIED WITHIN THIS SEQUENCE (BY EFFECTIVITY):

	PD10	CV17	PD10/CV17
EFFECTIVITY	I-5 V41BB0.050	I-5 V41BA0.080-B	ALL V41BB0.051

HARDWARE REQUIRED:

QTY	PART NO.	NOMENCLATURE	
1	ME261-0033-0104	K-SEAL (CLN LVL 100A)	(OV-102)
1	ME261-0033-0204	K-SEAL (CLN LVL 100A)	(OV-103 & SUBS)
	OR		
1	ME261-0033-0104	K-SEAL	(OV-103 & SUBS)

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
			NOTE]
			DO NOT PERFORM CPV17/PD10 REV LK VALIDATION IF OMDP OMRS V41BA0.080-B REQUIREMENT IS TO BE MET THIS FLIGHT.]
			CV17/PD10 REV LK VALIDATION]
			-----]
			NOT PERFORMED]
			NOTE]
			NOTED REQUIREMENT IS SATISFIED BY COMPLETION OF FOLLOWING SIX STEPS.]
			OMRS V41BB0.051]
08-001	CMPS		PERFORM "GH2 PREPRESS SYSTEM PRESSURIZATION" (OPF) THRU PD10 PER V1171 VL1, OR THIS OMI.]
			RTOMI LOG NO. _____]
08-002	CMPS		CRT (VAE20)]
			VERIFY GH2 PREPRESS SYSTEM IS PRESSURIZED TO 400 +/- 25 PSIG.]
			RECORD GH2 PRESS _____ PSIG]
			400 +/- 25]
08-003	CMPS		CURSOR CNTL (VAE20)]
			A83134 LH2 PREPRESS SUPPLY SOV - CLOSE]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.

GH2 PRESS SYS (SUPPLY SIDE) VENTING				

08-004	CMPS RTH2		S70-0695-8 PANEL	
			A83066 SUPPLY SOV - CLOSE (CW)	
			VERIFY A83068 SUPPLY SOV CLOSED (CW)	
			A83115 REG - FULL DECREASE (CCW)	
			A83070 VENT - OPEN (CCW)	
			VERIFY A83143 GAGE 0 PSIG	
			A83070 VENT - CLOSE (CW)	
			LOCAL TIME _____ EST	

T: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

WARNING

DURING PERFORMANCE OF FOLLOWING STEP, AUDIBLE VENTING OF GHE WILL OCCUR. IF VENTING DOES NOT CEASE WITHIN 60 SECONDS, NOTIFY CMPS.

NOTE

CMPS WILL DETERMINE IF CV17 REV LEAK CHECK WILL BE PERFORMED (PER THIS SEQ) OR TO REINSTALL PLUG, IF VENTING DOES NOT CEASE.

ALLOW 5 MINUTES MINIMUM AFTER GSE GHE SUPPLY LINE IS VENTED BEFORE PERFORMING NEXT STEP. IF VENTING DOES NOT OCCUR IN THE FOLLOWING STEP, PERFORM PD10 REVERSE LEAK CHECK PER THIS SEQUENCE. IF VENTING DOES NOT CEASE (CV17 SUSPECT) OR DOES NOT OCCUR (PD10 SUSPECT) IN THE FOLLOWING STEP, NOT PERFORM SUBSTEP (3) AND PERFORM THE APPLICABLE CONTINGENCY TESTING PER THIS SEQUENCE.

TP10 PLUG REMOVAL

- | | | | | |
|--------|------|------|--|--|
| 08-005 | CMPS | OMTO | 1. VERIFY 5 MINUTES HAS ELAPSED SINCE GH2 PRESS SYS (SUPPLY SIDE) VENTING.

LOCAL TIME _____ EST | |
| | | | 2. SLOWLY LOOSEN MD273-0044-2004 BLEEDER PLUG IN TP10 2-4 TURNS TO ALLOW LINE TO VENT. | |
| | | | 3. VERIFY AUDIBLE VENTING FOLLOWED BY CESSATION OF AUDIBLE VENTING, (S/B LESS THAN 60 SEC.). | |

NOT PERFORMED

SS3

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
08-006		CMPS	CRT (VAE20) VERIFY GH2 PREPRESS SYSTEM IS PRESSURIZED TO 400 +/- 25 PSIG. RECORD GH2 PRESS _____ PSIG 400 +/- 25	
NOTE				
PERFORM FOLLOWING STEP IF VENTING AT TP10 CEASED THIS SATISFIES CV17/PD10 VALIDATION.				
08-007		CMPS	COMPLETION OF THE PREVIOUS SIX STEPS SATISFIES THE NOTED REQUIREMENT. OMRSD V41BB0.051	NOT PERFORMED _____
08-008		CMPS OMT0	PLUG IF VENTING DID NOT CEASE AT TP10 AND DIRECTED BY CMPS, REINSTALL PLUG WRENCH TIGHT.	OK TO INSTALL QW: _____ TQV: _____ NOT PERFORMED _____
CV17/PD10 REV LK VALIDATION COMPLETE]]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

PER V070-415413, EO C10,
FOR OV-103 AND SUBS,
ON THAT DRAWING,
ME261-0033-0104 AND
ME261-0033-0204 SEALS
ARE EQUIVALENT.]

PLUG AND NEW SEAL INSTALLED]
AND LEAK CHECKED AT END]
OF THIS SEQUENCE.]

08-010	CMPS	OMTO	REMOVE MD273-0044-2004 PLUG AND ME261-0033-0104 (OV-102 ONLY) OR ME261-0033-0104/ME261-0033-0204 (103 AND SUBS) SEAL FROM 50V41TP10. DISCARD SEAL, RETAIN PLUG CLEAN FOR LATER INSTALLATION.	
--------	------	------	--	--

TQV: _____

NOTE

IF REQD BY EFFECTIVITY,
(I-5 FLIGHTS), PERFORM NEXT
STEP TO INSTALL HANDVALVE
AT TP10.]

08-011	CMPS	OMTO	IF NOT INSTALLED, PERFORM ORBITER OPERATION SUPPORT SETUP 1 - TP10 HANDVALVE INSTALLATION. REPORT COMPLETION.	
--------	------	------	---	--

NOT PERFORMED _____

08-012	CMPS	OMTO	IF PD10 REV LK CK IS REQUIRED THIS FLOW, PERFORM OPERATION SUPPORT SETUP 2 - MPS 1-INCH QD LEAK CHECK TOOL SETUP. REPORT COMPLETION.	
--------	------	------	--	--

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

PERFORM PD10 LH2 PREPRESS
DISCONNECT REVERSE LEAK CHECK
IF REQUIRED BY EFFECTIVITY/
LRU REPLACEMENT/SUSPECTED
LEAKAGE.

PD10 LH2 PREPRESS DISCONNECT REVERSE

LEAK CHECK (SEE FIGURE 4)

EFFECTIVITY: (REF SECTION 1.8)

NOT PERFORMED

08-021	CMPS	OMTO	VERIFY PD16 GROUND HALF QD AND FLEXHOSE IS CONNECTED TO FLIGHT HALF QD.	
--------	------	------	---	--

TQW: _____

08-022	CMPS	OMTO	VERIFY MPS 1-INCH QD LEAK CHECK TOOL IS ON HAND AND READY TO SUPPORT LK CK.	
--------	------	------	---	--

TQW: _____

08-023	CMPS		CRT (VAE20) VERIFY A83134 LH2 PREPRESS - CLOSE	
--------	------	--	--	--

08-024	CMPS	RTH2	S70-0695-8 PNL A83115 REG - FULL DECREASE (CCW) VERIFY GAGE A83143 INDICATES 0 PSIG A83145 VENT - OPEN (CCW) A83070 VENT - OPEN (CCW)	
--------	------	------	---	--

08-025	CMPS		CRT (VAE20) VERIFY GH2 PRESS SYSTEM IS AMBIENT RECORD GH2 PRESS _____ PSIG	
--------	------	--	--	--

08-026	CMPS	OMTO	IF NOT PREVIOUSLY PERFORMED VERIFY H/V AT TP10 IS CLOSED. REMOVE KC150C4 CAP ON H/V. BAG AND SEAL.	
--------	------	------	--	--

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
08-027	CMPS	OMTO	1. REMOVE GW70-420958-002 COUPLING AND FLEXHOSE FROM 50V41PD16 (CCW). INSTALL (SNUG ONLY) GND AND AIRBORNE DUST CAPS. 2. REMOVE GW70-420958-002 COUPLING FROM 79K10547-HE16 FLEXHOSE. MAINTAIN CLEANLINESS. CLEAN BAG AND SEAL GND HALF COUPLING.	TQW: _____
08-028	CMPS	OMTO	CONNECT 79K10547-HE16 FLEXHOSE PREVIOUSLY REMOVED, TO ADAPTER IN HANDVALVE AT TP10 USING A KC103-6 SEAL. TORQUE TO 270-345 IN. LBS. RESTRAIN FLEXHOSE (REF 80K51846) USING BACKUP WRENCH.	
			Z _____ DUE DATE _____	
			VERIFY CSR-242	TQV: _____ TQW: _____
08-029	CMPS	RTH2	S70-0695-8 PANEL A83070 VENT VLV - CLOSE (CW) A83145 VENT VLV - CLOSE (CW)	T: _____
08-030	CMPS	CRT	(VAE20) A83134 LH2 PREPRESS SOV - CLOSE	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
<u>PD10 - PREPRESS QD REMOVAL</u>				
08-031	CMPS	OMTO	REMOVE G070-005820-005 (GROUND QD ASSY FROM 50V41PD10 AS FOLLOWS: 1. DISENGAGE LOCKING PINS (2). 2. PULL BACK COLLAR UNTIL COLLET FULLY EXPOSED. 3. DISENGAGE GRND QD FROM FLT HALF.	TQV: _____
08-032	CMPS	OMTO	LH2 (T-0) QD PD10 1. INSPECT G070-005820-005 (GROUND QD ASSY FOR ANY NOSE SEAL OR OTHER OBVIOUS MATING SURFACE DAMAGE. 2. DOUBLE BAG AND INTEGRITY SEAL OUTLET OF G070-005820-005 GRND QD ASSY. 3. PLACE G070-005820-005 ASSY IN ITS PROTECTIVE QD COVER. 4. STOW GSE QD/FLEXHOSE ASSY SO IT WILL NOT INTERFERE WITH PLATFORM OPS. 5. SECURE G070-005820-005 ASSY TO PLATFORM WITH BALES.	TQW: _____
08-033	CMPS	OMTO	PERFORM VISUAL INSPECTION OF 50V41PD10. VERIFY NO SEALING SURFACE DAMAGE.	TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

LH2 HELIUM PREPRESS (50V41PD10)

08-034	CMPS	OMTO	INSTALL 74332026-503 MPS 1-INCH QD LK CK TOOL ASSY AS FOLLOWS:	
--------	------	------	--	--

OK TO INSTALL QW: _____

1. ADJUST CENTER BOLT FULL (CCW) TO EXTEND RETENTION FINGERS.
2. INSERT 74332026-503 CAP ONTO PD10 UNTIL RETENTION FINGERS ARE ENGAGED OVER FLIGHT HALF SWIVEL ASSY.
3. ORIENT CAP SO ACCESS TO ELBOW WITH FLOWMETER IS POSSIBLE.
4. ROTATE CENTER BOLT (CW) TO SET RETENTION FINGERS. TORQUE TO 120-180 IN. LBS.

Z _____ DUE DATE _____

VERIFY CSR-242 TQV: _____

TQW: _____

08-035	CMPS	OMTO	VERIFY 79K10547-HE16 FLEXHOSE IS CONNECTED TO HANDVALVE AT TP10.	
--------	------	------	--	--

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
08-036	CMPS OTC 132	OTC *ACM	IF AFT FUSELAGE IS OCCUPIED, NOTIFY PERSONNEL IN AFT FUSELAGE THAT GH2 PRESSURIZATION MANIFOLD WILL BE PRESSURIZED WITH GHE AND FLOW WILL BE AUDIBLE.	_____
			NOT PERFORMED	_____
08-037		CMPS	CURSOR CNTL (VAE20) A83134 LH2 PREPRESS VLV - OPEN	
08-038	CMPS	OMT0	OPEN HAND VALVE (CCW) INSTALLED AT TP10.	TQW: _____
08-039	CMPS	RTH2	S70-0695-8 PNL A83145 VENT VLV - OPEN (CCW) A83115 REG - SLOWLY INCREASE (CW) UP TO 400 +/- 25 PSIG AS INDICATED ON A83143	TQW: _____
08-040		CMPS	CRT (VAE20) VERIFY GH2 PRESSURIZATION SYSTEM PRESSURIZED TO 400 +/- 25 PSIG. RECORD GH2 PRESS _____ PSIA BD CONVERT TO _____ PSIG BD	
08-041	CMPS	OMT0	USE A C70-0903 FLOWMETER TO LEAK CHECK PD10 BY CONNECTING FLOWMETER TO KC118C4 ELBOW ON MPS 1-INCH QD LEAK CHECK TOOL. RECORD DATA IN APPENDIX A, DATA SHEET A-1 FOR 50V41PD10 (10 SCIM MAX). OMRSD V41BB0.050-1R	TQW: _____
			PD10 LH2 PREPRESS DISC REV LK CK COMPLETE]]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
08-042	CMPS	RTH2	S70-0695-8 PANEL A83066 SUPPLY VLV - CLOSE (CW) A83068 SUPPLY VLV - CLOSE (CW) A83115 REG - FULL DECREASE (CCW) A83070 VENT - OPEN (CCW) VERIFY GAGE A83143 IND 0 PSIG A83070 VENT - CLOSE (CW)	T: _____
08-043	CMPS		CURSOR CNTL (VAE20) A83134 LH2 REPRESS VLV - CLOSE	
08-044	CMPS	OMTO	REMOVE HE16 FLEXHOSE FROM HAND VALVE AT 50V41TP10. BAG AND SEAL END.	TQW: _____
08-045	CMPS	OMTO	CLOSE HANDVALVE (CW) AT TP10. INSTALL KC150C4 CAP WRENCH TIGHT.	TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

PD16 MAY BE MATED UNDER PRESSURE.

08-046 CMPS OMT0 RECONFIGURE PD16 SETUP AS FOLLOWS:

OK TO INSTALL QWN: _____

1. INSTALL GW70-420958-002 LEAR-SEIGLER GND COUPLING TO HE16 FLEXHOSE. TORQUE TO 270-345 IN. LBS AND INSTALL KELLUM GRIPS.

Z _____ DUE DATE _____

2. CONNECT GW70-420958-002 ASSY TO 50V41PD16 DISCONNECT. TORQUE TO 15-20 IN. LBS.

Z _____ DUE DATE _____

3. SECURE 79K10547-HE16 FLEXHOSE TO AFT STRUCTURE WITH TIE WRAPS (REF 80K51846).

VERIFY CSR-242 TQV: _____

TQW: _____

08-047 CMPS IF PRESSURIZED, PERFORM GH2 PREPRESS VENTING/SYSTEM SECURING (OPF) PER THIS OMI.

RT OMI LOG NO. _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

WARNING

PERSONNEL HANDLING FREON MUST WEAR RUBBER GLOVES AND EYE PROTECTION.

08-048 CMPS OMT0 REMOVE 74332026-503 MPS 1-INCH QD LK CK TOOL AS FOLLOWS:

1. TURN CENTER BOLT (CCW) TO EXTEND RETENTION FINGERS.
2. REMOVE CAP ASSY FROM PD10.
3. PERFORM FREON RINSE OF 74332026-503 CAP DOUBLE BAG AND SEAL. RETURN TO MPS CAP AND PLUG SET.

TQW: _____

CAUTION

DO NOT SPRAY FREON-TF DIRECTLY INTO DISCONNECT.

PD10 VEHICLE DISCONNECT INSPECTION

08-049 CMPS OMT0 CLEAN AND INSPECT VEHICLE DISCONNECT.

1. WIPE QD CLEAN USING FREON MOISTENED LINT FREE CLOTH.
2. USING WHITE LIGHT INSPECTION, VERIFY NO RESIDUALS OR DAMAGE.
3. IF GND HALF QD IS NOT TO BE REINSTALLED, COVER VEHICLE QD PD10 WITH ACLAR AND SEAL.

NOT PERFORMED

SS3

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

PD10 - LH2 PREPRESS QD INSTALLATION

CAUTION

FLIGHT HALF QD IS FLOATING.
FLIGHT HALF QD MUST BE
CENTERED PRIOR TO ATTEMPTING
MATE WITH GSE.

PD10 IS KEYED WITH TWO SLOTS
AT 90 DEGREE INTERVALS.
ORIENT FLIGHT HALF TO GND
HALF PRIOR TO INSTALLATION.

THE FOLLOWING STEPS MUST
BE WORKED IN ORDER TO
PREVENT INADVERTANT
CONNECTION OF WRONG GROUND
HALF TO ORBITER DISCONNECTS
AS PD10 AND PD14 ARE
PHYSICALLY IDENTICAL AND
COULD BE SWITCHED.

08-050	OMTO		VERIFY 79K10547-HE10 FLEXHOSE IS CONNECTED TO (0-2) A105347 I/F PNL PORT (SEE FIGURE 8-10).	
--------	------	--	---	--

TQV: _____

08-051	OMTO		TRACE FLEXHOSE TO END AND VERIFY G070-005820-005 GH2 PREPRESS GND QD IS CONNECTED TO 79K10547-HE10 FLEXHOSE.	
--------	------	--	--	--

TQV: _____

08-052	OMTO		LOCATE PD10 ON LH2 T-0 (SEE FIGURE 11).	
--------	------	--	---	--

T: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
08-053	OMTO	1.	IF FLEXHOSE IS TWISTED, LOOSEN 79K10547-HE10 FLEXHOSE FROM INLET OF G070-005820-005 QD. MAINTAIN SYSTEM CLEANLINESS.	
			NOT PERFORMED	SS1
		2.	PRIOR TO INSTALLING G070-005820-005 GND HALF REMOVE ACLAR AND TAPE FROM FORWARD END OF G070-005820-005. INSPECT TEFLON NOSE SEAL AND MATING SURFACE, RINSE WITH FREON AND REMOVE ANY RESIDUE WITH LINT FREE CLOTH.	
		3.	PRIOR TO MATE TO 50V41PD10 LH2 PREPRESS DISCONNECT, VERIFY TWO LOCKING PINS ARE DISENGAGED SO RETENTION FINGERS ARE EXPOSED ON G070-005820-005.	
				TQW: _____
08-054	OMTO		G070-005820-005 QD	
			OK TO INSTALL	QWN: _____
		1.	ENGAGE G070-005820-005 QD TO DISCONNECT 50V41PD10, PUSHING G070-005820-005 FORWARD TO LOCK COLLET.	
		2.	MOVE TWO LOCKING PINS TO THE LOCKED POSITION AND VERIFY QD IS FULLY ENGAGED. TURN LOCKING PINS (CW) SNUG.	
		3.	SUPPORT G070-005820-005 QD ASSY IN HORIZONTAL POSITION, USING TIE WRAPS ATTACHED TO CARRIER FRAME.	
				TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

IF FLEXHOSE WAS LOOSEMED IN PREVIOUS STEP, PERFORM NEXT STEP.

08-055	OMTO		CONNECT 79K10547-HE10 FLEXHOSE TO INLET OF G070-005820-005 QD. TORQUE 270-345 IN. LBS.	
--------	------	--	--	--

Z _____ DUE DATE _____

VERIFY CSR-242 TQV: _____

TQW: _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

TP10 H/V REMOVAL

- | | | | | |
|--------|------|------|---|--|
| 08-056 | CMPS | OMTO | <ol style="list-style-type: none"> REMOVE HANDVALVE, MINIFILTER, KC FITTING AND K-SEAL INSTALLED AT 50V41TP10. MAINTAIN SYSTEM CLEANLINESS. DISCARD K-SEAL LOCALLY RETURN REMAINING ITEMS TO STOCK. INSPECT ME286-0068-0008 MINIFILTER TO VERIFY THAT FILTER SCREEN IS INSTALLED. | |
|--------|------|------|---|--|

TIR LOG NO. _____

TQW: _____

- | | | | | |
|--------|------|------|--|--|
| 08-057 | CMPS | OMTO | <p>MD273-0044-2004 PLUG
ME261-0033-0104 SEAL (OV-102),
OR ME261-0033-0104/ME261-0033-0204
(OV-103 AND SUBS).</p> | |
|--------|------|------|--|--|

OK TO INSTALL QWN: _____

INSTALL:

MD273-0044-2004 TEST PORT PLUG WITH NEW
ME261-0033-0104 SEAL/ME261-0033-0204 INTO 50V41TP10.
TORQUE TO 170-200 IN. LBS

Z _____ DUE DATE _____

INSTALL SAFETY WIRE MS20995N32 PER MA0102-306.

VERIFY CSR-242 TQV: _____

TQWN: _____

- | | | | | |
|--------|------|--|--|--|
| 08-058 | CMPS | | IF NOT PRESSURIZED, PERFORM GH2 PREPRESS SYSTEM PRESSURIZATION (OPF)" PER OMI V1171VL1, OR THIS OMI. | |
|--------|------|--|--|--|

RT OMI LOG NO. _____

NOT PERFORMED _____

- | | | | | |
|--------|------|--|---|--|
| 08-059 | CMPS | | <p>CRT (VAE20)</p> <p>VERIFY GH2 PREPRESS SYSTEM IS PRESSURIZED TO 400 +/- 25 PSIG.</p> | |
|--------|------|--|---|--|

GH2 PRESS _____ PSIG
400 +/- 25

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

TP10 LEAK CHECK

WARNING

PERSONNEL PERFORMING SOAP SOLUTION LEAK CHECKS SHALL WEAR EYE PROTECTION.

NOTE

REF 1.7 SPECIAL INSTRUCTIONS FOR MASS SPEC LEAK CHECKS.

08-060	OMTO		PERFORM SOAP SOLUTION LEAK CHECK OF FOLLOWING JOINT. RECORD DATA BELOW:	
--------	------	--	---	--

JOINT DESCRIPTION	RESULTS
-------------------	---------

TP10	
------	--

OMRSD V41AY0.045

TQW: _____

08-061	CMPS		IF NO LONGER REQUIRED, PERFORM MPS GH2 PREPRESS SYSTEM SECURING (OPF) PER OMI V1171VL1, OR THIS OMI.	
--------	------	--	--	--

RT OMI LOG NO. _____

NOT PERFORMED _____

08-062			PD10 AND CV17 - VALIDATION AND INTERNAL LEAK CHECKS COMPLETE.	
--------	--	--	---	--

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
09-000			GH2 PRESSURIZATION SYSTEM FLANGE LEAK CHECKS	

NOTE

THIS OPERATION PERFORMED ONLY IF REQUIRED BY EFFECTIVITY/FLIGHT AND/OR VEHICLE. REF 1.7 SPECIAL INSTRUCTIONS FOR NOT PERFORMED DEFINITION.

EFFECTIVITY: (REF SECTION 1.8)

NOTE

STEPS AND SUBSTEPS WITHIN THIS SEQUENCE MAY BE WORKED OUT OF NUMERICAL ORDER AS DETERMINED BY MPS ENGINEERING.

OPERATIONS INVOLVING CRIT 1 AND/OR 1R ITEMS ARE CONTAINED IN THE FOLLOWING SEQUENCE/STEPS.

GH2 SYSTEM PRESSURE MUST BE 400 +/- 25 PSIG. THE FOLLOWING SEQUENCE WILL PERFORM FLANGE LEAK CHECKS OF GH2 PRESSURIZATION SYSTEM USING C70-0903 ATMOSPHERIC FLOWMETER (REF 1.7 SPECIAL INSTRUCTIONS).

REF FIGURES 5 AND 13

09-001 OMT0 OBTAIN C70-0903 FLOWMETER AND VERIFY DATA TABLES WITH METER.

Z _____ DUE DATE _____

T: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
09-002		CMPS	IF NOT ACTIVE, PERFORM GH2 PREPRESS SYSTEM PRESSURIZATION (OPF) ^m PER OMI V1171VL1, OR THIS OMI. PRESSURIZE SYSTEM TO 400 +/- 25 PSIG. RT OMI LOG NO. _____	

NOT PERFORMED _____

NOTE

FOLLOWING STEP IS TO BE REPEATED FOR EACH JOINT LISTED BELOW.

09-003 CMPS OMT0 PERFORM GH2 SYS FLANGE LEAK CHECKS FOR EACH FLANGE PER THE FOLLOWING (SEE FIGURE 5 AND 13):

1. REMOVE MD273-0032-2002 LEAK CHECK PLUG AND SEAL. MAINTAIN PLUG AND SEAL CLEAN.

TQW: _____
SS1

2. INSPECT K-SEAL USING 3X (MINIMUM) GLASS FOR SCRATCHES OR OTHER DAMAGE. REPLACE IF DAMAGE FOUND.

TQW: _____
SS2

3. USING C70-0903 FLOWMETER PERFORM LEAK CHECK OF LISTED FLANGES (0.29 SCIM MAX).

FLG	FLOWMETER Z	LEAK RATE (SCIMS)	WRENCH Z	TQW
---	-----	-----	-----	---
				SS3
FAQ	_____	_____	_____	_____
FAR	_____	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
09-003 CON'T			4. ME261-0033-0102 K SEAL/MD273-0032-2002 PLUG OK TO INSTALL INSTALL K-SEAL AND PLUG FOR GH2 PRESSURIZATION SYS FLANGES FAQ, FAR. TORQUE 70 +/- 5 IN. LBS. Z _____ DUE DATE _____	QWN: _____ SS4
			5. SAFETY WIRE WITH MS20995N32. OMRSD V41AY0.040-B-1 VERIFY CSR-242	TQV: _____ TQWN: _____ SS4-5
09-004	CMPS		IF NO LONGER REQUIRED, PERFORM "MPS GH2 PREPRESS SYSTEM SECURING (OPF)", PER OMI V1171VL1, OR THIS OMI. RT OMI LOG NO. _____	NOT PERFORMED _____
09-005	CMPS		GH2 PRESSURIZATION SYSTEM FLANGE LEAK CHECKS COMPLETE.	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
10-000			GH2 PRESSURIZATION SYSTEM LEAK CHECK - CMPS, OMTO, OQCV, AND RTH2	

NOTE

THIS OPERATION PERFORMED ONLY IF REQUIRED BY EFFECTIVITY/FLIGHT AND/OR VEHICLE. REF 1.7 SPECIAL INSTRUCTIONS FOR NOT PERFORMED DEFINITION.

EFFECTIVITY: (REF SECTION 1.8)

NOTE

STEPS AND SUBSTEPS WITHIN THIS SEQUENCE MAY BE WORKED OUT OF NUMERICAL ORDER AS DETERMINED BY MPS ENGINEERING.

OPERATIONS INVOLVING CRIT 1 AND/OR 1R ITEMS ARE CONTAINED IN THE FOLLOWING SEQUENCE/STEPS.

NOTED REQUIREMENT IS SATISFIED BY COMPLETION OF THIS SEQUENCE.

OMRS V41AY0.040-A-1

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

DO NOT RUN THE FOLLOWING
LEAK CHECKS UNTIL ALL
COMPONENT CHECKOUTS FOR
THIS FLOW ARE COMPLETE
(AS REQD BY OMRS EFFECTIVITY).

MPS GROUND HALF QD'S FOR
PD10 AND PD16 ARE REQUIRED
TO SUPPORT PRESSURIZATION/
SECURING IN THIS SEQUENCE
(VERIFICATION IS PERFORMED
PER V1171VL1). REF FIGURES
5 AND 13.

GH2 PRESSURIZATION SYSTEM MASS SPEC LEAK

CHECKS - 400 +/- 25 PSIG

10-001

CMPS IF NOT ACTIVE, PERFORM GH2 PREPRESS SYSTEM
PRESSURIZATION (OPF) PER THIS OMI. PRESSURIZE
SYSTEM TO 400 +/- 25 PSIG.

RT OMI LOG NO. _____

RUN: _____

NOT
PERF: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
10-002	CMPS	OMTO	PERFORM MASS SPEC LEAK CHECK OF GH2 FCV INLET AND OUTLET WELD JOINTS LV56B, LV56C, LV57B, LV57C, LV58B AND LV58C. RECORD DATA IN DATA SHEET B-1.	
			OMRSD V41AY0.046 EFFECTIVITY:	
			V02F12-90]
			V03F15-90]
			V04F11-90]
			V05F1-90]
			VERIFY CSR-085	TQV: _____
			VERIFY CSR-086	TQV: _____
				TQW: _____

NOTE

NOT PERFORM NEXT STEP
IF I-5 FLIGHT LEAK CHECKS
ARE REQUIRED PER OMRS
V41AY0.040-A

V02 F8 I5F
V03 F7 I5F
V04 F3 I5F
V05 F2 I5F

10-003 CMPS IF ACTIVE AND NO LONGER REQUIRED,
SECURE MPS GH2 PRESS PER V1171VL1,
OR THIS OMI.

RT OMI NO. _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

DO NOT PERFORM REMAINDER
OF SEQUENCE IF LEAK CHECKS
NOT REQUIRED PER ABOVE
OMRS V41AY0.040-A

10-004 CMPS OMT0

PERFORM A MASS SPEC LEAK CHECK OF GH2
PRESSURIZATION SYSTEM (REF 1.7 SPECIAL
INSTRUCTIONS) AS FOLLOWS:

1. ALL BRAZED, WELDED, AND THREADED JOINTS INCLUDING COMPONENT JOINTS FROM FCV'S TO SSME INTERFACES.
2. BELLOWS AND ADJACENT WELDS.
3. BRAZED, WELDED AND THREADED FITTINGS INCLUDING COMPONENT JOINTS BETWEEN FCV'S TO T-0 AND ET/ORB I/F THAT ARE NON-FOAMED (TYPE II).
4. FLOW CONTROL VALVE SOLENOIDS TO VALVE BODY O-RING.
5. RECORD DATA IN APPENDIX B, DATA SHEETS B-1, B-2, AND B-4.

VERIFY CSR-086 TQV: _____

VERIFY CSR-085 TQV: _____

TQW: _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

			GH2 PRESSURIZATION SYSTEM BUBBLE SOAP LEAK CHECKS - 400 +/- 25 PSIG	
--	--	--	--	--

WARNING

FACESHIELDS OR GOGGLES SHALL BE WORN BY PERSONNEL PERFORMING SOAP SOLUTION LEAK CHECKS.

NOTE

DO NOT RUN THE FOLLOWING LEAK CHECKS UNTIL ALL COMPONENT CHECKOUTS FOR THIS FLOW ARE COMPLETE (AS REQD, BY OMRS EFFECTIVITY).

PD5 TEST PLATE MUST BE REMOVED FOR FP5 LEAK CHECK.

10-005	CMPS OMT0		IF INSTALLED, REMOVE PD5 TEST PLATE PER: JC V41-40016 - PLATE, PD5 2 IN. GH2 PREPRESS REMOVAL	
--------	-----------	--	---	--

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

DO NOT RUN THE FOLLOWING
LEAK CHECKS UNTIL ALL COMPONENT
CHECKOUTS FOR THIS FLOW ARE
COMPLETE (AS REQD, BY
OMRS EFFECTIVITY).

10-006	CMPS	OMTO	PERFORM A LEAK CHECK OF ALL NONFOAMED GH2 PRESSURIZATION SYSTEM TYPE I THREADED, COMPONENT, WELD, AND BRAZED JOINTS BETWEEN FCV'S, T-0 I/F, AND ET/ORB I/F THAT CAN BE ACCESSED FOR 360 DEG BUBBLE SOAP OBSERVATION (TYPE I), USING LEAK DETECTION SOLUTION (REF 1.7 SPECIAL INSTRUCTIONS). RECORD DATA IN APPENDIX B, DATA SHEETS B-1 AND B-4, AND JOINT FPD5 (DATA SHEET B-3).]]
--------	------	------	--	-----

TQW: _____

NOT PERFORMED _____

10-007	CMPS	RTH2	S70-0695-8 A83066 SUPPLY SOV - CLOSE (CW) A83115 REG - FULL DECREASE (CCW) VERIFY A83145 VENT/SOV OPEN (CCW) A83070 VENT VALVE - OPEN (CCW) VERIFY A83143 GAGE 0 PSIG	
--------	------	------	--	--

T: _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
----- GH2 PRESSURIZATION SYSTEM BUBBLE SOAP LEAK CHECKS ----- DOWNSTREAM OF LV52 -----				

NOTE

FOLLOWING STEPS PERFORM
LEAK CHECK OF JOINTS
DOWNSTREAM OF LV52.

10-008	CMPS		VERIFY GH2 SYSTEM PRESSURE IS AMBIENT.	
10-009	CMPS	OMTO	IF NOT INSTALLED, INSTALL GH2 2 IN. DISC TEST PLATE ONTO PD5 DISC PER: JC V41-50008 - TEST PLATE, PD5 GH2 2 IN. CLEANING/INSPECTION/INSTALLATION	
				NOT PERFORMED _____
10-010	CMPS	OMTO	OPEN PD5 FLT POPPET BY TURNING POPPET ACTUATOR BOLT FULL (CW) UNTIL SNUG AND SEATED AGAINST BASE.	
				TQW: _____
				NOT PERFORMED _____
10-011	CMPS		IF NOT ACTIVE, PERFORM GH2 PREPRESS SYSTEM PRESSURIZATION (OPF) PER OMI V1171VL1, OR THIS OMI. PRESSURIZE SYSTEM TO 400 +/- 25 PSIG. RT OMI LOG NO. _____	
			RUN: _____	
			NOT PERF: _____	
10-012	CMPS	OMTO	PERFORM SOAP SOLUTION LEAK CHECK OF JOINTS F247 THRU F255. RECORD RESULTS IN APPENDIX B, DATA SHEET B-3.	
				TQW: _____
				NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
10-013	CMPS		IF NO LONGER REQUIRED, PERFORM "MPS GH2 PREPRESS SYSTEM SECURING (OPF)" PER OMI V1171VL1, OR THIS OMI. RT OMI LOG NO. _____	NOT PERFORMED _____
NOTE DO NOT PERFORM NEXT STEP IF GH2 SYSTEM DECAY TEST STILL REQUIRED TO BE PERFORMED THIS FLOW.				
10-014	CMPS	OMTO	REMOVE PD5 TEST PLATE PER: JC V41-40016 - PLATE, PD5 2 IN. GH2 PREPRESS, REMOVAL	NOT PERFORMED _____
10-015			GH2 PRESSURIZATION SYSTEM LEAK CHECK COMPLETE. VERIFY DATA IS COMPLETE AND ENGINEER WILL VERIFY ACCEPTABLE. CMPS: _____	NOT PERFORMED _____
10-016	CMPS	CMQC	COMPLETION OF THIS SEQUENCE SATISFIES NOTED OMRS REQUIREMENT. OMRSD V41AY0.040-A-1	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
11-000			CV21, CV22, CV23 INTERNAL LEAK CHECK - CMPS, OMT2, OMT0, QQCV & RTH2	

NOTE

THIS OPERATION PERFORMED ONLY IF REQUIRED BY EFFECTIVITY/FLIGHT AND/OR VEHICLE. REF 1.7 SPECIAL INSTRUCTIONS FOR NOT PERFORMED DEFINITION.

EFFECTIVITY: (REF SECTION 1.8)

NOTE

STEPS AND SUBSTEPS WITHIN THIS SEQUENCE MAY BE WORKED OUT OF NUMERICAL ORDER AS DETERMINED BY MPS ENGINEERING.

OPERATIONS INVOLVING CRIT 1 AND/OR 1R ITEMS ARE CONTAINED IN THE FOLLOWING SEQUENCE/STEPS.

HARDWARE REQUIRED

QTY	PART NO.	NOMENCLATURE
3	MD273-0032-2004	PLUG
3	ME261-0033-0104	K-SEAL
1	KC131C4	ELBOW
5	KC103-4	SEAL
6	MS28778-4	O-RING
1	C70-0903	FLOWMETER
3	RG001505	THROAT PLUG
3	ME286-0068-0008	MINIFILTER
3	KC125C6-4	REDUCER-ADAPTER
3	L070-000070-009	1/4 IN. BACK-TO-BACK

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

RG001505 THROAT PLUG INSTALLATION SSME 1, 2, 3

- | | | | | |
|--------|------|--|---|--|
| 11-001 | OMT1 | | <p>INSTALL, IF REQUIRED AND NOT ALREADY INSTALLED, RG001505 THROAT PLUGS:</p> <ol style="list-style-type: none"> HANDWIPE MAIN COMBUSTION CHAMBER CONVERGING AREA IMMEDIATELY UPSTREAM OF THROAT FREE OF VISIBLE CONTAMINATION. REMOVE CAPS FROM UNIONS INSTALLED IN PORTS MARKED INLET AND MONITOR ON PLUG HALF. FOLD SEAL AS REQUIRED TO PERMIT INSTALLATION: THEN CAREFULLY INSERT PLUG HALF WITH SEAL THROUGH THRUST CHAMBER THROAT. DO NOT ALLOW ANY METAL PORTION OF PLUG TO CONTACT WALLS OF THRUST CHAMBER. CAREFULLY INSERT SECOND PLUG HALF THROUGH THRUST CHAMBER THROAT. INSTALL SECOND PLUG HALF ONTO SHAFT OF PLUG HALF WITH SEAL. STRETCH SEAL AS REQUIRED TO SEAT PLUG HALF INTO SEAL. DO NOT USE SHARP OR METAL TOOL TO STRETCH SEAL. ALIGN HOLES IN PLUG HALVES AND INSTALL PIN. CENTER AND SEAT ASSEMBLED THROAT PLUG IN THRUST CHAMBER THROAT. INSTALL SUPPORT ON SHAFT OF THROAT PLUG. SECURE WITH NUT/WASHER. TIGHTEN WRENCH TIGHT. | |
|--------|------|--|---|--|

	E1C	E2L	E3R
	---	---	---
OK TO INSTALL			
QWN:	_____	_____	_____
TQW:	_____	_____	_____
NOT PERF:	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
11-002	CMPS		CONSOLE KYBD (C4) PVO GH2 PRESSURIZATION SYSTEM PRESSURE TRANSDUCER, RECORD VALUES: PVO_V41P1160A1 XMIT CMD KEY - PRESS E1C _____ PSIA BD PVO_V41P1260A1 XMIT CMD KEY - PRESS E2L _____ PSIA BD PVO_V41P1360A1 XMIT CMD KEY - PRESS E3R _____ PSIA BD PVO_V41P1490A1 XMIT CMD KEY - PRESS MANIFOLD _____ PSIA BD	
11-003	CMPS		VERIFY GH2 PRESSURIZATION SYSTEM PRESSURE IS AMBIENT.	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.

CV21, CV22, CV23 (FWD) REVERSE SEAT LEAK CHECKS				

CAUTION

ME261-0033-0104 K-SEALS
ARE NOT REUSEABLE AND MUST
BE LOCALLY SCRAPPED.

GH2 PRESSURIZATION SYSTEM MUST
BE AMBIENT BEFORE REMOVING PLUG.
(SEE FIGURE 7)

E1C

11-004	CMPS OMT0	REMOVE GH2 E1C PRESS CV TEST PORT PLUG MD273-0044-2004 TP5. MAINTAIN PLUG CLEAN AND DISCARD SEAL.
--------	-----------	---

TQW: _____

E2L

11-005	CMPS OMT0	REMOVE GH2 E2L PRESS CV TEST PORT PLUG MD273-0044-2004 TP6. MAINTAIN PLUG CLEAN AND DISCARD SEAL.
--------	-----------	---

TQW: _____

E3R

11-006	CMPS OMT0	REMOVE GH2 E3R PRESS CV TEST PORT PLUG MD273-0044-2004 TP7. MAINTAIN PLUG CLEAN AND DISCARD SEAL.
--------	-----------	---

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

THE FOLLOWING MEASURES
LEAKAGE PAST FORWARD
CHECK VALVE IN CV21,
CV22, CV23.

11-009 CMPS OMT0 MEASURE LEAKAGE AT

50V41TP5 E1C GH2 PRESS CV TEST PORT
50V41TP6 E2L GH2 PRESS CV TEST PORT
50V41TP7 E3R GH2 PRESS CV TEST PORT

USING C70-0903 ATMOSPHERIC FLOWMETER
(REF 1.7 SPECIAL INSTRUCTIONS). RECORD DATA IN
APPENDIX A, DATA SHEET A-2 FOR 50V41CV21 (FWD)/
50V41CV22 (FWD)/50V41CV23 (FWD) (1000 SCIM MAX).

REFERENCE:

OMRS V41BA0.100-A-1R
OMRS V41BA0.100-B-1R
OMRS V41BA0.100-C-1R

TQW: _____

11-010 CMPS RTH2 S70-0695-8 PANEL 12E

A83115 REG - FULL DECREASE (CCW)
A83070 VENT - OPEN (CCW)
A83145 VENT/SUPPLY - OPEN (CCW)

VERIFY A83143 GAGE 0 PSIG

T: _____

11-011 CMPS CURSOR CNTL (VAE20)
A83134 LH2 PREPRESS - CLOSE

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
11-012	CMPS	OMTO	1. IF INSTALLED, REMOVE MPS GH2 SENSE LINE AND GROUND COUPLING (50V41PD16) TURN (CCW). 2. DUST CAPS OK TO INSTALL INSTALL AIRBORNE AND GND HALF DUST CAPS ON PD16 FLT AND GND COUPLING.	QW: _____ SS2 TQW: _____ NOT PERFORMED _____
11-013	CMPS	OMTO	IF INSTALLED, REMOVE GW70-420958-002 LEAR-SEIGLER GND COUPLING FROM 79K10547-HE16 FLEXHOSE. MAINTAIN CLEANLINESS OF GW70-420958-002 COUPLING AND HE16 FLEXHOSE. RETAIN GND HALF FOR REINSTALLATION.	T: _____ NOT PERFORMED _____
11-014	CMPS	OMTO	1. CONNECT MPS GH2 SENSE LINE FLEXHOSE (HE16) TO KC125C6-4 REDUCER-ADAPTER USING KC103-6 SEAL. TORQUE 3/8 IN. FITTING TO 270-345 IN. LBS. Z _____ DUE DATE _____ 2. CONNECT FLEXHOSE/ADAPTER ASSEMBLY TO L070-000070-009, 1/4 IN. BACK-TO-BACK USING KC103-4 SEAL. TORQUE TO 135-185 IN. LBS. SECURE FLEXHOSE RESTRAINTS (REF 80K51846). Z _____ DUE DATE _____ VERIFY CSR-242	TQV: _____ TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
<u>CV21, CV22, CV23 (AFT) REVERSE SEAT</u>				
<u>LEAK CHECKS</u>				

NOTE

THE FOLLOWING MEASURES
LEAKAGE PAST THE AFT
CHECK VALVE IN 50V41CV21,
50V41CV22, AND 50V41CV23.

IF SSME ARE NOT INSTALLED,
PERFORM CHECK VALVE LEAK
CHECKS AT REMOVED PLUG ON
SSME INTERFACE PLATE.

IF SSME ARE INSTALLED,
PERFORM CHECK VALVE LEAK
CHECKS AT SSME THROAT PLUGS.

RG000014 AND C70-0903 ARE
EQUIVALENT FLOWMETERS.

E1C/CV21 LEAK CHECK

11-015 CMPS OMT0 INSPECT ME286-0068-0008 MINIFILTER TO VERIFY
THAT FILTER SCREEN IS INSTALLED.

TQW: _____

11-016 CMPS OMT0 MINIFILTER WITH O-RING

OK TO INSTALL QWN: _____

INSTALL ME286-0068-0008 MINIFILTER WITH MS28778-4
O-RING INTO 50V41TP5. LUBE MINIFILTER AND O-RING
(REF 1.7 SPECIAL INSTRUCTIONS).
TORQUE TO 60-90 IN. LBS.

Z _____ DUE DATE _____

VERIFY CSR-242 TQV: _____

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
11-017	CMPS	OMTO	CONNECT MPS HE16 FLEXHOSE ASSEMBLY TO MINIFILTER INSTALLED IN 50V41TP5. RESTRAIN FLEXHOSE (REF 80K51846). TORQUE TO 135-185 IN. LBS. Z _____ DUE DATE _____ VERIFY CSR-242	TQV: _____ TQW: _____
11-018	CMPS	OMTO	IF TEST PLATE IS INSTALLED, REMOVE 45-11333 GLAND NUT AND 45-11340 PLUG FROM G070-005904-001 GH2 PRESS ORB/SSME INTERFACE TEST PLATE AT E1C. MAINTAIN CLEANLINESS. BAG AND SEAL PLUG.	TQW: _____
			NOT PERFORMED	_____
11-019	CMPS		CURSOR CNTL (VAE20) A83134 LH2 PREPRESS - OPEN WARNING MONITOR ORB/SSME INTERFACE PLATE FOR AUDIBLE FLOW. IF AUDIBLE, OMTO MUST NOTIFY CMPS IMMEDIATELY TO VENT GH2 PRESS SYSTEM PER APPENDIX Z - EMERGENCY GH2 PRESSURIZATION SYSTEM VENTING THRU S70-0695-8 PANEL.	
11-020	CMPS	RTH2	S70-0695-8 A83070 VENT - CLOSE (CW) A83115 REG - INCREASE SLOWLY (CW) TO INDICATE 400 +/- 25 PSIG ON GAGE A83143	TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
11-021	CMPS	OMTO	IF SSME NOT INSTALLED: LEAK CHECK AFT CHECK VALVE IN 50V41CV21 AT ORB/SSME INTERFACE TEST PLATE USING C70-0903 ATMOSPHERIC FLOWMETER (REF 1.7 SPECIAL INSTRUCTIONS). RECORD DATA IN APPENDIX A, DATA SHEET A-2 FOR 50V41CV21 (AFT) (1000 SCIM MAX). OMRSD V41BA0.100-A-1R	TQW: _____ NOT PERFORMED _____
11-022	QSME	QMTG	IF SSME AND THROAT PLUG INSTALLED (E1C) MEASURE LEAKAGE WITH RG000014 AT THROAT PLUG MONITOR HOSE. MONITOR FOR 10 MINUTES THEN RECORD IN APPENDIX A, DATA SHEET A-2 FOR 50V41CV21 (AFT). (1000 SCIM MAX) OMRSD V41BA0.100-A-1R	TQW: _____ NOT PERFORMED _____
11-023	CMPS	RTH2	S70-0695-8 A83115 REG - FULL DECREASE (CCW) A83070 VENT VALVE - OPEN (CCW) VERIFY A83143 GAGE IND 0 PSIG.	T: _____
11-024		CMPS	CURSOR CNTL (VAE20) A83134 LH2 PREPRESS - CLOSE	
11-025	CMPS	OMTO	REMOVE FLEXHOSE ASSY FROM FILTER IN TP5.	TV: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
11-026	CMPS	OMTO	1. REMOVE ME286-0068-0008 MINIFILTER AND MS28778-4 O-RING FROM 50V41TP5. 2. INSPECT ME286-0068-0008 MINIFILTER TO VERIFY FILTER SCREEN IS INSTALLED.	

TQW: _____

NOTE

ALL THREE TEST PORT PLUGS MAY BE INSTALLED AT THE SAME TIME AT THE END OF THIS SEQUENCE. ACLAR/TAPE PLUG TO LINE NEAR PORT IF THIS IS TO BE DONE. THE -0104 AND -0204 K-SEALS ARE INTERCHANGEABLE ON OV-103 AND SUBS (REF V070-415413 EOC10).

11-027	CMPS	OMTO	TEST PORT PLUG	OK TO INSTALL	QWN: _____
--------	------	------	----------------	---------------	------------

INSTALL MD273-0044-2004 TEST PORT PLUG WITH NEW ME261-0033-0104 (OV-102 ONLY) OR ME261-0033-0104/ME261-0033-0204 (OV-103 AND SUBS) SEAL INTO 50V41TP5. TORQUE TO 170-200 IN. LBS.

Z _____ DUE DATE _____

INSTALL SAFETY WIRE MS20995N32.

VERIFY CSR-242 TQV: _____

TQWN: _____

E2L/CV22 LEAK CHECK

11-028	CMPS	OMTO	INSPECT ME286-0068-0008 MINIFILTER TO VERIFY THAT FILTER SCREEN IS INSTALLED.		TQW: _____
--------	------	------	---	--	------------

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
11-029	CMPS	OMTO	MINIFILTER WITH O-RING INSTALL ME286-0068-0008 MINIFILTER WITH MS28778-4 O-RING INTO 50V41TP6. LUBE MINIFILTER AND O-RING (REF 1.7 SPECIAL INSTRUCTIONS). TORQUE TO 60-90 IN. LBS. Z _____ DUE DATE _____ OK TO INSTALL QWN: _____ VERIFY CSR-242 TQV: _____ TQW: _____	
11-030	CMPS	OMTO	CONNECT MPS HE16 FLEXHOSE ASSEMBLY TO MINIFILTER INSTALLED IN 50V41TP6. RESTRAIN FLEXHOSE (REF 80K51846). TORQUE TO 135-185 IN. LBS. Z _____ DUE DATE _____ VERIFY CSR-242 TQV: _____ TQW: _____	
11-031	CMPS	OMTO	IF TEST PLATE IS INSTALLED, REMOVE 45-11333 GLAND NUT AND 45-11340 PLUG FROM G070-005904-001 GH2 PRESS ORB/SSME INTERFACE TEST PLATE AT E2L. MAINTAIN CLEANLINESS, BAG AND SEAL PLUG. NOT PERFORMED _____ TQW: _____	
11-032	CMPS		CURSOR CNTL (VAE20) A83134 LH2 PREPRESS - OPEN	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

WARNING

MONITOR ORB/SSME INTERFACE
PLATE FOR AUDIBLE FLOW. IF
AUDIBLE, OMT0 MUST NOTIFY
CMPS IMMEDIATELY TO VENT GH2
PRESS SYSTEM PER APPENDIX Z -
EMERGENCY GH2 PRESSURIZATION
SYSTEM VENTING THRU S70-0695-8
PANEL.

11-033 CMPS RTH2 S70-0695-8 12E

A83070 VENT - CLOSE (CW)

A83115 REG - INCREASE SLOWLY (CW) TO
INDICATE 400 +/- 25 PSIG ON GAGE A83143

TQW: _____

11-034 CMPS OMT0

IF SSME NOT INSTALLED:
LEAK CHECK AFT CHECK VALVE IN 50V41CV22
AT ORB/SSME INTERFACE TEST PLATE USING
C70-0903 ATMOSPHERIC FLOWMETER (REF 1.7 SPECIAL
INSTRUCTIONS). RECORD DATA IN APPENDIX A,
DATA SHEET A-2 FOR 50V41CV22 (AFT)
(1000 SCIM MAX).

OMRSD V41BA0.100-B-1R

TQW: _____

NOT PERFORMED _____

11-035 QSME QMTG

IF SSME AND THROAT PLUG INSTALLED (E2L)

MEASURE LEAKAGE WITH RG000014 AT THROAT PLUG
MONITOR HOSE. MONITOR FOR 10 MINUTES THEN
RECORD IN APPENDIX A, DATA SHEET A-2 FOR
50V41CV22 (AFT). (100 SCIM MAX)

OMRSD V41BA0.100-B-1R

TQW: _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
11-036	CMPS	RTH2	S70-0695-8 A83115 REG - FULL DECREASE (CCW) A83070 VENT VALVE - OPEN (CCW) VERIFY A83143 GAGE IND 0 PSIG.	T: _____
11-037	CMPS		CURSOR CNTL (VAE20) A83134 LH2 PREPRESS - CLOSE	
11-038	CMPS	OMT0	REMOVE FLEXHOSE ASSY FROM FILTER IN TP6.	TV: _____
11-039	CMPS	OMT0	1. REMOVE ME286-0068-0008 MINIFILTER AND MS28778-4 O-RING FROM 50V41TP6. 2. INSPECT ME286-0068-0008 MINIFILTER TO VERIFY FILTER SCREEN IS INSTALLED.	TQW: _____
11-040	CMPS	OMT0	TEST PORT PLUG OK TO INSTALL INSTALL MD273-0044-2004 TEST PORT PLUG WITH NEW ME261-0033-0104 (OV-102 ONLY) OR (ME261-0033-0104/ME261-0033-0204 (103 AND SUBS) SEAL INTO 50V41TP6. TORQUE TO 170-200 IN. LBS. Z _____ DUE DATE _____ INSTALL SAFETY WIRE MS20995N32 VERIFY CSR-242	QWN: _____ TQV: _____ TQWN: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
E3R/CV23 LEAK CHECK				
11-041	CMPS	OMTO	INSPECT ME286-0068-0008 MINIFILTER TO VERIFY FILTER SCREEN IS INSTALLED.	TQW: _____
11-042	CMPS	OMTO	50V41TP7 OK TO INSTALL	QWN: _____
INSTALL ME286-0068-0008 MINIFILTER WITH MS28778-4 O-RING INTO 50V41TP7. LUBE MINIFILTER AND O-RING (REF 1.7 SPECIAL INSTRUCTIONS). TORQUE TO 60-90 IN. LBS.				
Z _____ DUE DATE _____				
VERIFY CSR-242				
11-043	CMPS	OMTO	ELBOW WITH SEAL OK TO INSTALL	TQV: _____ TQW: _____ QWN: _____
INSTALL KC131C4 SWIVEL ELBOW WITH KC103-4 SEAL TO ME286-0068-0008 MINIFILTER AT TP7. TORQUE TO 135-180 IN. LBS.				
Z _____ DUE DATE _____				
VERIFY CSR-242				
11-044	CMPS	OMTO	CONNECT MPS HE16 FLEXHOSE ASSEMBLY TO ELBOW INSTALLED IN 50V41TP7. RESTRAIN FLEXHOSE (REF SP611(2)KV). TORQUE TO 135-185 IN. LBS.	TQV: _____ TQW: _____
Z _____ DUE DATE _____				
VERIFY CSR-242				
TQV: _____				
TQW: _____				

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
11-045	CMPS	OMTO	IF TEST PLATE IS INSTALLED, REMOVE 45-11333 GLAND NUT AND 45-11340 PLUG FROM G070-005904-001 GH2 PRESS ORB/SSME INTERFACE TEST PLATE AT E3R. MAINTAIN CLEANLINESS, BAG AND SEAL PLUG.	TQW: _____ NOT PERFORMED _____
11-046	CMPS		CURSOR CNTL (VAE20) A83134 LH2 PREPRESS - OPEN	WARNING MONITOR ORB/SSME INTERFACE PLATE FOR AUDIBLE FLOW. IF AUDIBLE, OMTO MUST NOTIFY CMPS IMMEDIATELY TO VENT GH2 PRESS SYSTEM PER APPENDIX Z - EMERGENCY GH2 PRESSURIZATION SYSTEM VENTING THRU S70-0695-8 PANEL.
11-047	CMPS	RTH2	S70-0695-8 12E A83070 VENT - CLOSE (CW) A83115 REG - INCREASE SLOWLY (CW) TO INDICATE 400 +/- 25 PSIG ON GAGE A83143	TQW: _____
11-048	CMPS	OMTO	IF SSME NOT INSTALLED: LEAK CHECK AFT CHECK VALVE IN 50V41CV23 AT ORB/SSME INTERFACE TEST PLATE USING C70-0903 ATMOSPHERIC FLOWMETER (REF 1.7 SPECIAL INSTRUCTIONS). RECORD DATA IN APPENDIX A, DATA SHEET A-2 FOR 50V41CV23 (AFT) (1000 SCIM MAX). OMRSD V41BA0.100-C-1R	TQW: _____ NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
11-049	QSME	QMTG	IF SSME AND THROAT PLUG INSTALLED (E3R): MEASURE LEAKAGE WITH RG000014 AT THROAT PLUG MONITOR HOSE. MONITOR FOR 10 MINUTES THEN RECORD IN APPENDIX A, DATA SHEET A-2 FOR 50V41CV23 (AFT). (1000 SCIM MAX) OMRSD V41BA0.100-C-1R	TQW: _____
			NOT PERFORMED	_____
11-050	CMPS	RTH2	S70-0695-8 A83115 REG - FULL DECREASE (CCW) A83070 VENT VALVE - OPEN (CCW) VERIFY A83143 GAGE IND 0 PSIG.	T: _____
11-051	CMPS		CURSOR CNTL (VAE20) A83134 LH2 PREPRESS - CLOSE	
11-052	CMPS	OMTO	REMOVE FLEXHOSE ASSY AND ELBOW FROM MINIFILTER IN TP7 AND MAINTAIN CLEANLINESS.	TQW: _____
11-053	CMPS	OMTO	1. REMOVE ME286-0068-0008 MINIFILTER AND MS28778-4 O-RING FROM 50V41TP7. 2. INSPECT ME286-0068-0008 MINIFILTER TO VERIFY FILTER SCREEN IS INSTALLED.	TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

IF NOT PREVIOUSLY INSTALLED,
INSTALL ALL THREE TEST PORTS
FOR TP5, TP6 AND TP7.

11-054 CMPS OMT0 TEST PORT PLUG

OK TO INSTALL QWN: _____

INSTALL MD273-0044-2004 TEST PORT PLUG
WITH NEW ME261-0033-0104 (102) OR
(ME261-0033-0104/ME261-0033-0204)
(103 AND SUBS) SEAL INTO 50V41TP7.
TORQUE TO 170-200 IN. LBS.

Z _____ DUE DATE _____

INSTALL SAFETY WIRE MS20995N32

VERIFY CSR-242 TQV: _____

TQWN: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

PD16 RECONFIGURE

11-055	CMPS		GW70-420958	OK TO INSTALL QW:_____
--------	------	--	-------------	------------------------

IF NOT REQUIRED FOR FURTHER TESTING:
 REMOVE KC125C6-4 REDUCER-ADAPTER AND
 L070-000070-009 1/4 IN. BACK-TO-BACK FROM
 HE16 FLEXHOSE. INSTALL GW70-420958
 LEAR-SIEGLER GND COUPLING TO HE16 FLEXHOSE.
 USE KC103-6 SEAL. TORQUE TO 270-345 IN. LBS.

Z_____ DUE DATE_____

VERIFY CSR-242 TQV:_____

TQW:_____

NOT PERFORMED _____

CAUTION

GH2 SYSTEM IS PRESSURIZED TO
 400 PSI MAX. THE LEAR-SIEGLER
 QD IS DESIGNED TO BE MATED/
 DEMATED WITH PRESSURE APPLIED.
 IF LEAKAGE IS NOTED DURING
 MATE OR DEMATE, NOTIFY MPS.

11-056	CMPS OMT0		PD16 FLT TO GRND HALF MATE	OK TO INSTALL QWN:_____
--------	-----------	--	----------------------------	-------------------------

1. REMOVE CAP/PLUG (DUST CAPS) FROM PD16 FLT AND GRND HALFS AND CONNECT TOGETHER.
2. INSTALL GH2 SENSE LINE TO 50V41PD16 FLT HALF. TURN CW. TORQUE TO 15-20 IN. LBS.

Z_____ DUE DATE_____

VERIFY CSR-242 TQV:_____

TQWN:_____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

CAUTION

THE G070-005911 PLUG MUST
HAVE LUBRICANT APPLIED
PRIOR TO INSTALLATION TO
PREVENT GALLING.

E1C I/F SECURING

11-057 CMPS OMT0 PLUG

OK TO INSTALL QW: _____

IF ENGINE IS REMOVED AND TEST PLATE IS
INSTALLED, LUBRICATE AND INSTALL 45-11333
GLAND NUT WITH 45-11340 PLUG ON E1C
G070-005904-001 GH2 PRESS ORB/SSME
INTERFACE PLATE. TORQUE TO 264-336 IN. LBS.

Z _____ DUE DATE _____

VERIFY CSR-242 TQV: _____

TQW: _____

NOT PERFORMED _____

E2L I/F SECURING

11-058 CMPS OMT0 PLUG

OK TO INSTALL QW: _____

IF ENGINE IS REMOVED AND TEST PLATE IS INSTALLED,
LUBRICATE AND INSTALL 45-11333 GLAND NUT WITH
45-11340 PLUG ON E2L G070-005904-001 GH2
PRESS ORB/SSME INTERFACE PLATE. TORQUE TO
264-336 IN. LBS.

Z _____ DUE DATE _____

VERIFY CSR-242 TQV: _____

TQW: _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

E3R I/F SECURING

11-059 CMPS OMT0 PLUG

OK TO INSTALL QW: _____

IF ENGINE IS REMOVED AND TEST PLATE IS INSTALLED,
LUBRICATE AND INSTALL 45-11333 GLAND NUT WITH
45-11340 PLUG ON E3R G070-005904-001 GH2
PRESS ORB/SSME INTERFACE PLATE. TORQUE TO
264-336 IN. LBS.

Z _____ DUE DATE _____

VERIFY CSR-242 TQV: _____

TQW: _____

NOT PERFORMED _____

GH2 SYSTEM SECURING

11-060 CMPS RTH2 S70-0695-8

A83066 SUPPLY SOV - CLOSE (CW)

A83070 VENT - OPEN (CCW)

A83115 REG - FULL DECREASE (CCW)

VERIFY A83143 GAGE IND 0 PSI.

A83070 VENT - CLOSE (CW)

A83145 SUPPLY/VENT - CLOSE (CW)

T: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

RG001505 THROAT PLUG REMOVAL

11-061 OMT1

REMOVE RG001505 THROAT PLUG IF INSTALLED AND NO LONGER REQUIRED:

1. WHILE HOLDING SUPPORT, REMOVE NUT/WASHER THEN CAREFULLY REMOVE SUPPORT FROM THRUST CHAMBER.
2. CAREFULLY PUSH PLUG HALVES INTO COMBUSTION ZONE AS REQUIRED TO OBTAIN ACCESS TO SEAL.
3. REMOVE PIN SECURING PLUG HALVES TOGETHER.
4. CAREFULLY SEPARATE PLUG HALVES. WHILE HOLDING PLUG HALF WITH SEAL, REMOVE SECOND PLUG HALF, THEN REMOVE PLUG HALF WITH SEAL.

E1C

E2L

E3R

TQV: _____

NOT
PERF _____

11-062

CMPS CV21, CV22, CV23 INTERNAL LEAK CHECK COMPLETE.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
12-000			LV52 GH2 VENT SOL FLOW PATH VERIFICATION - CMPS, OMT0, RTH2, OQCV, AND NASA QC	

NOTE

THIS OPERATION PERFORMED ONLY IF REQUIRED BY EFFECTIVITY/FLIGHT AND/OR VEHICLE. REF 1.7 SPECIAL INSTRUCTIONS FOR NOT PERFORMED DEFINITION.

EFFECTIVITY: (REF SECTION 1.8)

NOTE

STEPS AND SUBSTEPS WITHIN THIS SEQUENCE MAY BE WORKED OUT OF NUMERICAL ORDER AS DETERMINED BY MPS ENGINEERING.

OPERATIONS INVOLVING CRIT 1 AND/OR 1R ITEMS ARE CONTAINED IN THE FOLLOWING SEQUENCE/STEPS.

12-001	CMPS OMT0		IF INSTALLED, REMOVE G070-005861-003 TEST PLATE FROM PD5 PER JC V41-40016 - PLATE, PD5 2 IN. PREPRESS REMOVAL]]]]
--------	-----------	--	--	---------

TQV: _____

NOT PERFORMED _____

12-002	CMPS OMT0		VERIFY G070-005861-003 TEST PLATE NOT INSTALLED AT PD5.	
--------	-----------	--	---	--

TQV: _____

12-003	CMPS OMT0		VERIFY PD16 CONNECTED TO GW70-420958-002 GND HALF COUPLING, 79K10547-HE16 FLEXHOSE AND A131506 (0-2) I/F PNL PORT (SEE FIGURE 8 THRU 10).	
--------	-----------	--	---	--

T: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
12-004	CMPS	OMT0	IF INSTALLED, VERIFY TP10 HAND VALVE CLOSED (CW).	T: _____
			NOT PERFORMED	_____
12-005	CMPS	RTH2	S70-0695-8 PANEL VERIFY FOLLOWING POSITIONS: A83066 SUPPLY CLOSED A83115 REG FULL DECREASE A83068 SUPPLY SOV CLOSED A83116 REG FULL DECREASE A83070 VENT VALVE CLOSED A83065 GAGE SOV OPEN A83143 GAGE IND 0 PSIG	T: _____
12-006	CMPS	CRT	(VAE20) VERIFY A83135 LH2 F/D CLOSED A83041 F/D VENT CLOSED A83134 LH2 PREPRESS CLOSED LV52 DEENERGIZED	
12-007	CMPS	RTH2	S70-0695-8 PANEL A83066 SUPPLY SOV - SLOWLY OPEN A83145 PD16 SUPPLY VLV - OPEN A83115 REG - SLOWLY INCREASE UNTIL 150 +/- 10 PSIG INDICATED ON GAGE A83143	

TQW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
12-008	CMPS OTC	OTC *AAM	IF AFT FUSELAGE IS OCCUPIED, NOTIFY PERSONNEL IN AFT FUSELAGE THAT GH2 PRESSURIZATION MANIFOLD WILL BE PRESSURIZED WITH GHE AND FLOW WILL BE AUDIBLE.	
				T: _____ NOT PERFORMED _____
12-009	CMPS	OMTO	VERIFY LV52 OUTLET TUBE AT PD5 DISC IS OPEN TO ALLOW FLOW VERIFICATION.	

NOTE

THE FOLLOWING STEP WILL ENERGIZE LV52 AND SUPPLY PRESSURE TO VERIFY FLOW OUT OF LV52 OUTLET TUBE. OMTO SHOULD NOTIFY CMPS AS SOON AS FLOW VERIFICATION IS ACCOMPLISHED.

12-010	CMPS		CURSOR CNTL (VAE20) A83134 LH2 PREPRESS - OPEN VERIFY PD5 DISC PRESSURE IND BETWEEN 100-425 PSIA RECORD _____ PSIA 100 - 425 LV52 LH2 PRESSURIZATION VENT VLV - ENERGIZE	
12-011	CMPS	OMTO	VERIFY AUDIBLE FLOW OUT OF LV52 OUTLET TUBE AT PD5 DISC. OMRSD V41BZ0.220	

TQWN: _____

12-012	CMPS		CUSRROR CNTL (VAE20) LV52 LH2 PRESSURIZATION VENT VLV - DEENERGIZE A83134 LH2 PREPRESS - CLOSE	
--------	------	--	--	--

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
12-013	CMPS	RTH2	S70-0695-8 PANEL A83066 SUPPLY SOV - CLOSE A83070 VENT VLV - OPEN, WHEN VENTING CEASES, CLOSE A83115 REG - FULL DECREASE VERIFY A83143 GAGE IND 0 PSIG. A83145 SOV - CLOSE	
12-014	CMPS		LV52 GH2 VENT SOL FLOW PATH VERIFICATION COMPLETE.	T: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
13-000			GH2 PREPRESS SYSTEM PRESSURIZATION (OPF) (CONTINGENCY)	

NOTE

THIS IS A MULTIPLE RUN SEQUENCE. BUYOFFS ARE TO BE PERFORMED ON A COPY OF THIS SEQUENCE AND ATTACHED TO THIS OMI AT CALLING SEQ/STEP.

THIS SEQUENCE MAY BE PERFORMED AT ANY TIME PER MPS ENGINEERING DIRECTION.

STEP/SUBSTEPS MAY BE WORKED OUT OF ORDER WITH ENGINEERING CONCURRENCE.

ENTIRE SEQUENCE NOT PERFORMED _____

13-001 CMQC RECORD SEQUENCE AND STEP THAT THIS OPERATION WAS PERFORMED AT:
SEQ _____, STEP _____
QW: _____

13-002 CMPS CONSOLE KYBD
VAE18
PERF PGM KEY - PRESS
PFK-3 KEY - PRESS (OPF)

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
13-003	CMPS		CONSOLE KYBD VAE20 PERF PGM KEY - PRESS PFK-3 KEY - PRESS (OPF)	

NOTE

PD10 AND/OR PD16 GSE ARE
REQUIRED TO BE INSTALLED.
THE FOLLOWING STEPS VERIFY
CONNECTION OF PD10 OR PD16
TO RESPECTIVE GSE.

PD10 GSE IS REQUIRED IF
PRESSURIZATION BETWEEN FLIGHT
HALF QD (PD10) AND CHECK VLV
(CV17) IS NEEDED TO SUPPORT
TESTING.

PD10 CONFIGURATION VERIFICATION

13-004 CMPS OMT0 PLATFORM 11 LEFT

IF PRESSURIZATION THRU LH2 T-0 DISC (PD10)
IS REQUIRED AND IF NOT ALREADY VERIFIED,
VERIFY THAT G070-005820 LH2 T-0 GSE QD IS
INSTALLED AT 50V41PD10 AND THAT A111596
(BAY 1/2) A512454 (BAY 3) (79K10547 HE10)
FLEXHOSE IS CONNECTED TO DISCONNECT AND TO
A105347 (0-2) I/F PANEL PORT.

TQV: _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

IF PRESSURIZATION THRU PD16 IS PERFORMED, FLEXHOSE AND QD FOR PD10 WILL ALSO BE PRESSURIZED.

PD16 CONFIGURATION VERIFICATION

13-005	CMPS	OMTO	IF PRESSURIZATION OR SECURING THRU 50V41PD16 WILL BE PERFORMED, VERIFY GW70-420958-002 GND HALF COUPLING IS INSTALLED TO FLT HALF 50V41PD16. VERIFY 79K10547-HE16 FLEXHOSE CONNECTED TO PD16 AND TO A131506 (0-2) I/F PNL PORT.	
--------	------	------	---	--

TQV: _____

NOT PERFORMED _____

TP10 CONFIGURATION VERIFICATION

13-006	CMPS	OMTO	IF HANDVALVE IS INSTALLED AT 50V41TP10, VERIFY H/V CLOSED (CW).	
--------	------	------	---	--

TQV: _____

NOT PERFORMED _____

LH2 ORB/ET 2-INCH DISC

13-007	CMPS	OMTO	IF MPS TEST PLATE IS INSTALLED AT PD5 GH2 2 IN. DISCONNECT, VERIFY SECURED AS FOLLOWS:	
--------	------	------	--	--

- IF FLIGHT HALF POPPET IS REQUIRED OPEN DURING PRESSURIZATION, VERIFY BOTH TEST PLATE PORTS CAPPED OR PLUGGED.

NOT PERFORMED _____

SS1

- IF FLIGHT HALF POPPET IS NOT REQUIRED OPEN, TURN POPPET ACTUATOR BOLT FULL (CCW).

NOT PERFORMED _____

SS2

TQV: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

13-008	CMPS	RTH2	S70-0695-8 PANEL	
--------	------	------	------------------	--

IF A83048 PANEL INLET SUPPLY VLV IS CLOSED:

- A83049 VENT VLV - CLOSE (CW)
- A83062 VENT VLV - CLOSE (CW)
- A83051 SUPPLY SOV - CLOSE (CW)
- A83053 SUPPLY SOV - CLOSE (CW)
- A83054 SUPPLY SOV - CLOSE (CW)
- A83066 SUPPLY SOV - CLOSE (CW)
- A83063 SUPPLY SOV - CLOSE (CW)
- A83050 GAGE SOV - OPEN (CCW)
- A83048 PANEL INLET - SLOWLY OPEN (CCW)

VERIFY A83097 GAGE INDICATES
3000-6000 PSIG

T: _____

NOT PERFORMED

13-009	CMPS		CRT (VAE20)	
--------	------	--	-------------	--

VERIFY

- A83134 LH2 PREPRESS SUPPLY SOV CLOSED
- A83041 LH2 FILL AND DRAIN LINE VENT CLOSED
- LV52 DEENERGIZED

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

NOTE

PERFORM NEXT STEP IF PANEL
LEG IS SECURED, A83066 VLV
IS CLOSED AND/OR GAGE A83143
INDICATED 0 PSIG.

13-010 CMPS RTH2 S70-0695-8 PANEL

A83066 SUPPLY SOV - CLOSE (CW)
A83115 REG - FULL DECREASE (CCW)
A83068 SUPPLY SOV - CLOSE (CW)
A83065 GAGE SOV - OPEN (CCW)

VERIFY A83143 GAGE IND 0 PSIG

A83070 VENT - CLOSE (CW)
A83145 VENT - CLOSE (CW)
A83066 SUPPLY SOV - SLOWLY OPEN (CCW)

T: _____

NOT PERFORMED

13-011 CMPS RTH2 S70-0695-8 PANEL

IF PRESSURIZATION THRU PD16 REQUIRED:

A83145 - PD16 SUPPLY VLV - OPEN (CCW)

T: _____

NOT PERFORMED

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

GH2 SYSTEM PRESSURIZATION

WARNING

GH2 SYSTEM WILL BE PRESSURIZED WITH HELIUM. FLOW WILL BE AUDIBLE TO PERSONNEL IN AFT AND AT LH2 T-0.

13-012	CMPS OTC OTC *AAM		IF AFT FUSELAGE IS OCCUPIED, NOTIFY PERSONNEL IN AFT FUSELAGE THAT GH2 PRESSURIZATION MANIFOLD WILL BE PRESSURIZED WITH GHE, FLOW WILL BE AUDIBLE.	
--------	----------------------	--	--	--

T: _____

NOT PERFORMED

13-013	CMPS		CURSOR CNTL (VAE18) A83134 LH2 PREPRESS SUPPLY SOV - OPEN	
--------	------	--	--	--

13-014	CMPS RTH2		S70-0695-8 PANEL (12E) A83115 REG - INCREASE (CW) TO INDICATE 400+/-25 PSIG ON GAGE A83143.	
--------	-----------	--	--	--

TQW: _____

13-015	CMPS		CRT (VAE20) VERIFY GH2 PRESS SYSTEM PRESSURE IS 400 +/- 25 PSIG.	
--------	------	--	---	--

RECORD: GH2 PRESS _____ PSIG

LH2 MANIF PRESS _____ PSIG

13-016	CMPS		GH2 PREPRESS SYSTEM PRESSURIZATION (OPF) COMPLETE.	
--------	------	--	--	--

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
14-000			GH2 PREPRESS SYSTEM VENTING THRU PD16 (OPF) (CONTINGENCY)	

NOTE

THIS SEQUENCE MAY BE PERFORMED AT ANY TIME PER MPS ENGINEERING DIRECTION.

ENTIRE SEQUENCE NOT PERFORMED _____

NOTE

THIS IS A MULTIPLE RUN SEQUENCE. BUYOFFS ARE TO BE PERFORMED ON A COPY OF THIS SEQUENCE AND ATTACHED TO THIS OMI AT CALLING SEQ/STEP.

STEP/SUBSTEPS MAY BE WORKED OUT OF ORDER WITH ENGINEERING CONCURRENCE.

14-001 CMQC RECORD SEQUENCE AND STEP THAT THIS OPERATION WAS PERFORMED AT:

SEQ _____, STEP _____

QW: _____

14-002 CMPS OMT0 IF NOT INSTALLED, PERFORM "PD16 HARDWARE INSTALLATION (OPF)" PER OMI V1171VL1.

TQ: _____

NOT PERFORMED _____

14-003 CMPS CURSOR CNTL (VAE20)
A83134 LH2 PREPRESS SUPPLY SOV - CLOSE

14-004 CMPS RTH2 S70-0695-8 PANEL

A83070 VENT - OPEN (CCW)
A83145 VENT - OPEN (CCW)

T: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
14-005	CMPS		CRT (VAE20) V41P1490A1 VERIFY ORBITER GH2 SYSTEM VENTS TO AMBIENT.	
14-006	CMPS RTH2		S70-0695-8 PANEL A83145 VENT - CLOSE (CW) A83070 VENT - CLOSE (CW)	T: _____
NOTE				
DO NOT PERFORM NEXT STEP IF LH2 FILL/DRAIN SYSTEM PRESSURIZATION STILL REQUIRED.				
14-007	CMPS RTH2		S70-0695-8 PANEL A83066 SUPPLY SOV - CLOSE (CW) VERIFY A83068 SUPPLY SOV CLOSED (CW) A83115 REG - FULL DECREASE (CCW) A83143 GAGE IND 0 PSIG	T: _____
			NOT PERFORMED	_____
14-008	CMPS		IF NO LONGER REQUIRED: TERMINATE PGM (VAE20)	
			NOT PERFORMED	_____
14-009	CMPS		GH2 PREPRESS SYSTEM VENTING THRU PD16 (OPF) COMPLETE.	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
15-000			GH2 PREPRESS SYSTEM VENTING THRU PD5/LV52 (OPF) (CONTINGENCY)	

NOTE

THIS SEQUENCE MAY BE PERFORMED AT ANY TIME PER MPS ENGINEERING DIRECTION.

ENTIRE SEQUENCE NOT PERFORMED

NOTE

THIS IS A MULTIPLE RUN SEQUENCE. BUYOFFS ARE TO BE PERFORMED ON A COPY OF THIS SEQUENCE AND ATTACHED TO THIS OMI AT CALLING SEQ/STEP.

STEP/SUBSTEPS MAY BE WORKED OUT OF ORDER WITH ENGINEERING CONCURRENCE.

15-001 CMQC RECORD SEQUENCE AND STEP THAT THIS OPERATION WAS PERFORMED AT:
 SEQ _____, STEP _____

QW: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

CAUTION

PERFORM VENTING OF GH2 PRESS SYSTEM THRU PD5/LV52, ONLY IF VENTING THRU PD16 IS NOT POSSIBLE. (INCREASE IN OPF HELIUM BACKGROUND MAY IMPACT OTHER TESTING.)

15-002 CMPS CRT (VAE20)

VERIFY

A83134 LH2 PREPRESS SUPPLY SOV CLOSED
A83041 LH2 FILL AND DRAIN LINE VENT CLOSED
LV52 DEENERGIZED

NOTE

DO NOT PERFORM NEXT STEP IF LH2 FILL/DRAIN SYSTEM PRESSURIZATION STILL REQUIRED.

15-003 CMPS RTH2 S70-0695-8 PANEL

A83066 SUPPLY SOV - CLOSE (CW)

VERIFY A83068 SUPPLY SOV CLOSED (CW)

A83115 REG - FULL DECREASE (CCW)
A83143 GAGE IND 0 PSIG

T: _____

NOT PERFORMED _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
----- PD5 CONFIGURATION VERIFICATION -----				
15-004	CMPS	OMTO	<p>IF NOT PREVIOUSLY VERIFIED, REPORT CONFIGURATION OF MPS 2 IN. GH2 DISCONNECT PD5.</p> <ol style="list-style-type: none"> 1. TEST PLATE INSTALLED WITH POPPET ACTUATOR FULL (CW) - FLT HALF OPEN. 2. TEST PLATE INSTALLED WITH POPPET ACTUATOR FULL (CCW) - FLT HALF CLOSED. 3. NO TEST PLATE INSTALLED. <p>RECORD CONFIGURATION NO. _____</p>	<p>TQV: _____</p> <p style="text-align: center;">NOT PERFORMED</p>
15-005	CMPS	OMTO	<p>IF PD5 TEST PLATE IS INSTALLED WITH POPPET ACTUATOR FULL (CW), TURN POPPET ACTUATOR FULL (CCW) TO CLOSE FLT HALF POPPET.</p>	<p>TQV: _____</p> <p style="text-align: center;">NOT PERFORMED</p>
15-006	CMPS	OMTO	<p>IF PD5 TEST PLATE IS INSTALLED WITH POPPET ACTUATOR FULL (CCW) OR IF PREVIOUS STEP WAS PERFORMED AND TETHERED CAP IS INSTALLED, SLOWLY REMOVE TETHERED CAP FROM PLATE TEST PORT. A SMALL VOLUME OF HELIUM MAY VENT DURING CAP REMOVAL.</p>	<p>TQV: _____</p> <p style="text-align: center;">NOT PERFORMED</p>
15-007	CMPS	OMTO	<p>IF PD5 TEST PLATE IS NOT INSTALLED, REMOVE ACLAR FROM THE PD5 DISCONNECT TO PERMIT VENTING.</p>	<p>TQV: _____</p> <p style="text-align: center;">NOT PERFORMED</p>
15-008	CMPS	OTC OTC *PAD	<p>NOTIFY PERSONNEL TO CLEAR AREA AROUND LH2 ORBITER/ET DISCONNECT. HELIUM WILL BE VENTED THRU PD5 AND THERE WILL BE AN AUDIBLE FLOW.</p>	<p>TQV: _____</p> <p style="text-align: center;">NOT PERFORMED</p>

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
15-009	NTD PA		ATTENTION IN OPF BAY ____: LOUD VENTING WILL OCCUR IN AREA OF LH2 17 IN. DISC.	
15-010	CMPS		CURSOR CNTL (VAE20) LV52 - ENERGIZE	
15-011	CMPS		VERIFY GH2 PRESSURE DECAYS TO AMBIENT.	
15-012	CMPS		CURSOR CNTL (VAE20) LV52 - DEENERGIZE	
15-013	CMPS		IF NO LONGER REQUIRED: TERMINATE PGM (VAE20)	
			NOT PERFORMED	_____
15-014	CMPS	OMTO	IF TEST CAP WAS REMOVED TO PERMIT VENTING, INSTALL CAP ONTO PD5 TEST PLATE TEST PORT WRENCH TIGHT AND CONFIGURE POPPET AS NEEDED FOR FURTHER TESTING AS DIRECTED BY CMPS. 1. POPPET ACTUATOR FULL (CW)	
			NOT PERFORMED	_____
				SS1
			2. POPPET ACTUATOR FULL (CCW)	
			NOT PERFORMED	_____
				SS2
				TQW: _____
			ENTIRE STEP NOT PERFORMED	_____
15-015	CMPS	OMTO	IF PD5 TEST PLATE WAS NOT INSTALLED AND ACLAR WAS REMOVED TO PERMIT VENTING, REINSTALL ACLAR AND TAPE OVER PD5 DISCONNECT OPENING. MAINTAIN SYSTEM CLEANLINESS (REF MA0110-311).	
				TQV: _____
			NOT PERFORMED	_____
15-016	CMPS		GH2 PREPRESS SYSTEM VENTING THRU PD5/LV52 (OPF) COMPLETE.	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
16-000			TEST SUPORT TERMINATION	
16-001	CMPS	OTC	V1009.007 COMPLETE.	
16-002	OTC NTD 232	NTD STM LPS	TEST COMPLETE FOR V1009.007. RELEASE ALL SUPPORT.	
16-003	STM 111 GYCC	GYCC GYCR 117	TERMINATE VOICE RECORDING FOR V1009.007. TEST COMPLETE. SUPPORT RELEASED.	
16-004	CMPS	OTC	TEST SUPPORT TERMINATION COMPLETE.	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

SECTION V

POST OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
17-000			POST OPERATION INSTRUCTIONS - ORBITER -----	
17-001			POST OPERATION INSTRUCTION 1 - MPS GH2 ----- SYSTEM DATA REVIEW -----	
17-002			MPS ENGINEER - RECORD/COPY ALL DATA FROM APPENDICES TO SUPPORT MPS ENGINEERING DATA FILE. COPY ALL PERMANENT DEVIATIONS AND PEN AND INK CHANGES. MPSE _____ DATE _____	
17-003			ORBITER POST OPERATION INSTRUCTION 1 - MPS LH2 SYSTEM DATA REVIEW COMPLETE.	

QV: _____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

POST OPERATION INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX A

GH2 SYSTEM COMPONENTS - INTERNAL LK CKS

DATA SHEET A-1 - MPS COMPONENT SEAT INTERNAL LEAK CHECKS

ITEM DESCRIPTION	MAX LEAK ALLOWED (SCIMS)	TUBE SCALE READING	LEAK RATE (SCIMS)	FLOWMETER TUBE Z NO.	DUE DATE
CV17	15	_____	_____	_____	_____
					TQW: _____]
				NOT PERFORMED	_____]
PD10	10	_____	_____	_____	_____
					TQW: _____]
				NOT PERFORMED	_____]
CV24	15	_____	_____	_____	_____
					TQW: _____]
				NOT PERFORMED	_____]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX A

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX A

DATA SHEET A-2 - CHECK VALVE REVERSE LEAKAGE (INTERVAL REQUIREMENTS)

NOTE

CV21,22,23 - MAX ALLOWABLE
LEAKAGE IS 1000 SCIM TOTAL
FOR FWD AND AFT CHECK VALVES.

REF DESIGN -----	MAX ALLOWABLE (SCIM) -----	LEAK RATE (SCIM) -----	MANIF PRESS (PSIA) -----	FLWMTR TUBE Z NO. -----	FLWMTR SCALE READING -----	DUE DATE -----
CV21 (FWD)	1000	_____	_____	_____	_____	_____
						TQW: _____
				NOT PERFORMED		_____
CV22 (FWD)	1000	_____	_____	_____	_____	_____
						TQW: _____
				NOT PERFORMED		_____
CV23 (FWD)	1000	_____	_____	_____	_____	_____
						TQW: _____
				NOT PERFORMED		_____
CV21 (AFT)	1000	_____	_____	_____	_____	_____
						TQW: _____
				NOT PERFORMED		_____
CV22 (AFT)	1000	_____	_____	_____	_____	_____
						TQW: _____
				NOT PERFORMED		_____
CV23 (AFT)	1000	_____	_____	_____	_____	_____
						TQW: _____
				NOT PERFORMED		_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX A

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - GH2 PRESSURIZATION SYSTEM (HIGH PRESSURE) JOINT
LIST AND RESULTS

EFFECTIVITY: (REF SECTION 1.8)

WARNING

FACESHIELDS OR GOGGLES SHALL
BE WORN BY PERSONNEL
PERFORMING SOAP LEAK CHECKS.

NOTE

ACCEPTANCE CRITERIA FOR
LEAK CHECKS USING MASS
SPECTROMETER AND LEAK
CHECK OF FOAMED JOINTS ARE
DEFINED IN 1.7 SPECIAL
INSTRUCTIONS.

NON-FOAMED THREADED, BRAZED
OR WELDED FITTINGS MAY BE
LEAK CHECKED USING SOAP
SOLUTION. ENTER "SOAP" UNDER
METHOD COLUMN IF LEAK DETECTION
SOAP SOLUTION METHOD IS BEING
USED. ENTER N/A FOR SENS.
FACTOR, BACK GROUND AND SCALE
READING.

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 (CONTINUED)

NOTE

GH2 HIGH PRESSURE SYSTEM
LEAK CHECKS ARE FROM
SSME I/F TO INLET OF FCV.

OV-105 UNIQUE JOINTS
ARE SHOW IN BRACKETS.

EIC GH2 HIGH PRESSURE SYSTEM - SSME I/F TO FCV

JOINT -----	DESCRIPTION -----	FIG NO. -----
CV21A	WELD ON CV21 BODY OUTLET	7
F204	ME284-0479-0012 ASSY BRAZE JOINT AT V070-415410-001 TUBE	7
F205	V070-415410-001 TUBE BRAZE JOINT AT V070-415448-001 FITTING	5
F206	SEAL AT MT11 TRANSDUCER ON V070-415448-001 FITTING	5
F207	V070-415448-001 FITTING BRAZE JOINT AT V070-415410-002 TUBE	5
F208	V070-415410-002 TUBE BRAZE JOINT AT V070-415410-023 TUBE	4
F238 (F228)	V070-415410-023 TUBE BRAZE JOINT AT LV56	14

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

JOINT -----	DESCRIPTION -----	FIG NO. -----
LV56A (F261)	O-RING BETWEEN SOLENOID VALVE HOUSING AND LV56 BODY	15
LV56B	WELD ON FCV INLET MEASURED THRU VENT PORT	15
	E2L - GH2 HIGH PRESSURE SYSTEM -----	
CV22A	WELD ON CV22 BODY OUTLET	7
F213	ME284-0479-0012 ASSY BRAZE JOINT AT V070-415410-021 TUBE	7
F213A	MR JOINT BETWEEN CV22 AND TEE (OV-102 ONLY, NOT SHOWN IN FIGURE)	7
F214	V070-415448-001 ASSY INLET TO TEE	6
F215	V070-415448-001 ASSY SEAL AT MT24 TRANSDUCER	6
F216	V070-415448-001 ASSY OUTLET BRAZE JOINT AT V070-415410-021 TUBE	6

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

JOINT -----	DESCRIPTION -----	FIG NO. -----
F236 (F226)	V070-415410-024 TUBE ASSY BRAZE JOINT AT LV57	14
LV57A (F262)	O-RING BETWEEN SOLENOID VALVE HOUSING AND LV57 BODY	15
LV57B	WELD ON FCV. INLET MEASURED THRU VENT PORT	15
E3R - GH2 HIGH PRESSURE SYSTEM -----		
CV23A	WELD ON CV23 BODY OUTLET	7
F220	ME284-0479-0012 ASSY BRAZE JOINT AT V070-415410-006	7
F221	V070-415410-006 TUBE BRAZE JOINT AT V070-415448-001 FITTING	6
F222	V070-415448-001 FITTING SEAL AT TRANSDUCER	6
F223	V070-415448-001 FITTING BRAZE JOINT AT V070-415410-007 TUBE	6

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

JOINT -----	DESCRIPTION -----	FIG NO. -----
F224	V070-415410-007 TUBE BRAZE JOINT AT V070-415410-019 TUBE (OV-103 & SUBS) V070-415410-008 TUBE (OV-102 ONLY)	4
F225	V070-415410-008 TUBE (OV-102 ONLY) V070-415410-019 TUBE (OV-103 & SUBS) BRAZE JOINT AT V070-415410-022 TUBE	4
F237 (F227)	V070-415410-022 TUBE BRAZE JOINT AT LV58	14
LV58A (F263)	O-RING BETWEEN SOLENOID VALVE HOUSING AND LV58 BODY	15
LV58B	WELD ON FCV INLET MEASURED THRU VENT PORT ON INLET PORT	15

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

LOW PRESSURE GH2 SYSTEM

LH2 (T-0) TO FCV - AND ORB/ET

JOINT -----	DESCRIPTION -----	FIG NO. -----	
F226	BRAZE JOINT AT (PD10) V070-415410-009 TUBE	4]
F227	V070-415410-009 TUBE BRAZE JOINT AT (TP10) V070-415446-001 ASSY	4]
F228	ME261-0033-0104 K-SEAL AT TP10	4]
F229	V070-415446-001 ASSY BRAZE JOINT AT (TP10) V070-415410-010 TUBE	4]
F230	V070-415410-010 TUBE BRAZE JOINT AT V070-415410-017 TUBE	4]
F231	V070-415410-017 TUBE BRAZE JOINT AT CV17 INLET	50R13]
CV17A	OUTLET WELD ON CV17	5	
F232	CV17 (OUTLET) BRAZE JOINT AT V070-415442-001 TEE ASSY	50R13]
F233	V070-415442-001 ASSY SEAL AT PD16 DISCONNECT	50R13]

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

JOINT -----	DESCRIPTION -----	FIG NO. -----	
F233A	EXTERNAL WELD ON 50V41PD16 FLIGHT HALF DISCONNECT	5]
F234	V070-415442-002 TEE ASSY BRAZE JOINT AT V070-415410-012 TUBE	5]
F235	V070-415410-012 TUBE BRAZE JOINT AT V070-415420-001 MANIF ASSY	13	
F235A	V070-415420 MANIF ASSY BRAZE JOINT (REF UPPER TUBE TO LV58)	13	
F235B	V070-415420 MANIF ASSY BRAZE JOINT (REF LOWER TUBE TO LV56)	13	
F235C	V070-415420 MANIF ASSY BRAZE JOINT (REF LOWER TUBE TO LV57)	13	
F235D	V070-415420 ASSY BRAZE JOINT (REF JOINT AT LV56)	13	
F235E	V070-415420 ASSY BRAZE JOINT AT LV58	13	
LV56C	OUTLET WELD ON FCV TO TUBE	15	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

<u>JOINT</u>	<u>DESCRIPTION</u>	<u>FIG NO.</u>
F235F	V070-415420 ASSY BRAZE JOINT AT LV57	13
LV58C	OUTLET WELD ON FCV TO TUBE	15
LV57C	OUTLET WELD ON FCV TO TUBE	15
F239	V070-415420-001 ASSY WELD AT 2 IN. LINE FLANGE.	13
F240	V070-415425-001 ASSY SEAL AT TRANSDUCER (OV-102 ONLY) (V070-415440)	5

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

<u>JOINT</u>	<u>DESCRIPTION</u>	<u>FIG NO.</u>
F241	ME273-0115-0004 CONNECTOR TO BOSS IN LH2 PRESS LINE AT PD5	1
F242	ME273-0144-0420 ELBOW TO ME273-0115-0004 CONNECTOR	1
F243	V070-415542-003 TUBE TO ME273-0144-0420 ELBOW	1
F244	V070-415542-003 TUBE TO ME273-0197-0002 TEE	1
F245	ME273-0197-0002 TEE TO ME273-0115-0006 CONNECTOR AT LV52 INLET	1
F246	ME273-0115-0006 CONNECTOR TO LV52 INLET	1
LV52A	BODY CONNECTION ON LV52	1

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	CV21A	F204	F205	
SYSTEM PRESSURE (PSIA)	_____	_____	_____	
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)]
MACHINE S/N	_____	_____	_____	
PERM RATIO - PR (600 MAX)	_____	_____	_____	
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____	
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____	
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____	
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____	
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____]
MAX METER READING	_____	_____	_____	
CORRECTED LEAK RATE (CLR)	_____	_____	_____]
PASS/FAIL	_____	_____	_____	
TIME	_____	_____	_____]
VFY CSR 085/086	TQV: _____	_____	_____	
MACHINE OPERATOR	T: _____	_____	_____	
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____	
INSPECTOR	QW: _____	_____	_____	
ENGINEER	_____	_____	_____]
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____]
JOINT NOT PERFORMED	_____	_____	_____	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	F206	F207	F208
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 ⁽⁻⁷⁾	1 X 10 ⁽⁻⁷⁾	1 X 10 ⁽⁻⁷⁾
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 ⁻⁵ MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	F238	LV56A	LV56B
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	CV22A	F213	F213A
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	F214	F215	F216
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	F236	LV57A	LV57B
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (<= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	CV23A	F220	F221
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	F222	F223	F224
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	F225	F237	LV58A
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	LV58B	F226	F227
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	F228	F229	F230
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	F231	CV17A	F232
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	F235	F235A	F235B
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	LV56C	F235F	LV58C
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	F241	F242
SYSTEM PRESSURE (PSIA)	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____
MAX METER READING	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____
PASS/FAIL	_____	_____
TIME	_____	_____
VFY CSR 085/086	TQV: _____	_____
MACHINE OPERATOR	T: _____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____
INSPECTOR	QW: _____	_____
ENGINEER	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____
JOINT NOT PERFORMED	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-1 - JOINT LIST AND RESULTS

JOINT NO.	BASELINE DATA	BASELINE DATA	BASELINE DATA
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-2 - GH2 2 IN. LINE GIMBAL JTS - MASS SPEC LEAK CHECK
JOINT LIST AND RESULTS

ENTIRE DATA SHEET NOT PERFORMED _____

JOINT -----	DESCRIPTION -----	FIG NO. -----
FGM1 TYPE I (LOWER)	LOWER GIMBAL JOINT BELLOWS	17
LW1	LOWER WELD	17
UW1	UPPER WELD	17
FGM2 TYPE I (MID)	MID GIMBAL JOINT BELLOWS	17
LW2	LOWER WELD	17
UW2	UPPER WELD	17
FGM3 TYPE I (AFT)	AFT GIMBAL JOINT BELLOWS	17
LW3	LOWER WELD	17
UW3	UPPER WELD	17

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-2 - JOINT LIST AND RESULTS

JOINT NO.	FGM1	LW1	UW1
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-2 - JOINT LIST AND RESULTS

JOINT NO.	FGM2	LW2	UW2
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-2 - JOINT LIST AND RESULTS

JOINT NO.	FGM3	LW3	UW3
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-3 GH2 PRESSURIZATION SYSTEM BUBBLE SOAP LEAK CHECKS
JOINT LIST AND RESULTS

NOTE

TEST OR FERRY PLATE MUST BE
REMOVED FROM PD5 TO PERFORM
THE FOLLOWING STEP. PERFORM
LEAK CHECK FROM ET SIDE OF
UMBILICAL.

FPD5 FLANGE SEAL BETWEEN PD5 CAP ASSEMBLY AND DISCONNECT BODY
HELD IN PLACE BY 18 ALLEN HEAD SCREWS. (SEE FIGURE 18).

NOTE

THE FOLLOWING NINE JTS ARE
DOWNSTREAM OF LV52 AND MUST
BE LEAK CHECKED WITH TEST
PLATE INSTALLED AND PD5 POPPET
OPEN. SEE FIGURE 1 VIEW D-D.

JOINT -----	DESCRIPTION -----	FIG NO. -----
F247	ME273-0115-0006 CONNECTOR TO LV52 OUTLET	1
F248	ME273-0199 ELBOW ME273-0115-0006 CONNECTOR AT LV52 OUTLET	1
F249	V070-415542-004 LINE TO ME273-0199-0006 ELBOW AT LV52 OUTLET	1
F250	V070-415502-004 LINE TO MD273-0030-0420 ELBOW	1
F251	MD273-0030-0420 ELBOW TO V070-415542-015 LINE	1
F252	V070-415542-015 LINE TO MD273-0030-0420 ELBOW AT PD5	1

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

JOINT -----	DESCRIPTION -----	FIG NO. -----
F253	MD273-0030-0420 ELBOW TO ME273-0127-0420 FTG AT PD5	1
F254	ME273-0127-0420 FTG TO ME273-0115-0004 CONNECTOR AT PD5	1
F255	ME273-0115-0004 CONNECTOR/ ME261-0033-0104 K-SEAL TO BOSS	1

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-3 - JOINT LIST AND RESULTS

JOINT NO.	FPD5	F247	F248
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (< / = 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-3 - JOINT LIST AND RESULTS

JOINT NO.	F249	F250	F251
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-3 - JOINT LIST AND RESULTS

JOINT NO.	F252	F253	F254
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-4 - GH2 LEAK CHECKS AT ORB/ET DISCONNECT

JOINT -----	DESCRIPTION -----	FIG NO. -----
F337A TYPE II	V070-415523-022 TUBE BRAZE JOINT AT CV24 OUTLET ELBOW	3A OR 3B
F338A TYPE II	V070-415523-022 TUBE BRAZE JOINT AT TEE N/A FOR OV-105	3A
F339 TYPE II	V070-415523-021 TUBE BRAZE JOINT AT TEE N/A FOR OV-105	3A
F340 TYPE II	BRAZE JOINT BETWEEN ELBOW AND TEE AT MT44, DELTA-P X-DUCER PRESSURE PORT N/A FOR OV-105	3A
F341 (FOAMED)	MECHANICAL FITTING AT MT44 DELTA-P XDUCER PRESSURE PORT N/A FOR OV-105	3A
F343B TYPE II (FOAMED)	MECHANICAL FITTING AT CV24 OUTLET	3A OR 3B
F361 TYPE II	V070-415523-021 TUBE BRAZE JOINT AT MT47, GH2 DISC PRESSURE X-DUCER	3A OR 3B
F363 TYPE II	50V41TM47 GH2 DISC PRESSURE X-DUCER XDUCER SEAL	3A OR 3B

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

JOINT -----	DESCRIPTION -----	FIG NO. -----
F256 TYPE I	ME273-0197-0002 TEE V070-415542-002 TUBE	1
F257	V070-415542-003 TUBE TO V070-415542-014	3A OR 3B
F258	V070-415542-014 TUBE TO V070-415533-001	3A OR 3B

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-4 - JOINT LIST AND RESULTS

JOINT NO.	F337A	F338A	F339
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-4 - JOINT LIST AND RESULTS

JOINT NO.	F340	F341	F343B
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-4 - JOINT LIST AND RESULTS

JOINT NO.	F361	F363	F256
SYSTEM PRESSURE (PSIA)	_____	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____	_____
MAX METER READING	_____	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____	_____
PASS/FAIL	_____	_____	_____
TIME	_____	_____	_____
VFY CSR 085/086	TQV: _____	_____	_____
MACHINE OPERATOR	T: _____	_____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____	_____
INSPECTOR	QW: _____	_____	_____
ENGINEER	_____	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____	_____
JOINT NOT PERFORMED	_____	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX B

DATA SHEET B-4 - JOINT LIST AND RESULTS

JOINT NO.	F527	F258
SYSTEM PRESSURE (PSIA)	_____	_____
SPECIFIC LEAK RATE	1 X 10 (-7)	1 X 10 (-7)
MACHINE S/N	_____	_____
PERM RATIO - PR (600 MAX)	_____	_____
RESPONSE TIME - RT (20 SEC MAX)	_____	_____
FLOW RATE - FR (1.25 - 1.75 SCCS)	_____	_____
PRESSURE - PIII (< 8 X 10 -5 MBAR)	_____	_____
EMISS CURRENT - IE (0.5 - 1.5 MA)	_____	_____
BK GRND READING (</= 0.8 X SLR)	_____	_____
MAX METER READING	_____	_____
CORRECTED LEAK RATE (CLR)	_____	_____
PASS/FAIL	_____	_____
TIME	_____	_____
VFY CSR 085/086	TQV: _____	_____
MACHINE OPERATOR	T: _____	_____
PROBE OPERATOR (OR BUBBLE SOAP)	T: _____	_____
INSPECTOR	QW: _____	_____
ENGINEER	_____	_____
BUBBLE SOAP LK CK (PASS/FAIL SEE NOTE)	_____	_____
JOINT NOT PERFORMED	_____	_____

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

APPENDIX Z

EMERGENCY INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
18-000			EMERGENCY SHUTDOWN -----	

NOTE

IN THE EVENT OF A LOSS OF
OIS COMMUNICATIONS, SECURE
THE OPF PNEUMATICS SYSTEMS
PER THE FOLLOWING TWO STEPS.

IN THE EVENT OF AN LPS LOSS.
NO SPECIAL EMERGENCY ACTIONS
ARE DICTATED.

18-001 RTH2 SECURE THE S70-0695-8 (0-2) PANEL AS
FOLLOWS
A83048 SUPPLY SHUTOFF VALVE - CLOSE (CW)

18-002 NOTIFY TEST CONDUCTOR OF THE PROBLEM AND
THE ACTION TAKEN.

GENERAL

18-003 INSTRUCTIONS FOR OTHER EMERGENCIES ARE
CONTAINED IN EPD S9904 (OPF).

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

EMERGENCY INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

EMERGENCY INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
19-000			EMERGENCY GH2 PRESSURIZATION SYSTEM VENTING THRU S70-0695-8 PANEL	

NOTE

IN THE EVENT OF EXCESSIVE
LEAKAGE OF HELIUM INTO
AFT FUSELAGE FROM THE MPS
GH2 PRESSURIZATION SYSTEM
SECURE/VENT SYSTEM PER
THE FOLLOWING.

19-001	CMPS		CURSOR CNTL (VAE20) A83134 LH2 PREPRESS - CLOSE	
19-002	CMPS	RTH2	S70-0695-8 PNL A83145 SUPPLY/VENT - OPEN A83070 VENT - OPEN A83115 REG - FULL DECREASE	

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

EMERGENCY INSTRUCTIONS

SEQ	CMD	RESP	DESCRIPTION	VERIF.
-----	-----	------	-------------	--------

THIS PAGE INTENTIONALLY BLANK

DATE: 02-25-92

OMI NO. - V1009.007
REV. - A

END OF OMI

